INFORMATION TO USERS

This reproduction was made from a copy of a document sent to us for microfilming. While the most advanced technology has been used to photograph and reproduce this document, the quality of the reproduction is heavily dependent upon the quality of the material submitted.

The following explanation of techniques is provided to help clarify markings or notations which may appear on this reproduction.

1. The sign or "target" for pages apparently lacking from the document photographed is "Missing Page(s)". If it was possible to obtain the missing page(s) or section, they are spliced into the film along with adjacent pages. This may have necessitated cutting through an image and duplicating adjacent pages to assure complete continuity.
2. When an image on the film is obliterated with a round black mark, it is an indication of either blurred copy because of movement during exposure, duplicate copy, or copyrighted materials that should not have been filmed. For blurred pages, a good image of the page can be found in the adjacent frame. If copyrighted materials were deleted, a target note will appear listing the pages in the adjacent frame.
3. When a map, drawing or chart, etc., is part of the material being photographed, a definite method of "sectioning" the material has been followed. It is customary to begin filming at the upper left hand corner of a large sheet and to continue from left to right in equal sections with small overlaps. If necessary, sectioning is continued again—beginning below the first row and continuing on until complete.
4. For illustrations that cannot be satisfactorily reproduced by xerographic means, photographic prints can be purchased at additional cost and inserted into your xerographic copy. These prints are available upon request from the Dissertations Customer Services Department.
5. Some pages in any document may have indistinct print. In all cases the best available copy has been filmed.

**University
Microfilms
International**

300 N. Zeeb Road
Ann Arbor, MI 48106

8322653

South, David Long

LABORATORY STUDIES OF FLUID FLOW THROUGH BOREHOLE SEALS

The University of Arizona

PH.D. 1983

University
Microfilms
International

300 N. Zeeb Road, Ann Arbor, MI 48106

PLEASE NOTE:

In all cases this material has been filmed in the best possible way from the available copy. Problems encountered with this document have been identified here with a check mark ✓.

1. Glossy photographs or pages ✓
2. Colored illustrations, paper or print ✓
3. Photographs with dark background ✓
4. Illustrations are poor copy _____
5. Pages with black marks, not original copy _____
6. Print shows through as there is text on both sides of page _____
7. Indistinct, broken or small print on several pages ✓
8. Print exceeds margin requirements _____
9. Tightly bound copy with print lost in spine _____
10. Computer printout pages with indistinct print _____
11. Page(s) _____ lacking when material received, and not available from school or author.
12. Page(s) _____ seem to be missing in numbering only as text follows.
13. Two pages numbered 59. Text follows.
14. Curling and wrinkled pages _____
15. Other _____

University
Microfilms
International

LABORATORY STUDIES OF FLUID FLOW
THROUGH BOREHOLE SEALS

by
David Long South

A Dissertation Submitted to the Faculty of the
DEPARTMENT OF MINING AND GEOLOGICAL ENGINEERING
In Partial Fulfillment of the Requirements
For the Degree of
DOCTOR OF PHILOSOPHY
WITH A MAJOR IN GEOLOGICAL ENGINEERING
In the Graduate College
THE UNIVERSITY OF ARIZONA

1 9 8 3

THE UNIVERSITY OF ARIZONA
GRADUATE COLLEGE

As members of the Final Examination Committee, we certify that we have read
the dissertation prepared by David Long South
entitled Laboratory Studies of Fluid Flow Through Borehole Seals

and recommend that it be accepted as fulfilling the dissertation requirement
for the Degree of Doctor of Philosophy.

Paul E. Hsu
Samuel D. Evers

5/23/83
Date

5/23/83
Date

Kulatilaka
Edward J. Nowatzki
Harman

5/23/83
Date

5-23-83
Date

5-24-83
Date

Final approval and acceptance of this dissertation is contingent upon the
candidate's submission of the final copy of the dissertation to the Graduate
College.

I hereby certify that I have read this dissertation prepared under my
direction and recommend that it be accepted as fulfilling the dissertation
requirement.

Harman
Dissertation Director

6-27-83
Date

STATEMENT BY AUTHOR

This dissertation has been submitted in partial fulfillment of requirements for an advanced degree at The University of Arizona and is deposited in the University Library to be made available to borrowers under rules of the Library.

Brief quotations from this dissertation are allowable without special permission, provided that accurate acknowledgment of source is made. Requests for permission for extended quotation from or reproduction of this manuscript in whole or in part may be granted by the head of the major department or the Dean of the Graduate College when in his judgment the proposed use of the material is in the interests of scholarship. In all other instances, however, permission must be obtained from the author.

SIGNED: David L. South

ACKNOWLEDGEMENTS

This work was for the U.S. Nuclear Regulatory Commission, initially under the auspices of the SAFER Division and now under the Division of Health, Siting, and Waste Management. The support of the Commission, and particularly our contract officer, Dr. Larry Doyle, is very much appreciated.

I would also like to thank my committee members, and especially my dissertation director, Dr. Jaak J.K. Daemen, for his help and guidance throughout this project.

The main laboratory apparatus, four radial permeameters and four constant pressure pumps were built by the Central Machine Shop, University of Arizona Instrument Shops, under the direction of Ron McLean. The quality and timeliness of this workmanship contributed greatly to this project. The assistance of Dick Van Reeth of the College of Mines Machine Shop in constructing and repairing numerous items of equipment is greatly appreciated. Scott Forbes and Mike Bosnos, of Applied Microtechnology, Inc., guided my initial venture into the world of computer monitored laboratory measurements.

Numerous student workers assisted greatly in sample preparation and equipment assembly. Carolyn Audilet, in particular, helped assemble much of the laboratory. Doug Knight, staff technician in charge of the rock mechanics laboratory, provided excellent support services.

Thanks to Mike Porter for meticulous typing and to Sue Angelon and Allison Habel for drafting.

TABLE OF CONTENTS

	<u>Page</u>
LIST OF ILLUSTRATIONS.....	viii
LIST OF TABLES.....	xii
ABSTRACT.....	xiv
CHAPTER ONE: INTRODUCTION.....	1
Borehole Sealing and Nuclear Waste Isolation.....	4
High-Level Nuclear Waste Isolation Research Efforts.....	4
Borehole Sealing Considerations.....	7
Research Objectives.....	8
CHAPTER TWO: BOREHOLE SEALING: CURRENT PRACTICE AND RECENT STUDIES.....	11
Current Methods of Borehole Sealing.....	12
Methods of Well Cementing.....	12
Safety Plugging of Oil Wells Penetrating Appalachian Coal Mines.....	19
Implications for Nuclear Waste Disposal.....	19
Borehole Sealing with Clay.....	21
Recent Studies Regarding Borehole Sealing for Nuclear Waste Isolation.....	23
The Bell Canyon Test.....	24
The Work of D'Appolonia Consulting Engineers.....	27
The 1979 Report.....	27
The 1980 Reports.....	28
The 1981 Report.....	29
The 1982 Report.....	30
Discussion.....	31
Wellbore Damage Zone Studies by Terra Tek.....	31
Research at The Pennsylvania State University.....	33
The PSU/WES Interlaboratory Study.....	38
Research at the Waterways Experiment Station.....	39
Research at Oak Ridge National Laboratory.....	40
Studies at Woodward-Clyde Consultants for the Basalt Waste Isolation Project.....	44
Information Base for Waste Repository Design.....	46
Research at the University of Arizona.....	48

TABLE OF CONTENTS--Continued

	<u>Page</u>
CHAPTER THREE: EXPERIMENTAL METHODS.....	50
Materials.....	53
Rock Types.....	53
Oracle Granite.....	53
Charcoal Granite.....	56
Catalina Granite.....	59
Sentinel Gap Basalt.....	61
Topopah Spring Tuff.....	63
Seal Materials.....	66
Cement.....	66
Clay.....	72
Experimental Apparatus.....	76
Permeameter Design.....	76
Design Details.....	80
Pump Design.....	84
Data Acquisition System.....	87
Experimental Procedure.....	89
Sample Preparation and Loading.....	89
Testing.....	90
CHAPTER FOUR: EXPERIMENTAL RESULTS.....	94
Tests on Cement Plugs.....	97
Oracle Granite.....	97
Tests with Rock Bridge in Place.....	97
Tests without Rock Bridge.....	102
Tests with Cement Plug.....	104
Experimental Procedure Modifications.....	104
Charcoal Granite.....	105
Sample CG-101.....	106
Sample CG-102.....	111
Sample CG-103.....	117
Sentinel Gap Basalt.....	125
SGE-2-2.....	128
SGE-2-3.....	135
Topopah Spring Tuff.....	142
Catalina Granite.....	150
Sample CCR-P-100.....	150
Sample CCR-D-100.....	154
Tests on Bentonite Plugs.....	159

TABLE OF CONTENTS---Continued

	<u>Page</u>
CHAPTER FIVE: ANALYSIS OF EXPERIMENTAL RESULTS.....	170
Analysis of Tests on Cement Plugs.....	172
Charcoal Granite.....	172
Sample CG-101.....	172
Samples CG-102 and CG-103.....	174
Sample CG-104.....	176
Comparison of CG-103 and CG-104.....	183
Discussion.....	187
Sentinel Gap Basalt.....	190
Sample SGE-2-2.....	190
Sample SGE-2-3.....	194
Oracle Granite.....	194
Topopah Spring Tuff.....	201
Catalina Granite.....	206
Tests on Bentonite Plugs.....	208
Charcoal Granite.....	208
Influence of Relative Plug-Rock Permeabilities.....	210
CHAPTER SIX: SUMMARY AND CONCLUSIONS.....	218
Summary of Results.....	218
Conclusions.....	223
Cement Plugs.....	223
Bentonite Plugs.....	225
Discussion.....	225
Suggestions for Further Research.....	227
APPENDIX A: TEST RESULTS.....	230
REFERENCES.....	273

LIST OF ILLUSTRATIONS

<u>Figure</u>	<u>Page</u>
2.1	Open-hole plugging: the balance method..... 15
2.2	Open-hole plugging: the dump bailer method..... 16
2.3	Open-hole plugging: the two-plug method..... 17
3.1	Experimental method: flow through intact rock is compared to flow through sealed rock..... 51
3.2	Photomicrograph of Oracle Granite..... 55
3.3	Photomicrograph of Charcoal Granite..... 58
3.4	Photomicrograph of Catalina Granite..... 60
3.5	Photomicrograph of Sentinel Gap Basalt..... 62
3.6	Photomicrograph of Topopah Spring Tuff..... 67
3.7	Diagram of Ruska liquid permeameter..... 70
3.8	Expansive stress vs. time for Cement System 1..... 73
3.9	Radial permeameter assembly drawing..... 77
3.10	Constant pressure pump assembly drawing..... 85
4.1	Sample OAZ-M1 - dimensions..... 98
4.2	Sample CG-101, flow rate in vs. injection pressure, Charcoal Granite..... 108
4.3	Sample CG-101 - dimensions..... 109
4.4	Sample CG-102, flow rate in vs. injection pressure, Charcoal Granite..... 113
4.5	Sample CG-102 - dimensions..... 114
4.6	System 1 Cement plug in sample CG-102..... 115

LIST OF ILLUSTRATIONS--Continued

<u>Figure</u>		<u>Page</u>
4.7	Diametric view of cement plug, sample CG-102.....	116
4.8	Photomicrograph of plug in Sample CG-102.....	116
4.9	Sample CG-103, flow rate in vs. injection pressure, Charcoal Granite.....	119
4.10	Sample CG-103 - dimensions.....	120
4.11	Pulse test data, CG-103, Cement 1 plug, June 9, 1982.....	122
4.12	Pulse test data, CG-103, Cement 1 plug, June 10, 1982.....	123
4.13	CG-103, sketch of dye test.....	126
4.14	Flow rate vs. time, sample SGE-2-2.....	130
4.15	Sample SGE-2-2 - dimensions.....	131
4.16	Sample SGE-2-2, flow rate vs. time, Cement 1 plug, after drying, June 12 - March 2, 1983.....	134
4.17	Flow rate vs. time, sample SGE-2-3.....	137
4.18	Sample SGE-2-3 - dimensions.....	138
4.19	Sample SGE-2-3, dye test.....	141
4.20	Sample NTS-TPTS-101, flow rate vs. top pressure for rock bridge.....	145
4.21	Sample NTS-TPTS-101, flow rate vs. time, Cement System 1 plug.....	146
4.22	Sample NTS-TPTS-101 - dimensions.....	147
4.23	Sample NTS-TPTS-101 showing fractures and lithophysal cavities.....	148
4.24	Sample CCR-P-100 - dimensions.....	151
4.25	Sample CCR-P-100, dye test.....	155
4.26	Sample CCR-D-100 - dimensions.....	156

LIST OF ILLUSTRATIONS--Continued

<u>Figure</u>		<u>Page</u>
4.27	Sample CCR-D-100, flow rate in vs. injection pressure....	158
4.28	Sample CG-104, flow rate in vs. injection pressure.....	162
4.29	Sample CG-104 test results on 2nd and 3rd clay plugs	163
4.30	Sample CG-104 - dimensions.....	164
4.31	Fracture in CG-104.....	168
5.1	Finite element mesh used with program FRESURF I to simulate radial permeameter tests of rock bridge and plug flow rates.....	171
5.2	Sample CG-101, calculated flow rate vs. permeability for injection pressure, P_T , of 10.0, 7.0 and 3.5 MPa.....	173
5.3	Sample CG-101, variation in flow rate with variation in the ratio of the plug permeability, K_p to rock permeability, K_R	175
5.4	Sample CG-102, flow rate vs. permeability for injection pressures, P_T , of 10.1, 7.0 and 3.5 MPa.....	177
5.5	Sample CG-102, variation in flow rate with variation in the ratio of the plug permeability, K_p , to rock permeability, K_R	178
5.6	Sample CG-103, flow rate vs. permeability for injection pressures, P_T , of 10.1, 7.0 and 3.4 MPa.....	179
5.7	Sample CG-103, variation in flow rate with variation in the ratio of plug permeability, K_p , to rock permeability to rock permeability, K_R	180
5.8	Sample CG-104, rock bridge, permeability vs. first stress invariant, I_1	184
5.9	Sample CG-103, rock bridge, permeability vs. first stress invariant, I_1	186
5.10	Sample SGE-2-2, variation in flow rate with variation in the ratio of plug permeability, K_p , to rock permeability, K_R	191

LIST OF ILLUSTRATIONS--Continued

<u>Figure</u>		<u>Page</u>
5.11	Sample SGE-2-3, variation in flow rate with variation in the ratio of plug permeability, K_p , to rock permeability, K_R	195
5.12	Sample CG-104, variation in flow rate with variation in the ratio of plug permeability, K_p , to rock permeability, K_R	211
5.13	Flow net for intact rock, $K_p = K_R$	213
5.14	Flow net for plug more permeable than rock, $K_p = 10K_R$	215
5.15	Flow net for plug less permeable than rock, $K_p = 0.1K_R$...	216

LIST OF TABLES

<u>Table</u>	<u>Page</u>
3.1 Physical Properties of Oracle Granite.....	57
3.2 Physical Properties of Charcoal Granite.....	59
3.3 Physical Properties of Sentinel Gap Basalt.....	64
3.4 Brazilian Tensile Strengths, T_0 , Sentinel Bluffs Basalt.....	65
3.5 Mechanical Properties of System 1 Cement.....	69
3.6 Expansion Experiment Data - System 1 Cement.....	74
3.7 Radial Permeameter Parts List.....	81
3.8 Nominal Test Schedule.....	92
4.1 Oracle Granite - Test Results for Convergent Flow with Rock Bridge.....	100
4.2 Oracle Granite - Test Results for Divergent Flow with Rock Bridge.....	101
4.3 Oracle Granite - Test Results for Convergent Flow - Hollow Cylinder.....	103
4.4 Oracle Granite - Test Results for Divergent Flow - Hollow Cylinder.....	103
4.5 Summary of Test Results for Sample CG-101.....	107
4.6 Summary of Test Results for Sample CG-102.....	112
4.7 Summary of Test Results for Sample CG-103.....	118
4.8 Summary of Test Results for Sample SGE-2-2.....	129
4.9 Summary of Test Results for Sample SGE-2-3.....	136
4.10 Summary of Test Results for Sample NTS-TPTS-101.....	143

LIST OF TABLES---Continued

<u>Table</u>		<u>Page</u>
4.11	Test Results for Sample NTS-TPTS-101, Cement System 1 Plug.....	144
4.12	Test Results for Sample CCR-P-100.....	153
4.13	Summary of Test Results for Sample CCR-D-100.....	157
4.14	Summary of Test Results for Sample CG-104.....	160
5.1	Summary of Permeability Values Calculated for the Charcoal Granite.....	181
5.2	Estimated and Measured Flow Rates and Permeabilities for Sample CG-104 with Rock Bridge.....	182
5.3	Sample CG-103 - Comparison of Measured Flow Rate through Plugged Sample with Estimated Flow Rate through Sample with Rock Bridge.....	188
5.4	Sample SGE-2-2 - Permeability of Cement System 1 Plug after Drying.....	193
5.5	Oracle Granite; Top Hole, Radial Permeability in Convergent Flow with Rock Bridge.....	197
5.6	Oracle Granite; Top Hole, Radial Permeability in Divergent Flow with Rock Bridge.....	197
5.7	Oracle Granite; Radial Permeability in Convergent Flow - Hollow Cylinder.....	199
5.8	Oracle Granite; Radial Permeability in Divergent Flow - Hollow Cylinder.....	199
5.9	Sample NTS-TPTS-101, Rock Bridge; Upper Bound Permeability.....	204
5.10	Test Results for Samples CCR-P-100 and CCR-D-100.....	207
6.1	Summary of Rock and Plug Permeability Data.....	219

ABSTRACT

Boreholes in the vicinity of a nuclear waste repository must be reliably sealed to prevent rapid migration of radionuclide contaminated water from the vicinity of the repository to the accessible environment. Few data currently exist regarding the effectiveness of borehole sealing. The objective of this research was to assess the performance of borehole seals under laboratory conditions, particularly with regard to varying stress fields.

The approach used to evaluate borehole seals was to compare flow through a sealed borehole with flow through intact rock. Granite, basalt, and tuff were tested, using either cement or bentonite as the seal material.

The main conclusion reached as a result of the experiments is that currently existing materials are capable of forming high quality seals when placed under laboratory conditions. Variation of triaxial stress state about a borehole does not significantly affect seal performance if the rock is stiffer than the seal material. Temperature/moisture variations (drying) degraded the quality of cement seals significantly. Performance partially recovered upon resaturation.

A skillfully sealed borehole may reasonably be expected to be as impermeable as a fractured rock mass (subject to site-specific verification). The influence of relative seal-rock permeabilities

provides insight into important seal parameters. A plug one order of magnitude greater in permeability than the rock through which it passes results in an increase in flow through the borehole and surrounding rock of only 1 1/2 times as compared to the undisturbed rock. Since a sealed borehole and its surrounding rock are only a small part of the total rock mass, the effect is even less pronounced. One of the simplest ways to decrease flow through a seal-rock system is to increase the length of the seal.

Significant remaining questions include field emplacement techniques; field verification of plug quality; plug performance over long time periods, particularly with respect to temperature/moisture variations and chemical stability; and radionuclide sorption capabilities. Scale effects are also important, as shafts and drifts must be sealed as well as larger diameter boreholes.

CHAPTER 1

INTRODUCTION

With the advent of disposal of high-level nuclear wastes in underground repositories, borehole plugs assume an important role in isolating waste from the earth's surface. When waste is placed underground one of the most likely ways by which it may return to the earth's surface is by transport in ground water. Low permeability rock surrounding the waste is relied upon to slow the migration of waste-contaminated water and prevent its reaching the accessible environment until the radionuclides have decayed to safe levels. Clearly an open borehole is a direct conduit from depth to the surface; boreholes in the vicinity of a waste repository must be reliably plugged. Indeed, one of the reasons for abandonment of a proposed waste repository near Lyons, Kansas, was concern about the ability to plug abandoned oil and gas wells in the area (Eilers, 1973, 1974).

Borehole plugging is particularly important if disposal strategies are adopted that do not emphasize the waste form and container as a barrier to release of radioactivity from the repository. Such strategies may arise due to the risks and costs involved in changing existing waste forms and containers. "The burden of protecting the public from long-term migration of nuclear wastes may then be placed

primarily on the engineered features of the repository" (Bartlett and Koplik, 1979).

Even given an optimum waste form and container, one of the main reasons for placing the waste in an underground repository is to use the surrounding rock to isolate the waste in case of container failure. An open borehole seriously compromises the integrity of the rock.

Borehole plugging is also critical in the disposal of chemical wastes by deep-well injection. The most common operation in this regard is the disposal of oil-field brines back into the formations from which they were produced. Toxic chemical wastes currently are also disposed of in this manner. "Opponents of deep-well injection argue that the wastes, which are injected under extreme pressure, can flow laterally through geologic strata into poorly constructed or unplugged deep wells and then rise to contaminate subsurface water supplies" (EPA, 1980, p. 16).

Piper (1969, p. 6) notes that, "Injection does not constitute permanent disposal. Rather, it detains in storage and commits to such storage - for all time in the case of the most intractable wastes - underground space of which little is attainable in some areas, and which definitely is exhaustible in most areas."

Few data currently exist regarding the effectiveness of borehole plugging (Christensen, 1980, p. 7). One recent report (ONWI-39, 1979, p. 6-11) states that, "To evaluate the integrity of borehole seals already in common use a study was made of failures that have

been experienced by the oil and gas industry in the United States. It was found (Schneider and Platt, 1974) that the probability of failure of seals on a typical oil well was $1\text{E}-04$ per year." Reference to Schneider and Platt (1974, p. 3.27) yields the basis of the study:

"Based on data in the Statistical Abstracts (U.S. Bureau of the Census, 1971), there are over 500,000 producing oil wells in this country. There is probably at least an equal number of abandoned wells. All have seals between the well casing and the underground strata.¹ The statistics on seal failure may be available, but no known research has been done on this point to date. However, Associated Press accounts in the past year have related at least two instances of shaft seals leaking. In one case oil was coming from a well in the front lawn of a residence in Southern California. The well had been capped several decades ago. The other case was a new well in Traverse City, Michigan. These are just two of significance. There are probably more that have not been reported. Thus, the probability of a seal failure by conventional techniques is more frequent than 1×10^5 per well-yr."

¹Compare this with the statement (EPA, 1978, p. 18) on water seepage problems at the proposed nuclear waste repository near Lyons, Kansas: "Seepage was along an abandoned drill hole that, like most, had not been cased and plugged."

Schneider and Platt state that an evaluation method is being discussed and they include a caveat (p. 3.1.1) against using their results to draw quantitative conclusions. This is a very small data base on which to base statistical conclusions regarding the probability of seal failure. One of the main problems is that, as Smith (1976) states, "There is no simple method of testing down-hole plugs. In most cases, plugs for abandonment or for sealing off bottom water are never tested."

It is widely recognized in the oil and gas industry that it is very difficult to achieve high quality sealing: "A common problem encountered in production operations is the movement of water in channels within the cement annulus behind casing of oil and gas wells" (Arnold and Paap, 1979); "Annular and interzone gas flow ... continues to be a major problem ... these occurrences have been experienced by the industry worldwide ..." (Levine et al., 1980).

Conclusions regarding borehole plugging must have a firmer data base than currently exists.

Borehole Sealing and Nuclear Waste Isolation

High-Level Nuclear Waste Isolation Research Efforts

Research regarding nuclear waste isolation is a major effort of scientists both in this country and abroad. At this writing (January, 1983), the President of the United States has just signed the Nuclear Waste Policy Act of 1982, Public Law 97-425, which requires the U.S. Department of Energy to recommend three sites for the first high-level

nuclear waste repository for commercially-generated (i.e., non-defense) nuclear waste by 1985. The president will have until March, 1985, to pick the location of the first repository (Hunt, 1983). Rock types considered for commercial nuclear waste repositories include welded and non-welded tuffs at the Nevada Test Site,¹ near Las Vegas; basalts of the Columbia Plateau at the Hanford Reservation¹ in southeastern Washington; and bedded and dome salt deposits in Louisiana, Mississippi, Texas, and Utah. The bill also requires the Department of Energy to recommend five sites by 1989 for a second repository. Granite formations around the Great Lakes, along the Atlantic Seaboard, and in New England are being considered. In addition to these potential commercial waste repository sites, bedded salt near Carlsbad, New Mexico, is being considered as a repository for defense related nuclear waste. This is known as the Waste Isolation Pilot Plant (WIPP).

The Department of Energy has established the National Waste Terminal Storage Program (NWTSP) to coordinate commercial waste isolation research. The program is managed by the Office of Nuclear Waste Isolation (ONWI), Battelle Memorial Institute, Columbus, Ohio. Much of the research concerning the tuffs at the Nevada Test Site¹ is being

¹The Nevada Test Site was established to provide an area for testing nuclear weapons. The Hanford Reservation is one of the original three research areas established under the Manhattan Project, the other two being Oak Ridge, Tennessee, and Los Alamos, New Mexico.

conducted by Sandia National Laboratories (SNL), Albuquerque, New Mexico, and by Lawrence Livermore National Laboratories (LLL), Livermore, California. Research regarding waste isolation in basalt at the Hanford Reservation is performed by Rockwell Hanford Operations, a division of Rockwell International Corp., which operates the plant for the Department of Energy.

ONWI is primarily responsible for research into salt sites; much of the research is performed by outside contractors which include several national laboratories as well as private consultants. Research for WIPP is conducted primarily by Sandia National Laboratories. Research efforts are furthest along for the Nevada Nuclear Waste Storage Investigation (NNWSI) at the Nevada Test Site, the Basalt Waste Isolation Project (BWIP) at Hanford, and the Waste Isolation Pilot Plant (WIPP) in New Mexico. Each year progress is reported at a National Waste Terminal Storage Program Information Meeting, except for the WIPP site which, being for defense waste, is (currently) outside the NWTs program.

One further note: The U.S. Department of Energy is responsible for finding and operating a high-level nuclear waste repository. However, the repository must be licensed by the Nuclear Regulatory Commission (NRC) and meet environmental standards set by the Environmental Protection Agency (EPA). The NRC conducts research of its own to support their licensing requirements. The research reported herein was sponsored by the NRC.

Borehole Sealing Considerations

At the most recent NWTs Program Information meeting borehole sealing continued to be a major topic. In their article regarding NNWSI, "Repository and Engineering Barriers Design", Scully and Rothman (1982) state that, "A well-engineered system of man-made barriers should be able to assist the natural barriers in retarding radionuclide migration. The areas where proper engineering can be most effective in protecting the biosphere in the long term include ... design of seals to close the repository." Both shaft seals and borehole seals are important.

Borehole sealing is also a concern in the BWIP. Anderson et al. (1982) state that, "The isolation of nuclear wastes in deep, mined repositories will require the sealing of all penetrations such as shafts, tunnels, repository rooms, or boreholes, into and nearby the repository."

Perhaps the most sophisticated borehole sealing research in connection with nuclear waste isolation performed to date has been for the WIPP program. Both laboratory testing and field testing have been performed by Sandia National Laboratory, the Materials Research Laboratory at the Pennsylvania State University, D'Appolonia Consulting Engineers, the Waterways Experiment Station of the Army Corps of Engineers, Oak Ridge National Laboratory, and Terra Tek, Inc. This work will be reviewed in the next chapter.

D'Appolonia is assisting in the design of seals for a bedded salt repository, and in their most recent report state that, "The isolation

of radioactive wastes in geologic repositories requires that man-made penetrations such as shafts, tunnels, or boreholes are adequately sealed" (Kelsall et al., 1982).

Borehole sealing is also a concern of nuclear waste isolation efforts in other countries. In a paper presented at the First European Community Conference, Barbreau, Heremans, and Jensen (1980) state that, "Efficient techniques must be developed for filling and plugging shafts, tunnels, and drill holes, to assure their imperviousness over a very long period of time, and create additional geochemical barriers." The International Atomic Energy Agency has stated, "Special attention has to be paid to the sealing of boreholes and shafts after deactivation of the repository" (IAEA, 1980). Further, "To get adequate subsurface hydrologic information comprehensive drilling programmes are often needed. Then, serious consideration must be paid to the short-circuiting effect of any borehole drilled into the repository host rocks. This is particularly important in stratified confined aquifers and in low permeability crystalline formations in which a borehole may constitute a gross perturbation to the natural undisturbed hydrogeological system."

Research Objectives

The objective of the research reported herein was to assess the performance of borehole seals under laboratory conditions. One of the prime goals was to obtain experimental data regarding the effectiveness of sealing.

Laboratory conditions represent a highly idealized approximation of field conditions. This permits the determination of the best possible sealing performance that may be expected because emplacement of a plug may be done under carefully controlled conditions. In the field plugs are emplaced in deep holes, in highly inaccessible locations, frequently in a wellbore filled with mud. Many variables are introduced in such a process, few of which can be controlled; some may not even be recognized.

Laboratory testing permits a systematic, controlled variation of the parameters that influence plug behavior. In this work the parameters considered are rock type (granite, basalt, and tuff), plug type (cement and clay), and mechanical plug-rock interaction under varying stress fields.

The experiments performed have direct bearing on proposed rules for the disposal of high-level nuclear waste in geologic repositories which state in part, "Shaft and borehole seals shall be designed ... [to] ... accommodate potential variations of stress, temperature, and moisture" (Nuclear Regulatory Commission, 1981).

In these experiments seal performance under varying stress fields was investigated; temperature was held constant and saturated conditions obtained. A significant part of the research effort was the development of laboratory equipment for performing the experiments. This equipment, with slight modifications, can be used to investigate both temperature and moisture variations.

This work is part of a larger research project regarding rock mass sealing performed at the University of Arizona. In addition to laboratory studies of borehole plug performance, field studies have been conducted by Greer (1982); Jeffrey (1981) has studied the stress-field in a shaft or borehole plug and the surrounding rock; Mathis (1982) has studied the damage zone induced in the walls of a wellbore during drilling; Cobb (1981) has performed further laboratory studies using a polyaxial permeameter; and Stormont (1983) has studied the shear strength of borehole plugs. This work is reviewed in the next chapter. In addition, Greer (1983) is currently performing further field studies.

CHAPTER 2

BOREHOLE SEALING: CURRENT PRACTICE AND RECENT STUDIES

Well cementing has been practiced by the oil and gas industry for decades; grouting to seal rock and soil masses began at least in the early 1800's, and there is some evidence that the Romans were aware of the potential uses of grouting (Bowen, 1975).

A wide variety of products and methods exist. All have some features or characteristics which under some external circumstances will prove to be undesirable. For a significant number the disadvantages suffice to eliminate them from further consideration. The remaining possibilities can be considered as having complementary characteristics, and it is virtually certain that an optimum borehole plug will use more than one type of material.

The most likely materials to be used in borehole plugging are portland cement and clay. These materials are the ones most commonly used by well drillers and plugging technology is well-developed. (However, experimental facts on past performance are mostly qualitative in nature.) For deep wells portland cement is the dominant plugging material. In this chapter methods of well cementing will be discussed, followed by a review of recent studies concerning borehole sealing for nuclear waste isolation. For more information on other systems see Daemen et al. (1979, Ch. 2) for a review of existing tech-

nology and potential plugging systems; South (1979) for an in-depth review of well-cementing; and Sultan (1979) for a review of chemical grouting techniques.

Current Methods of Borehole Sealing

Well cementing is performed routinely by the oil and gas industry. Portland cement, with a variety of additives, is normally used. Cementing serves both to restrict fluid movement between formations and to bond and support casing. Cement plugs are placed when a well is abandoned. Smith (1976) describes well cementing techniques in detail.

Clay is also used to seal wells, particularly for shallow wells and in isolating well-points (piezometers).

Methods of Well Cementing

Three basic types of well cementing are performed: primary cementing, squeeze cementing, and open-hole cementing (plugging).

In primary cementing a cement slurry is pumped down the casing and rises in the annulus between the casing and the hole. The casing is thus cemented into position and formations sealed off.

Squeeze cementing is the most common type of remedial cementing. Hydraulic pressure is applied to force (squeeze) cement slurry into a formation void or against a porous zone to obtain a better seal between casing and formation.

Open-hole cementing is used to isolate zones in uncased sections of a hole and to plug abandoned wells. Plugging of abandoned wells

is, of course, one of the primary sealing objectives in nuclear waste isolation. In the oil and gas industry problems associated with plugging may arise because a relatively small volume of cement is placed in a large volume of wellbore fluid. Mud contamination of the cement is a common cause of well cementing failures.

In placing a cement plug in an open hole, one must consider carefully the type of formation through which the plug is to be placed. Plug failures can be prevented by taking the following precautions (Anderson, 1955):

- (1) "Selecting, with the help of a caliper log, a gauge section of the hole.
- (2) "Carefully calculating cement, water, and displacement volumes, and always planning to use more than enough cement.
- (3) "Using a densified cement that will tolerate considerable mud contamination.
- (4) "Preceding the cement with sufficient flush.
- (5) "Rotating the tubing using tail pipe with centralizers and scratchers while placing the cement.
- (6) "Using drillpipe wiper plugs and plug catchers.
- (7) "Placing the plug with care and moving the pipe slowly out of the cement to minimize mud contamination."

For maximum bonding a clean, hard formation should be selected, particularly for zone isolation or abandonment. Cement plugs may be placed by the balance method, the dump bailer method, or the two-plug

method. The balance method, Figure 2.1, involves pumping a desired quantity of cement slurry through drillpipe or tubing until the level of cement outside is equal to that inside the string. The pipe or tubing is then pulled slowly from the slurry, leaving the plug in place. The characteristics of the mud are very important in balancing the plug in the well. Free circulation is especially vital while the cement is being pumped down the string.

The dump bailer method, Figure 2.2, is usually employed at shallow depths, although retarded cement has been used to depths exceeding 12,000 feet. A limit plug, cement basket, permanent bridge plug, or gravel pack (the first three being mechanical devices) is first placed below the zone to be plugged. A measured quantity of cement is placed in a dump bailer, which is then lowered on a wire line. Touching the mechanical plug or gravel pack opens the bailer, which is slowly raised to release the cement. Deep plugs are difficult to set by this method; mud may contaminate the cement unless the hole is circulated before dumping (this is also true of the balance method), and there is a limit to the quantity of slurry that can be placed per run.

The two-plug method, Figure 2.3, uses top and bottom tubing plugs to isolate the cement slurry from the well fluids and displacement fluids. A bridge plug is usually placed at the cement plugging depth. A special baffle tool is run on the bottom of the string and placed at the depth desired for the bottom of the cement plug. This tool permits the bottom tubing plug to pass through and out of the tubing or drillpipe. Cement is then pumped out of the string at the

Figure 2.1 Open-hole plugging: the balance method (after Smith, 1976).

Figure 2.2 Open-hole plugging: the dump bailer method (after Smith, 1976).

Figure 2.3 Open-hole plugging: the two-plug method (after Smith, 1976).

plugging depth and begins to fill the annulus. The top tubing plug, following the cement, is caught in the plug-catcher, which is part of the baffle tool, causing a sharp rise in the surface pressure, indicating that the plug has landed. The latching device holds the top tubing plug to help prevent cement from backing up into the string, but permits reverse circulation. This design allows the string to be pulled up after cement placement to cut off the cement plug at the desired depth by establishing reverse circulation through the plug catcher, thus allowing excess cement to be reversed up and out of the tubing. The string is then pulled, leaving a cement plug.

Advantages of the two-plug method are that it minimizes the likelihood of over-displacing the cement, it forms a tight, hard cement structure, and it permits establishing the top of the plug. The two-plug method is preferred to the balance method.

There is no simple method of testing down-hole plugs. In most cases, plugs for abandonment or for sealing off bottom water are never tested. Plugs set to control lost circulation or for whipstocking are tested by determining the hardness of the plug. The most common approach is to run drillpipe - either open ended or with a bit - back into the hole to locate the plug by applying weight. The method is commonly used after the plug has been allowed to set some 12 to 14 hours (Pugh, 1967). Although it is not always satisfactory, at least it gives some indication of whether some degree of plugging has been achieved in the desired location. A plug might be hard on top, but soft farther down, so that in time fluids can migrate past it.

Safety Plugging of Oil Wells Penetrating Appalachian Coal

Mines. Safety plugging of wells penetrating Appalachian coal seams has been described by Rennick et al. (1972). Such wells pose a methane hazard. An oil well penetrating the Pittsburgh bituminous coalbed in northern West Virginia was plugged and safely mined through 3 months later. A sensitive chemical tracer, introduced into the oil reservoir before the test, was not detected in the mine air following the plugging and during mining of the pillar about the well and penetration of the well. Effectiveness of the plugging in preventing reservoir gas from entering the mine through the well hole was verified by continuous monitoring of the mine air for indications of sulfur hexafluoride, an inert gas detectable in amounts as minute as 0.5 parts per billion. Expandable cement and fly ash-gel-water slurry were utilized to seal the well above and below the coal seam.

This injection of sulfur hexafluoride, plugging, and monitoring represents one of the rare instances in which a plugged, abandoned well was actually monitored for performance. This type of work is necessary to evaluate plugging performance.

Implications for Nuclear Waste Disposal. The foregoing has been concerned with the techniques of cementing wells as practiced by the oil and gas industry. These same techniques, with some extra caution, are used in plugging chemical waste disposal wells.

There is general agreement that well cementing and plugging in the oil and gas industry and for chemical waste disposal wells is usually successful. Successful cementing of an oil or gas well,

however, simply means that excessive water is not produced along with the oil or gas - that there are no production problems. Once a well is plugged and abandoned there is no monitoring; problems may not be detected. As noted in Chapter 1, channel flow in the cemented annulus between casing and wellbore is a continuing problem in the oil and gas industry.

Plugging of chemical waste disposal wells for abandonment must usually be approved by a state agency. There are many such wells along the Texas Gulf Coast, and the Texas Department of Water Resources (DWR) has regulatory responsibility for these wells. Conversations with their personnel indicate no problems in 17 years of operation - a very short period when considering nuclear waste disposal. Plugging designs for chemical waste wells must be approved by the Texas DWR, and the actual operation is witnessed in the field by a DWR representative. Quality assurance is obtained by tagging the plug; the plug is allowed to harden and then the drill string is lowered to touch the plug and verify its location. Plugs are a minimum of 100 feet long. Thus, a plug which is hard on top, and properly located, may have problems deeper in the hole which would not be detected by the tagging. Long term monitoring is usually not performed.

To recapitulate:

- (1) Successful well-cementing is defined as an absence of problems. That is, problems are not detected.
- (2) Little has been found to date to indicate quantitatively the effectiveness of well plugging. For example, how much

vertical fluid migration occurs in a skillfully plugged well?

- (3) Obtaining a good plug requires experience and a good knowledge of downhole conditions and geology.
- (4) Quality assurance of plugs is limited to tagging the plug, as there is no longer a hole in which to lower logging tools. In this regard the work by Rernick et al. (1972) in safety plugging of oil wells penetrating Appalachian coal mines, described in the previous section, is of interest.
- (5) Long term monitoring of plugged wells to assure lack of fluid migration is rare.
- (6) The critical zone in a well plug is probably the plug-rock interface, and the plug-casing interface if the hole is cased.
- (7) In most applications today a plug that would last 100 years would be considered permanent. This length of time is orders of magnitude less than the times of interest for nuclear waste disposal.

Borehole Sealing with Clay

Sodium bentonite clay is used frequently to seal shallow (a few hundred feet) wells. In the installation of piezometers for hydrologic studies the zone of interest may be isolated by using bentonite pellets. These small tablets of highly compressed bentonite may be dropped through water and will swell to ten or fifteen times their

original volume when hydrated with fresh water, thus forming a low permeability seal. The clay seal formed functions well when saturated, but will crack upon drying. Upon rewetting the clay will again swell and form a seal.

To maintain its performance the sodium bentonite must be in equilibrium with its surroundings. Bentonite has a high cation-exchange capacity and under certain chemical conditions the sodium may be replaced by calcium or other ions, rendering the clay more permeable. This effect can change the internal structure of the clay and lead to piping. Clays subject to this phenomenon are known as dispersive clays and are a cause of problems in earth dams.

A more detailed discussion of chemical considerations is given by South (1980).

Use of compacted shale or clay to form a borehole seal has been studied by Martin (1975) and by Fernandez et al. (1976). Martin conducted laboratory tests and concluded that both crushed shale and montmorillonite clay are feasible materials for sealing boreholes. A high compactive effort is necessary and in the laboratory tests water flow was concentrated at the interface between the plug and the model wellbore. Conceptual design of downhole compaction methods were static, impact, roller, vibratory, and air gun.

Fernandez et al., studied emplacement techniques as an extension of Martin's work and concluded that only static and impact compactors were feasible. A batch or bucket system would be used to supply material downhole. No commercial equipment was found suitable for

either conveying material downhole or compacting it in place. Some oil-well equipment could be used as a starting point, but refinement and instrumentation would require research and development.

Little work beyond Fernandez's on methods of emplacing compacted clay plugs has been done. One of the most serious drawbacks of Fernandez's work is the assumption of a dry hole. Only at the Nevada Test Site are potential repository horizons above the water table.

Compacted clay plugs are discussed by Kelsall et al. (1982, p. 67) as a possible component of a vertical borehole seal, but methods of emplacement are not discussed.

Cement remains the primary material considered for borehole plugging. Clay will likely be used in multi-component plugs. The ability of clay to deform without cracking makes it particularly valuable as a seal component and complements the greater mechanical strength, but more brittle nature of cement.

Recent Studies Regarding Borehole Sealing for Nuclear Waste Isolation

Department of Energy studies regarding borehole plugging in relation to high-level nuclear waste isolation have been conducted in recent years. Much of the work has been in connection with the WIPP site. Studies have been concerned with material selection, material development and laboratory and field testing. Studies concerned with BWIP and of a generic nature have also been done.

The literature on this subject is voluminous, both due to the many researchers involved and due to the fact that the work is reported in a series of quarterly, annual, and final reports.

The Bell Canyon Test

Perhaps the most significant test performed to date in the Department of Energy's program has been the Bell Canyon Test. This test was performed by Sandia National Laboratories at the WIPP site. The purpose of the test was, "To evaluate in situ the state of the art in borehole plugs and to identify and resolve problems encountered in evaluating a 'typical' plug installation in anhydrite" (Christensen and Peterson, 1981).

In this test a two meter long plug of cement was placed in a 20 cm. diameter hole at a depth of 1370 meters. The plug was placed in the lowest anhydrite of the Castile Formation, directly above the Bell Canyon aquifer. The aquifer provided a 12.4 MPa. differential fluid pressure across the plug and had a production capability of 38,000 liters/day.

A fresh-water grout mix, designated BCT-1FF, was selected to plug the hole. The composition of this mix was:

Class H cement	52.2%
Expansive agent	7.0%
Fly ash	17.6%
Dispersant	0.2%
Defoamer	0.02%
Water	23.0%

giving a water/cement ratio of 0.30¹ and a fluid density of 1.98 g/cc (17.0 lb/gal).

The plug was installed to isolate the upper regions of the borehole from the Bell Canyon aquifer. Measurements were made of both the volumetric flow and the velocity of fluid flowing from the aquifer through, or around, the plug into the upper wellbore. Because the upper portions of the borehole produce fluid, an umbrella packer was installed to provide an isolated test chamber for measurement purposes.

Four distinct fluid paths exist from the aquifer through, or around, the plug into the test region: through the plug itself, along the plug/borehole interface, through a possible damage region along the borehole wall resulting from drilling and coring operations, and through the undisturbed formation surrounding the plug. It is the total of the flow occurring along all these paths that was measured.

Additional flow paths along which fluid can enter or leave the test region include flow from above the umbrella packer through the surrounding formation or wellbore damage region, flows occurring along some formation discontinuity leading to a distant source, and leakage from the umbrella packer and attached tubing assembly.

The field data obtained during the Bell Canyon Test, along with laboratory data obtained in the course of the program, suggest that

¹As reported in the Bell Canyon Test Summary report. Actually this figure (0.30) is with respect to cement plus additives. Water/Class H cement ratio = $23.0/52.2 = .44$.

the predominant flow into the test region occurs through the plug/borehole interface region, with smaller contributions attributable to flow through the wellbore damage zone, the plug core, and the surrounding undisturbed anhydrite formation. A computer simulation was performed to demonstrate that the measured data were consistent with having a predominant interface flow and to establish an upper bound on the wellbore damage region flow properties.

In this simulation the undisturbed anhydrite was assumed to have zero permeability. No flow was permitted from above the umbrella packer, and the umbrella packer was simulated as a region having zero permeability. Typical laboratory values of 1 microdarcy permeability and .001 porosity were taken for the cement plug core. The predominant flow into the test region was modeled to occur through microstructure existing in the plug/borehole bond region. The cross-sectional area of this region was arbitrarily taken as 10% of that of the wellbore. This corresponds to a 0.5 cm wide microstructure region in the 20 cm diameter borehole. Properties of the wellbore damage region were unknown, and arbitrarily assumed to have a cross-sectional area equal to that of the wellbore, and a permeability and porosity of 8 microdarcies and 0.01, respectively. This corresponds to a wellbore damage region 4.4 cm thick. Agreement of the experimental data with the simulation was good, indicating the experimental data are compatible with the hypothesis that flow occurs predominantly through a small plug/borehole interface zone. The solutions are not unique, and any reasonable combination of flow zone properties, consistent with

the field values measured will provide test pressure histories consistent with the measured data.

Further calculations indicated that the permeability of any possible wellbore damage region surrounding the packer must be less than the 8 microdarcy value used in the initial calculation.

The Work of D'Appolonia Consulting Engineers

D'Appolonia Consulting Engineers, under a contract with the Office of Nuclear Waste Isolation (ONWI) has studied repository sealing. This work was in connection with the WIPP site and was directed toward sealing a repository in bedded salt, although the work applies in varying degrees to repositories in other geologic media (i.e., other rock types).

The work involved extensive literature review and conceptual design of borehole and shaft seals, and is discussed in a series of reports: D'Appolonia, 1979, 1980a, 1980b, 1981; Kelsall et al., 1982.

The 1979 Report. This report points out that the objective of borehole (and shaft) sealing as related to nuclear waste isolation is to provide an assured seal of any man-made penetrations to prevent or retard (i.e., keep below acceptable levels) the passage of water and gas between the waste repository and the accessible environment. Sealing for nuclear waste isolation differs from other areas in that a greater degree of assurance that sealing has been accomplished is necessary.

In 1979 D'Appolonia identified three important issues which needed quantification: (1) overall sealing program objectives and requirements; (2) importance of plugging boreholes and of sealing shafts in the area of a nuclear waste repository; (3) longevity requirements for penetration seals.

The report further points out the necessity for both site specific and general research and recommends that the exact results required of seals be established. If the consequence of significant harm due to an unplugged borehole can be shown to be small, plugging requirements may be less stringent.

The 1980 Reports. These two reports (D'Appolonia, 1980a, 1980b) concern design approaches and evaluation of materials research objectives and requirements. Four basic alternative design goals were considered, varying from "returning the repository formation to its original permeability" to "providing seals which control potential radioactivity release to an acceptable level with a margin of safety". The latter was recommended. To limit the consequences to acceptable limits a seal would be placed either as a barrier against fluid flow into the repository or as a barrier against radionuclide migration out of the repository. Radionuclide migration could be prevented using multiple seal components with either low permeability or high radionuclide adsorption capacity.

In their evaluation of materials research objectives and requirements D'Appolonia recommended a materials program based upon two major considerations: (1) establishing which engineering properties of

seals are useful in determining the applicability and performance of a penetration seal or material, and (2) establishing a range of candidate sealing materials that are potentially capable of providing the basic seal functions: prevention or retardation of fluid flow or sorption of radionuclides.

The 1981 Report. This report, which is available only in draft form, presents the results of studies carried out as a result of the recommendations made in the evaluation report (D'Appolonia, 1980b). From the range of materials considered, cement and sodium bentonite clay were chosen as having priority.

The design parameters thought by D'Appolonia to be important are:

- (1) Site geology, stratigraphy, and general hydrology.
- (2) Host rock chemical, physical, mechanical, and thermal properties.
- (3) Groundwater chemistry.
- (4) Undisturbed host rock permeability.
- (5) Host rock sorption properties.
- (6) Penetration geometry.
- (7) Penetration sidewall characteristics.
- (8) Disturbed zone pore and fracture characteristics and extent.
- (9) Disturbed zone permeability.
- (10) Penetration deformability.
- (11) Seal-host rock interface characteristics.

The work reported in this dissertation concerns influence of seal-host rock mechanical interaction (2), undisturbed host rock permeability (4), and seal-host rock interface characteristics (11). Jeffrey (1981) has performed theoretical analyses of seal-host rock interaction (2); Mathis (1982) has studied the disturbed zone (8,9); and Cobb (1981) has performed additional tests concerning seal-host rock mechanical interaction.

The 1982 Report. This report describes schematic seal designs for a repository in bedded salt. Borehole seal designs include cement, clay, and crushed salt as potential sealing materials. The borehole would be sealed in stages (Kelsall et al., 1982):

- (1) "Characterize the hole by examining drilling records and, if necessary, by running additional logs. Particular attention is paid to identifying the permeable zones and to describing the hole geometry using caliper logs and downhole television."
- (2) "Perform packer tests to identify permeable zones."
- (3) "Flush the hole to remove debris and clean the surface with brushes or reamers."
- (4) "Squeeze grout with cement in the more permeable zones, as appropriate."
- (5) "Drill out the hole and repeat packer tests in permeable zones; repeat the squeeze grouting if necessary."
- (6) "Drill out the hole and grout with bentonite or chemical grout (as necessary, if cement grouting does not eliminate water losses)."

- (7) "Drill out the hole and part fill from the bottom with an expansive cement."
- (8) "Fill section of hole above first cement stage with crushed salt or clay, densely-compacted in place."
- (9) "Fill remaining section of hole to ground surface with expansive cement."

Discussion. The D'Appolonia reports represent some of the more extensive work on borehole sealing for nuclear waste isolation to date. Although performed with the WIPP site (bedded salt) in mind, much of the work applies generally. The three important issues identified in the 1979 report - overall objectives and requirements, importance of plugging, and longevity - are still under discussion.

Wellbore Damage Zone Studies by Terra Tek

The extent and nature of the drilling induced damage zone around a borehole was investigated by Lingle et al. (1982) of Terra Tek, Inc. Full-scale drilling tests were conducted on samples of anhydrite, salt, basalt, and tuff. Cores 34 cm. in diameter and 91 cm. long were drilled under simulated downhole conditions using 20 cm. diameter bits. Roller-cone bits and diamond bits were used along with three different drilling fluids: mud, water, and air.

Damage assessment included dye-penetrant inspections, microscopic examinations, and laboratory permeability measurements. The techniques indicated damage only on the order of grain dimensions around the borehole in the anhydrite, granite, and basalt. No damage

was observed in the tuff, but damage could not be ruled out. Damage was not detected in the salt by microscopic or dye penetrant techniques, but laboratory permeability measurements showed increased flow.

The laboratory permeability test results on granite, basalt, and tuff are of interest for this dissertation. The granite tested is described as "fine-grained granodiorite with abundant dark-gray hornblende and biotite-rich inclusions; it has uniform texture and is fairly isotropic". The granite was obtained from the Cold Spring Granite Company, Cold Spring, Minnesota, and may be the same rock, or similar to, the Charcoal Granite obtained from the Cold Spring Granite Company used in the work reported herein. Granite permeabilities reported by Terra Tek range from 1.0×10^{-6} to 2.8×10^{-6} darcy.

The basalt used was dark gray to black with interlocking crystalline texture and was collected from the Columbia River basalt plateau flows near the John Day Dam. This rock exhibited permeabilities ranging from 0.2×10^{-6} to 0.7×10^{-6} darcy.

The tuff tested was a light grayish pink, partially welded tuff with volcanic rock fragments and glass shards. The rock was obtained from the Upper Provo River Canyon near Kamas, Utah. Permeability values measured ranged from 0.5×10^{-6} to 8.40×10^{-6} darcy.

A flow test on a plugged anhydrite using fresh water containing a tracer dye indicated all flow occurred at the grout/rock interface. In this test a 20 cm diameter hole was drilled with a roller cone bit into an anhydrite core 39 cm in diameter and 91 cm long. The

anhydrite was from the Winn Rock Quarry, Winnfield, Louisiana. BCT-1FF grout was used to form a 48 cm long plug in the sample. (This is the same grout used in the Bell Canyon Test.) Under a pressure differential of 13.8 MPa across the plug a fracture aperture at the interface of 4.1×10^{-6} meters was calculated. This assumes all flow is through an aperture between the plug and the anhydrite, i.e., along the grout/rock interface. Similar calculations using data from two measurements made during the Bell Canyon Test give similar results: 3.2×10^{-6} meters and 6.1×10^{-6} meters.

Research at The Pennsylvania State University

The Materials Research Laboratory at The Pennsylvania State University has been performing research on cementitious materials for use in sealing applications with respect to nuclear waste isolation since the mid '70's. Their work has considered both physical properties which allow a plug to be emplaced and function as desired and chemical properties which affect the longevity of the plug.

In one of the early reports (Roy et al., 1977) the effect of cement paste admixtures on the rheology and cement properties, chemical shrinkage, permeability, and cement-rock interaction is discussed. Cement permeabilities were measured using a method developed by Klinkenberg (1941) in which a gas is used as the permeant. Permeabilities of 2 to 3 microdarcies are reported for cements with 0.3 water/cement ratio after 60 days of curing. Sample preparation included drying for one hour at 110°C and placing in a dessicator until testing.

Also of interest in this report is a summary of results on cement/rock bonding from Chatterji and Jeffrey (1971) which, "indicate that aggregate of sand, basalt, granite, and limestone showed no signs of chemical bonding with portland cement hydration products, but did show evidence of chemical etching. [This] suggests that the cement/aggregate bond is mainly due to the free surface energy of the cement hydration products and the viscosity effect of the surrounding liquid phase present in the mortar."

In 1981 Wakeley, Roy, and Grutzeck reported on "Experimental Studies of Seal Materials for Potential Use in a Los Medanos-Type Bedded Salt Repository". Of most interest in the present context are the data on cement porosity, permeability, and bonding. The porosities of hardened cement pastes were calculated from measured evaporable water and varied from about 30 to 45 per cent as water/cement ratios varied from 0.35 to 0.50. Lower water/cement ratios yielded lower porosities. In addition, samples cured at higher temperatures had lower porosities, due to a greater degree of hydration in a short curing time. Porosity decreased with increased hydration. (After longer curing times, however, the degree of hydration for samples cured at a higher temperature is expected to be less than that of samples cured at a lower temperature (Brunauer and Kantro, 1964).)

Permeabilities reported ranged from about 5×10^{-9} to 1×10^{-7} darcy for water/cement ratios of 0.35 to 0.45, cured at 27°C, and 1×10^{-7} to 1×10^{-5} for water/cement ratios of 0.35 to 0.45, cured at

60°C. Lower curing temperatures and lower water/cement ratios resulted in lower permeabilities.

The pore-size distributions in samples with a water/cement ratio of 0.40 cured at 27°C and 60°C were determined by mercury intrusion porosimetry, which only measures pores less than 7.5 microns in radius. The sample cured at 27°C had a peak in the pore size distribution between 7.5×10^{-3} and 14×10^{-3} microns and absence of pores having radii larger than 430 microns. The sample cured at 60°C had two peaks, between 7.5×10^{-3} and 14×10^{-3} microns and between 140×10^{-3} and 230×10^{-3} microns. The values of total pore volumes measured by mercury intrusion porosimetry were less than those measured from the content of evaporable water, reflecting the inclusion of pores having radii greater than 7.5 microns in pore volumes calculated from evaporable water.

Wakeley, Roy, and Grutzeck (1981) conclude that pore structure, rather than total porosity, is the controlling factor for permeability. Samples with substantial volumes of pores with radii greater than 75×10^{-3} microns, that is, those samples cured at 60°C which exhibited a second peak in the pore size distribution measured by mercury porosimetry, had larger permeabilities. It is the interconnected porosity which contributes significantly to permeability.

Investigations concerning the nature and integrity of interfacial regions and rock indicated that the morphology and mode of fracture at the interfacial region between portland cement paste and rock were dependent on both the reactivity of the rock and the degree of hydra-

tion of the cement. The report continues, "A two-layered zone developed in the interfacial region between non-reactive rock (aggregate) and portland cement paste. The interfacial region is characterized by a thin film of silica-containing calcium hydroxide, from which calcium silicate hydrate particles appear to be growing. In addition to the calcium silicate hydrate, larger crystals of calcium hydroxide appear to attach the interfacial region to the bulk matrix material, and thereby the aggregate to the bulk matrix. As the degree of hydration increased, more bulk material became attached to the interfacial region. When the interfacial region was exposed in six month runs it still appeared as a two layer zone. The effect of elevated pressures was to increase the contact between the matrix and the rock surface and, when combined with elevated temperature, to increase also the hydration rate. Surface roughness of the rock resulted in no major effect upon the basic structure of the interface."

Permeabilities of the interface have been estimated. One 18-year old plug of cement in salt yielded a salt permeability of 2×10^{-6} darcy, a cement permeability of 1×10^{-3} darcy, and an interface permeability of 3×10^{-3} darcy.

A further test was performed in which grout was cast against dolostone, forming an interface. Both the grout and the dolostone had shown essentially no flow when tested individually; the sample with the interface showed a permeability of approximately 2.5×10^{-7} darcy. Finally, tests on an expansive grout indicated permeabilities

of less than 1×10^{-8} darcy for samples cured in various aqueous solutions. A sample cured in air and allowed to dry was not tested because of shrinkage which caused a gap between the sample and the ring in which it was cast.

Finally, Roy and Langton (1982) discuss the longevity of borehole and shaft sealing materials. In this study ancient cement-based building materials, some older than 2500 years, were characterized. While longevity was not under consideration in the study discussed herein, it is obviously of concern in the context of long-term waste isolation.

The results obtained by Roy and Langton emphasize the necessity of specifying borehole environmental conditions prior to attempting to extrapolate durability data for cementitious borehole sealing materials on a long-term basis. The temperature, wall rock mineralogy, pore fluid composition, and hydrostatic or lithostatic load should be known. Physical properties of the specific seal material of importance are porosity, permeability, expansion/shrinkage characteristics, and the influence of thermal effects. The phase stability of the borehole sealing material must be considered with respect to pressure, temperature, wall rock, and ground water composition.

Other items of interest are contained in this report. First, some degree of carbonation occurred in the samples studied, increasing as the age of the sample increased. Roy and Langton suggest that, "The extended durability and remarkable longevity of certain ancient

plasters, mortars, and concretes in fact may be at least partially attributed to the development of phase assemblages which include calcite (matrix) plus siliceous aggregates such as quartz."

In addition, crystalline calcium silicate hydrate compounds were not detected in any of the samples analyzed, but particle morphologies generally were better defined in older samples.

Finally, in interfacial regions formed between the matrix material and siliceous aggregates such as quartz, the aggregate surfaces appeared etched and had crystals (primarily calcite) growing on them. Zoned or layered interfacial regions such as those observed in earlier work at The Pennsylvania State University on reactive aggregate surfaces in the early stages of cement hydrations were not observed in this study.

The PSU/WES Interlaboratory Study

In addition to the studies at The Pennsylvania State University (PSU) of portland cement as a repository sealing material, studies are being conducted by the Structures Laboratory of the U.S. Army Engineers Waterways Experiment Station (WES). A comparative study (Roy and Grutzeck, 1980) was performed to determine the ability of these two laboratories to obtain accurate and similar results from tests performed upon the same potential seal materials. Testing included characterization of the materials by chemical, physical, and petrographic procedures. Tests performed on hardened specimens included restrained expansion, compressive strength, modulus of

elasticity, density, permeability, X-ray diffraction, and scanning electron microscopy. It was concluded that there was generally good agreement between the results of the tests performed by both laboratories. At the time of the report, 1980, the experiment was ongoing.

Of the tests performed, of most interest in the present context are those on permeability. PSU performed permeability measurements on samples hydrated for 3 and 7 days. All samples showed no flow to water at a pressure of up to 2.76 MPa for periods up to 94 hours. WES tests were incomplete at the time of the report.

Research at the Waterways Experiment Station

The Structures Laboratory of the U.S. Army Engineers Waterways Experiment Station has been closely involved in the grouting and concreting technology used in underground weapons testing and has continued to be involved in borehole plugging and in other uses of grout and concrete with experiments related to nuclear waste isolation. Much of the work is unpublished, but all is available for reference.

In the context of waste isolation, the Waterways Experiment Station has reviewed approximately 67 laboratory mixtures; 13 are being subjected to long-term physical testing and periodic petrographic examination. Extensive testing indicates that the phase composition and microstructure of the range of materials examined are similar, and each grout tends toward uniformity with time (Buck and Mather, 1982).

Buck and Mather further conclude that control parameters for a grout mixture such as flow time, setting time, compressive strength, and permeability be specified before a grout mixture is formulated and used. In addition, knowledge of the longevity of specific mixtures in the applicable environment is required.

In a related study Rhoderick and Buck (1981) examined five different grout mixtures approximately four years old. Some specimens were stored dry at ambient laboratory temperature, and companion specimens were stored in simulated brine ground water, also at ambient laboratory temperature. Most of both the wet and the dry storage specimens showed cracking for all five mixtures. Rhoderick and Buck attributed this to moisture and/or temperature changes.

Buck, Burkes, and Rhoderick (1981) also observed cracking in specimens obtained from plugs in the ERDA-10 experimental borehole in New Mexico as well as samples of the plug materials cast at the surface when the hole was plugged. They considered the cracks normal for the materials under the storage and test conditions used, and did not believe that similar cracking would occur downhole.

Research at Oak Ridge National Laboratory

Research regarding cement technology for borehole plugging is being conducted at Oak Ridge National Laboratory. This program is discussed in reports by Moore et al. (1979) and by McDaniel (1980).

The overall program was described by Moore, et al. The program was initiated to develop and test cementitious mixtures suitable for

plugging holes in the area of a radioactive waste repository, particularly one in bedded salt. Data were obtained from physical and chemical tests and from parametric studies involving cement/fly-ash concretes and saltcretes¹.

The addition of 10 wt % salt was found to double the initial and final set times. The set time could be increased or decreased by the addition of a lignite fly ash or a bituminous fly ash, respectively.

The compressive strength of cement/fly-ash concrete was found to vary with curing time and depended upon fly ash composition. Saltcrete strengths decreased with increasing salt, but increased if fly ash was added; the effect of fly ash composition was insignificant.

Thermal conductivities of cementitious solids were found to increase with density and with sand and/or salt concentration. Over a temperature range of 30 to 300°C the thermal conductivities of saltcrete decreased with increasing temperature but were almost constant for neat cement pastes. The conductivity values ranged from 0.4 watts/meter-K for a neat cement to 1.8 watts/meter-K for a saltcrete.

Shrinkage of neat cement pastes and saltcretes varied approximately linearly with time, but cement/fly-ash solids exhibited a high

¹Saltcrete is a standard mortar with 10 to 30 wt % salt added. Such a mix is used in the oil industry to bond set cement to salt sections and shales.

rate of shrinkage for the first few weeks, followed by a lower rate of shrinkage for a longer time period.

McDaniel (1980) reported details of the permeability testing. Type I, Class C, and Class H cements were used with a bituminous fly ash and a lignite/subbituminous fly ash. Permeabilities ranged from a high value of 3×10^{-4} darcy for a neat cement paste to a low of 5×10^{-8} darcy for a saltcrete containing 30 wt % salt. Samples were vacuum dried at 100°C, 50 microns pressure and tested using gas. Some samples were subsequently tested using water. Results were similar.

The drying procedure was a critical step in the test procedure. Preliminary results showed that the gas permeability could vary by as much as three orders of magnitude, depending on the drying technique. Air-drying of a cementitious solid results in the loss of water hydration, with possible collapse of gel structure and micro-cracking (Neville, 1973).

Of most interest are data on the permeability of plug-wall rock junctions. Studies were made in which boreholes in 2.54 cm diameter specimens of Westerly Granite, Dresser Basalt, Sioux Quartzite, and St. Cloud Granodiorite were plugged with a mortar containing 23 wt % Type I portland cement, 20 wt % bituminous fly ash, 43.2 wt % sand, and 13.8 wt % water. With the exception of the Sioux Quartzite, the plug-wall rock junctions exhibited water permeabilities of less than 6×10^{-6} darcy after curing for 91 days at ambient temperature and pressure. The Sioux Quartzite specimen, which showed a plug-wall rock permeability of 3×10^{-5} darcy, was believed to have contained a

crack. In order to measure the permeability of the rocks used, thin samples (0.6 cm) were used. At the pressures used for measurements there is a good possibility of altering the internal structure by mechanisms such as gel-pore collapse of the cement. In addition, the plug-wall rock specimens were not dried to a constant weight prior to measurements made with gas. The drying tended to cause cracking at the junction, resulting in extremely high permeability values. McDaniel recommended that larger specimens (on the order of 5 cm in diameter) be used in future tests.

Research at Oak Ridge is continuing, in collaboration with research at The Pennsylvania State University. The long-term objective is to develop cementitious mixes that will form stable solids for use in plugging boreholes in various geologic media at or near waste repository sites. Accelerated test methods will be developed and durability data obtained during the study to demonstrate the high probability of having plug integrities and lifetimes equivalent to those of the repository site.

The research was divided into two tasks. The first was the characterization of initial mixes to be used in borehole plug field tests at the WIPP site. Studies included wet mix properties, properties of the solidified plug, and interaction between the plug and the environment. (Field tests at WIPP have since taken place.)

The second task is long-term studies to develop durable long-lived solids for borehole plugs. Studies are being made on fly ash and saltcretes, water- and friction-reducing admixtures, preparation

of thermodynamically stable solids, development of an accelerated durability test method, and reactivity of plug solids with the environment.

Studies by Woodward-Clyde Consultants for the Basalt Waste Isolation Project

Woodward-Clyde Consultants (WCC), a geotechnical consulting firm, has performed studies regarding plugging of boreholes, shafts, and tunnels for the Basalt Waste Isolation Project (Taylor et al., 1979, and Taylor et al., 1980). For sealing shafts and tunnels natural materials were preferred because they can be shown to have existed for a long period of time. WCC cautions that processed materials (e.g. cement, processed bentonite, pozzolans) have not been shown to be unstable, however. Natural materials considered included basalt, smectite clays, clinoptilolite (a zeolite mineral), and selected aggregates.

Seepage control criteria were emphasized as the most significant design function. The principal design criteria adopted include:

- (1) "Design life of 10,000 years.
- (2) "Maximum seepage through the plug, after saturation, of one cubic meter per year with a 160 meter head across the plug.
- (3) "Maximum credible radioactive waste leakage from the repository at one end of the plug must be reduced to proposed regulatory agency permissible levels at the other end of the plug.

- (4) "Plug must sustain a thermomechanical loading cycle from a 50°C temperature change without compromising other performance criteria.
- (5) "Plug must have suitable bond strength to resist maximum credible axial forces (1,000 m of fluid pressure head)."

Borehole plug design suggested by WCC includes alternately (1) a zone of pea gravel with a mixture of compressed bentonite pellets and bentonite slurry, and (2) a zone of cement grout. The nominal length for all plugs is 300 meters.

Other points of interest in their studies are:

- (1) Placing and compacting materials, inspection of plugs, and quality control are difficult in plugs placed down boreholes. The only available methods at present that have been shown by experiment and practical use to be capable of producing a plug of the necessary characteristics are those of the oil and gas industry.
- (2) At the time of the WCC studies no performance data were available regarding flow rates through plugs or plug stability.
- (3) Possible design criteria for flow considered were (i) allowable seepage would be kept below a maximum annual rate, (ii) seepage travel time through the plug would be specified, (iii) the plug should be able to resist flow at least as well as the intact rock, or (iv) the amount of

radioactive material which could allowably pass through the plug in one year would be specified, taking material sorptive capacities into account.

- (4) Proposed design values of the permeabilities of materials to be used in repository sealing ranged from 1×10^{-7} to 1×10^{-9} cm/sec.
- (5) Plug performance may be divided into five design functions: core barrier performance, plug/wallrock performance disturbed zone cutoff performance, mechanical stability performance, and long-term integrity.
- (6) For long-term integrity, compacted earth and clay slurries are preferred.
- (7) Recommendations for needed research included the need for an early, shallow borehole plugging test, the need for instrumentation data concerning the performance of large excavations in basalt (for shaft and tunnel sealing), and the need to investigate a wider range of potential failure modes such as creep failure of soft plugs, piping, plug solutioning, or dispersion.

Information Base for Waste Repository Design

In 1979 The Analytic Sciences Corporation prepared for the U.S. Nuclear Regulatory Commission a seven volume document on nuclear waste repository design issues entitled "Information Base for Waste Repository Design". Volume 1 of this document, by Koplik, Pentz, and

Talbot (1979) concerns borehole and shaft sealing. The main conclusions regarding borehole sealing were as follows:

- (1) "No method currently exists for ensuring the long-term (thousands of years) performance of the borehole seal. Even when properly placed, borehole seals are likely to deteriorate during the first 1000 years following repository decommissioning.
- (2) "Sealing a borehole for its entire length would reduce the impact of seal failure or deterioration.
- (3) "It is recommended that an unmined pillar of rock be left around boreholes at the repository location to provide an additional barrier to waste transport.
- (4) "Cement appears to offer the best chance of achieving durable borehole seals using existing technology, at an acceptable cost.
- (5) "With the exception of compaction of natural earth material, advanced techniques for sealing borehole such as rock melting or plugging by hydrothermal transport cannot be recommended at this time. The technique of sealing by compaction of natural earth materials still requires considerable test work to demonstrate that satisfactory performance can be achieved."

Two other points are worth noting in this report. First, regarding seal failures, Koplik, Pentz, and Talbot indicate that the

most common cause of seal failure during emplacement is by contamination and/or transport of the seal material by ground water. Failure to achieve seal effectiveness usually results from underestimating the difficulties of emplacement.

Second, failure to match thermal expansion characteristics of the seal with the rock may result in cracking due to temperature loading.

Research at the University of Arizona

Other aspects of borehole sealing have been studied at the University of Arizona by Jeffrey (1981), Cobb (1981), Mathis (1982), and Stormont (1983). Jeffrey studied the mechanical interaction between a shaft or borehole plug and the surrounding rock. He found that if plug and rock mechanical properties are not matched to each other the stresses are less severe when the inclusion is less compressible and stiffer than the surrounding rock, when the applied stress field is hydrostatic, and when the interface condition is welded. Plug and rock materials that display continuous creep must be matched closely in viscous material properties if the development of adverse stress conditions is to be avoided. Because of inherent uncertainties associated with long-term prediction of stresses and rock and plug properties Jeffrey recommended that shafts and boreholes be plugged with multisection seals.

Cobb developed a test facility to determine the effectiveness of borehole plugging materials in rock samples subjected to three independent orthogonal stresses, a true triaxial test. Only a small

amount of experimental data were obtained, but the data collected indicated that varying the applied loads resulted in less than an order of magnitude change in rock permeability for Charcoal Granite. The permeability of a plugged rock sample also varied by less than an order of magnitude. Cobb suggests that the performance of a borehole plug can be estimated with only a minimum knowledge of the in situ stresses around the borehole.

Mathis performed an experimental and theoretical study of the damage induced by percussion and diamond drilling operations. He found that percussion drilling induces more damage than does diamond drilling, but that the width of damage was small and primarily restricted to cracks within grains.

Stormont performed laboratory tests in which cement plugs in model boreholes were pushed out of the borehole to evaluate the mechanical strength of the plug/rock system. The plugs had a high peak strength and a residual strength of 30-50% of the peak strength. Stormont concluded that cement plugs at repository depths will have strengths well in excess of anticipated loads.

CHAPTER 3

EXPERIMENTAL METHODS

The basic approach used to evaluate borehole seals in this work was to compare flow through a sealed borehole in rock with flow through intact rock. Rock cores six inches (15 cm) in diameter and twelve inches (30 cm) long (nominal dimensions) had one inch (2.54 cm) diameter holes drilled from each end, leaving a rock bridge in the center of the specimen, Figure 3.1a. Water pumped into the top hole flowed through the specimen to the bottom hole. Steady-state flow rates were measured. The rock bridge was then drilled from the sample and replaced with a seal and the experiment repeated, Figure 3.1b. This allows direct comparison of flow rate through intact rock with flow rate through the same rock after a small portion has been removed and replaced by a seal.

One of the main areas of interest was the performance of the seal under varying stress conditions. The intact rock specimen was placed under axial and confining stresses approximating a hydrostatic stress field at a depth of about 1000 m. The intact rock was tested, the rock bridge cored from the specimen, and a plug placed and tested while the specimen remained under this stress field. Axial and confining stresses were then lowered to simulate depths of about 600 and 300 m, and flow through the plug/rock system measured. Lowering

a. Sample with rock bridge.

b. Sample with seal
replacing rock bridge.

Figure 3.1 Experimental method: flow through intact rock is compared to flow through sealed rock. Heavy lines indicate no flow boundaries.

the stress field is a more severe condition with respect to the plug/rock interface than raising it because radial stresses across the interface are lessened.

These experiments have direct relevance to the Nuclear Regulatory Commission's (1981) proposed rule regarding the disposal of high-level radioactive wastes in geologic repositories. The proposed rule states in part that, "Shafts and boreholes will be sealed as soon as possible after they have served their operational purpose. At the time of permanent closure sealed shafts and boreholes will inhibit transport of radionuclides to at least the same degree as the undisturbed units of rock through which the shafts or boreholes pass Contact between shaft and borehole seals and the adjacent rock [should] not become a preferential pathway for water Shaft and borehole seals can accomodate potential variations of stress, temperature, and moisture."

The method of investigation was chosen to meet two criteria. First, and most generally, experimental data were desired, as opposed to computer simulation. Measurements on rocks similar to those considered for repository host rocks using currently available seal materials were wanted. This has the advantage of having a rock-plug interface, as opposed to measurements on individual rock cores and individual cement cores.

Second, the method permits simple, straightforward data analysis with few assumptions necessary.

The main disadvantage of the method chosen is that the experiments take a long time to perform.

Intact rock was chosen, as opposed to fractured rock, because a borehole plug seals against the intact zone of a rock mass. That is, the area between joints and fissures is the area in which sealing occurs. Plug material adjacent to a fracture will result in the diversion of fluid reaching that point into the fracture and out of the borehole.

There is, of course, the question of what to consider intact rock. In this work intact rock was considered as rock in which no fractures were visible upon careful examination by the unaided eye.

In the following paragraphs details of the materials, apparatus, and methods used in the experiments are described.

Materials

Five different rock types and two different seal materials were used. Three of the rock types were granite: Oracle Granite, Charcoal Granite, and Catalina Granite. A basalt from the Sentinel Gap area on the Columbia Plateau was tested, and the Topopah Spring Member of the Paintbrush Tuff was tested. Portland cement and bentonite were the two seal materials used.

All petrographic descriptions were provided by Laurel B. Goodwin (1983).

Rock Types

Oracle Granite. The Oracle Granite was obtained by core drilling at a field site near Oracle, Arizona (NW1/4, S15, T10S, R16E, Campo

Bonito Quadrangle, Arizona, USGS 7-1/2' Topographic Map Series). This site is used for field testing of borehole plugs and by the Hydrology Department, University of Arizona, in other aspects of this research.

The Oracle Granite is Precambrian in age and petrologically is a holocrystalline, hypidiomorphic-granular porphyritic quartz monzonite. The porphyritic texture is formed by phenocrysts of potassium feldspar (and possibly perthite) up to 2 cm in size in a medium-grained phaneritic groundmass.

Figure 3.2 is a photomicrograph of the rock. Petrographic examination indicates it is 74% subhedral feldspar, 0.1-2 cm in size. The potassium feldspar is probably microcline with some perthite, and the plagioclase has composition An_9 . The feldspars have been strongly sericitized, but not completely replaced.

In addition the rock contains 20% anhedral quartz, 1-5 mm; 3% chlorite (probably pennine), 0.5-3 mm, which is probably altered biotite; 2% opaque minerals, 0.5-2mm, including some anhedral magnetite and pyrite and some secondary hematite; and less than 1% sphene, 0.5-0.7 mm, and zircon, 0.25 mm.

A distinct set of roughly parallel fractures, about 0.1 mm or less in width cross the slide. The spacing is 1-5 mm. The fractures are filled with an anhedral carbonate mineral which is not identifiable petrographically, but which is probably calcite.

Other signs of deformation include breaking off of small pieces of quartz and feldspar along intergrain boundaries, bending of twin lamellae, strain shadows in quartz and feldspar, and fractures in

Figure 3.2 Photomicrograph of Oracle Granite. Picture is about 2.75 mm across.

quartz, opaque minerals, and feldspars, not necessarily parallel to cleavage.

Finally, the cores of the feldspars seem more altered than the rims. Opaque minerals, probably magnetite, sphene, and sericite occur along (001) in chlorite. Cleavage planes in chlorite are bent and chlorite and sericite may be found as fine anhedral material along grain boundaries.

Table 3.1 presents the physical properties of the rock. The elastic moduli were measured for stresses of up to only 24.1 Mpa, the range in which the rock is stressed in the permeameter. Throughout this range the rock behaved as a linear elastic medium. The specimens used for the moduli determinations were not failed, so the unconfined compressive strength is not available.

Charcoal Granite. Cores of Charcoal Granite were purchased from the Cold Spring Granite Company, St. Cloud, Minnesota. The rock was quarried from their Charcoal Black Quarry, which is in the St. Cloud Gray System. The rock is Precambrian in age.

The rock is a quartz monzonite in composition and is described by the Cold Spring Granite Company as containing 68% feldspar, 18% quartz, 6% biotite, and 6% hornblende.

Figure 3.3 is a photomicrograph of the rock. Petrographic examination indicates the samples obtained for this work are 66-67% feldspar up to 3 mm in size; 18% quartz up to 2.5 mm; 5% anhedral hornblende, 0.3-3 mm; 5% anhedral to subhedral biotite, 0.3-3 mm.; 1% pyroxene, 0.3-3 mm; 2% predominantly subhedral opaque minerals, 0.1-2 mm; and less than 1% subhedral apatite, 0.1-0.2 mm.

Table 3.1 Physical Properties of Oracle Granite

Sample Number	Young's Modulus (MPa)	Poisson's Ratio	Density gm/cc
OAZ-M1-1	60.4×10^3	0.12	2.66
OAZ-M1-2	65.8×10^3	0.16	2.67

Figure 3.3 Photomicrograph of Charcoal Granite. Picture is about 2.75 mm across.

The feldspars are composed of anhedral to euhedral plagioclase (An₁₈₋₁₉) and anhedral to subhedral potassium feldspar, probably microcline. They appear to be fractured in many places and exhibit strain shadows. Some compositional zoning and some seritization, particularly along fractures and cleavages, was observed.

Biotite in many places contains opaque minerals, possibly ilmenite, which appear to be exolved parallel to the cleavage plane (001). Pleochroism indicates the biotite does not contain high amounts of Fe⁺³ or Ti.

The hornblende has characteristic green to brown pleochroism and also contains opaque inclusions. It may occur in clusters and appears to be altering to biotite at the crystal edges.

Apatite is found clustered with mafic and opaque minerals, and may be included in both. Some relict clinopyroxene has been almost completely replaced by hornblende, and includes opaque minerals.

Table 3.2 presents the physical properties of the rock. The elastic moduli were measured for stresses of up to only 24.1 MMpa, the range in which the rock is stressed in the permeameter.

Catalina Granite. The Catalina Granite was obtained by core drilling at a field site near Catalina, Arizona (SE1/4,S25 (unsurveyed), T11S, R14E, Mt. Lemon, AZ, Quadrangle, USGS 15' Topographic Map Series). The site is described in South, et al. (1982).

The samples tested were the fine-grained phase of the Catalina Granite. Figure 3.4 is a photomicrograph of the rock. The rock

Table 3.2 Physical Properties of Charcoal Granite

Sample No.	Young's Modulus (MPa)	Poisson's Ratio	Unconfined Uncompressive Strength (MPa)	Density gm/cc
CG-1	62.46×10^3	0.25	-	2.70
CG-2	58.67×10^3	0.21	-	2.70
CG-3	60.39×10^3	0.12	-	2.72
CG-4	53.84×10^3	0.18	-	2.69
CG-5	47.29×10^3	0.17	-	2.71
CG-101a	-	-	65.90	-
CG-101b	-	-	177.66	-
CG-101c	-	-	131.10	-
CG-102a	-	-	96.23	-
CG-102b	-	-	99.23	-
CG-2000	-	-	169.60	-
Average:	56.53×10^3	0.19	123.31	2.70
Std Dev:	6.07×10^3	0.05	44.18	0.01

Figure 3.4 Photomicrograph of Catalina Granite. Picture is about 2.75 mm across.

contains 75-80% subhedral feldspar, up to 2 mm in size, and 20-25% quartz, up to 1 mm in size. There is about 1% biotite, up to 1 mm, 1% opaque minerals, up to 1 mm, and accessory (less than 1%) chlorite, apatite, sphene, rutile, and zircon. Accessory minerals are 0.1-0.5 mm in size. The feldspars are orthoclase and plagioclase (An_{14}), both of which exhibit some sericitization.

Some of the feldspars exhibit fractures which are not parallel to cleavage; quartz is also fractured in places. Breakage along crystal boundaries is infrequent and the rock is not as deformed as the Charcoal Granite. Some recrystallization has occurred, resulting in overgrowths on quartz and feldspar.

Sentinel Gap Basalt. The samples of basalt tested were all drilled from the same block, which was collected from Sentinel Bluffs, Washington (SE1/4, S15, T15N, R23E, Beverly, Washington, Quadrangle, USGS 7-1/2' Topographic Map Series). The block was collected from the bottom colonnade of flow SG/GR-8(E), as designated on "Sentinel Bluffs Stratigraphic Section, Plate III-3b, Geologic Studies of the Columbia Plateau (Rockwell International, 1979). Both samples were drilled parallel to the axis of the column from which the block came.

The rock is dense, very dark gray to black basalt. Vugs and vesicles are not present. Figure 3.5 is a photomicrograph of the rock. Petrographically it is 50% subhedral, randomly oriented laths of plagioclase (An_{40-60}), 0.1-0.5 mm in long dimension; 32-38% augite, less than 0.5 mm; 3-15% subhedral opaque minerals, less than 0.5 mm, some of which is magnetite; and 2-10% glass. It has an intergranular

Figure 3.5 Photomicrograph of Sentinel Gap Basalt. Picture is about 2.75 mm across.

texture showing laths of subhedral plagioclase with smaller anhedral grains of augite, opaque minerals, and greenish-brown glass in the interstices. Most of the glass is fresh or just beginning to devitrify. The rock is very fresh, shows no deformation, and is fairly homogeneous.

Table 3.3 and 3.4 present the physical properties of the rock. The elastic moduli were measured for stresses of up to only 24.1 MPa, the range in which the rock is stressed in the permeameter.

The basalt tested is in the same group as one of the potential candidate repository horizons at the BWIP, but stratigraphically lower.

Topopah Spring Tuff. Blocks of welded tuff from the Topopah Spring Member of the Paintbrush Tuff were collected from the Nevada Test Site. This tuff is considered a potential candidate repository horizon. The blocks were collected from a surface outcrop in the eastern part of T13S, R49E of the Topopah Spring SW Quadrangle, Nevada (USGS 7-1/2' Topographic Map Series). The outcrop is shown on GQ-439, Geologic Map of the Topopah Spring Quadrangle, Nye County, Nevada (Lipman and McKay, 1965). It is on the south end of the mountain just west of Fortymile Canyon, about 1.5 miles south of VABM Fran. The outcrop is faulted. The blocks collected were loose on the surface, not broken from outcrop.

The Topopah Spring Member of the Paintbrush Tuff is a 700± ft. thick multiple flow compound cooling unit of ash flow tuff. The blocks collected were from the sparse lithophysal zone (Spengler,

Table 3.3 Physical Properties of Sentinel Gap Basalt

Sample No.	Young's Modulus (MPa)	Poisson's Ratio	Unconfined Uncompressive Strength (MPa)	Density gm/cc
SGE-2-1	-	-	-	2.86
SGE-2-2	-	-	-	2.86
SGE-2-3	-	-	-	2.87
UNX-1	11.37×10^6	0.31	-	-
UNX-2	11.91×10^6	0.28	-	-
SGE-2-3-U-C3	-	-	376.83	-
SGE-2-4-U-C2	-	-	274.53	-
SGE-2-2-U	-	-	109.81	-
SGE-2-4-U-C1	-	-	116.08	-
SGE-2-1-U-C1	-	-	252.08	-
SGE-2-3-U-C1	-	-	321.58	-
SGE-2-3-U-C2	-	-	272.95	-
SGE-1-2-U-C1	-	-	384.33	-
SGE-2-2-U-C2	-	-	315.31	-
Average:	11.64×10^6	0.30	296.28	
Std Dev:	0.38×10^6		99.31	

Table 3.4 Brazilian Tensile Strengths, T_0 , Sentinel Bluffs Basalt

Sample No.	Length (cm)	Diameter (cm)	T_0 (MPa)
SGE-2-2-C1-B1	0.806	1.896	33.35
SGE-2-2-C1-B2	0.980	1.895	27.14
SGE-2-2-C1-B3	1.090	1.892	29.93
SGE-2-2-C1-B4	0.948	1.896	25.52
SGE-2-2-C2-B1	1.034	1.890	17.39
SGE-2-2-C2-B2	0.972	1.903	28.93
SGE-2-2-C2-B3	1.214	1.905	28.89
SGE-2-3-C1-B1	0.948	1.901	17.28
SGE-2-3-C1-B2	1.152	1.902	23.84
SGE-2-3-C1-B3	0.955	1.902	27.75
SGE-1-2-C1-B1	0.914	1.902	30.46
SGE-1-2-C1-B2	0.923	1.902	23.87
SGE-1-2-C1-B3	0.828	1.902	28.04
SGE-2-3-C2-B1	0.780	1.902	26.72
SGE-2-3-C2-B2	0.848	1.906	37.14
SGE-2-3-C2-B3	0.983	1.903	22.11
SGE-2-3-C2-B4	0.828	1.904	33.41
SGE-2-3-C3-B1	1.048	1.894	26.82
SGE-2-4-C1-B3	0.990	1.902	27.37
SGE-2-4-C1-B4	0.939	1.903	31.67
SGE-2-4-C2-B1	0.972	1.906	35.75
SGE-2-4-C2-B2	1.025	1.903	30.34
SGE-2-3-C3-B2	0.986	1.898	33.01
SGE-2-3-C3-B3	0.951	1.888	33.12
SGE-2-1-C1-B1	1.008	1.904	37.44
SGE-2-1-C1-B2	1.050	1.905	22.38
SGE-2-4-C1-B1	1.034	1.903	24.16
SGE-2-4-C1-B2	0.926	1.905	32.11
Average			28.43
Std Dev:			5.23

personal communication). The rock is a red-brown devitrified welded tuff with gray-white eutaxitic pumice comprising about 35% of the rock. The pumice is flattened at a ratio of 4:1 to 7:1 and is up to 5 cm in longest dimension. Lithophysal cavities may be several centimeters in size. The rock contains 1-2% lithic fragments, 0.2-1 cm in size.

Figure 3.6 is a photomicrograph of the rock. Petrographically a crystal vitric tuff, it is 35% glass, 60% cryptocrystalline to microcrystalline devitrified material, 5% sanidine, and less than 1% euhedral sphene, hornblende, and anhedral opaque minerals, including hematite.

Glass shards are well flattened and devitrification processes have begun. Crystals radiate perpendicular to shard walls. Fiamme are largely devitrified and are probably flattened pumice fragments. Devitrification in the fiamme consists of fans of microcrystalline material radiating inward from the wall.

The sanidine is anhedral to euhedral and exhibits both baveno and carlsbad twinning. Fine opaque inclusions occur, largely along cleavage planes.

Seal Materials

Cement. The cement used is a proprietary formulation provided by Dowell. It is composed of Ideal Class A cement (Tijeras Canyon) with 50% water content and proprietary Dowell additives D53 (10%), an expansive agent, and D65 (1%), a dispersant. All percentages are

Figure 3.6 Photomicrograph of the Topopah Spring Tuff. Picture is about 2.75 mm across. Lower part is flattened pumice fragment, upper part shows feldspar phenocryst in glassy matrix.

weight percent with respect to cement. The cement was mixed according to American Petroleum Institute specifications (American Petroleum Institute, 1977). Dowell indicates that the slurry has a density of 15.7 lb/gal, a strength of 3800 psi (26.20 Mpa) after 14 days of curing at 110°F (43°C), and 0.18% expansion after 14 days.

Uniaxial compression tests were performed for this research. Results are summarized in Table 3.5. The Young's modulus and Poisson's ratio are secant values at peak strength. The variability of these data suggests they be regarded with caution, but estimates of 10^6 psi for Young's modulus and 0.16 for Poisson's ratio are probably reasonable.

The permeability of Cement System 1 has been evaluated. A sample core 3.80 cm in diameter was prepared in a plastic cylinder sealed on the bottom with rubber gasket material and covered on the top with plastic film. After allowing the cement to cure for 7 days under a pressure of 1 atm and at a temperature of $21 \pm 2^\circ\text{C}$ (ambient laboratory conditions), the core was removed from the cylinder and cut to 3.35 cm in length.

The core was placed in the coreholder of a Ruska liquid permeameter (Figure 3.7). The column of water was kept at a pressure of 1.98 atm.

The test was continued 163 days, at which time 10 ml of water had flowed through the core. An estimate of the permeability has been calculated using the Darcy formula (De Wiest, 1965, eqns. 4.15, 4.20):

Table 3.5 Mechanical Properties of System 1 Cement

Sample No.	Young's Modulus (psi)	Poisson's Ratio	Uniaxial Uncompressive Strength (psi)	Curing time (days)
1	0.97×10^6	0.17	3800	10
2	1.00×10^6	0.15	2390	10
3	1.35×10^6	0.10	7000	7

Figure 3.7 Diagram of Ruska liquid permeameter.
(1) coreholder; (2) column of water;
(3) pressure gauge.

$$K = \frac{\mu VL}{APt} \quad (3.1)$$

where, K = permeability in darcies

μ = viscosity in centipoise

V = volume in cc of water which flowed through the sample

t = time in seconds for the water to flow through the sample

L = length of sample in cm.

A = cross-sectional area of the sample in sq. cm.

P = pressure in atm.

Using this formula, the permeability of Cement System 1 was calculated to be 95×10^{-9} darcy (0.1×10^{-9} cm/sec).

Experiments were performed to measure the expansive stress generated by Cement System 1. Slurry was mixed and poured into three steel pipes of different thicknesses and cured for 16 days. Expansive stresses generated during curing were calculated.

The test was performed under 1 atm pressure and at a temperature of $21 \pm 2^\circ\text{C}$ (ambient laboratory conditions).

The tangential strain on the outside of the pipe was measured with strain gauges. The expansive stress generated by the cement was calculated from the measured tangential strain according to formula derived from Jaeger and Cook (1979, Section 5.11):

$$P = \frac{E\epsilon}{(2R_1^2)/(R_2^2 - R_1^2)} \quad (3.2)$$

where, P = expansive stress

E = Young's modulus

ϵ = induced tangential strain

R_1 = inside radius of pipe

R_2 = outside radius of pipe

Figure 3.8 and Table 3.6 present the results obtained from this experiment. The highest expansive stress generated was 2.26 MPa for the thickest (most rigid) pipe.

Clay. The clay chosen as a seal material was bentonite in tablet form. Bentonite is sodium montmorillonite, a highly swelling clay. The tablet form is a commercial product of the American Colloid Company, Skokie, Illinois, marketed under the name "Volclay Tablet".¹ These are preformed compressed tablets made of high-swelling sodium bentonite which swells up to 15 times its dry volume when hydrated by fresh water. (The performance can be affected by water quality.) The tablets may be dropped through standing water and swell over a 24 hour period. One of the purposes for which these tablets are marketed is, "Sealing abandoned wells, maintaining aquifer yield and head". In practice the tablets are simply tremied to the desired depth.

Physical properties of the tablets are:

Size: 1/2-inch diameter tablet

Density: 2.3-2.5 gm/cc

Composition: Bentonite, a hydrous silicate of alumina comprised essentially of the clay mineral montmorillonite.

¹No endorsement is expressed or implied.

Figure 3.8 Expansive stress vs. time for Cement System 1.

Table 3.6 Expansion Experiment Data - System 1 Cement

Height	Pipe Dimensions (cm)		Thickness	Measured Tangential Strain	Expansive Stress (MPa)	Radial Displacement (cm)
	Outside Diameter	Inside Diameter				
12.50	7.26	6.35	0.46	71×10^6	2.26	6.38×10^{-3}
12.47	7.04	6.32	0.33	82×10^6	2.01	7.04×10^{-3}
12.47	6.71	6.32	0.20	172×10^6	2.04	12.75×10^{-3}

NOTES: (1) Tangential strain measured 16 days before pouring

(2) Tangential strain is approximately equal to half the volume increase of the cement within a plane normal to the sample axis.

Purity: Montmorillonite content about 90% minimum.
Contains small portions of feldspar, biotite,
selenite, etc.

pH: 8.5-10.5

Dry density: 82 lb/cu. ft.

A falling head test (Lambe and Whitman, 1969, p. 281) has been performed to measure the permeability of a plug formed by the bentonite tables under low head.

Fourteen tablets were placed on a rubber stopper inside a 2.54 cm diameter plexiglass tube, covered with distilled water and let stand overnight. The tablets swelled to form a plug about 8.3 cm. long; the top and bottom were somewhat irregular. The rubber stopper was removed and the tube filled with distilled water and covered with a small layer of vacuum pump oil to prevent evaporation. The bottom of the tube was placed in a shallow pan of water. The initial head was 58.7 cm.

After 42 days the head had declined to 57.9 cm and the plug length increased to 14 cm. Permeability of the plug was calculated according to the formula:

$$K = \frac{L \ln(h_0/h_1)}{t} \quad (3.3)$$

where, L = plug length

t = elapsed time

h_0 = initial head

h_1 = final head

This formula yields a permeability of 31×10^{-9} cm/sec (30×10^{-6} darcy) for a plug length of 8.3 cm, and a permeability of 53×10^{-9} cm/sec (50×10^{-6} darcy) for a plug length of 14 cm.

The test was continued, but the water in the bottom pan was allowed to evaporate. Some clay fell from the bottom of the plug, and the plug length shortened to 13.5 cm. After 185 days the head had fallen from 56.6 to 49.7 cm. Calculated plug permeability was 110×10^{-9} cm/sec (100×10^{-6} darcy).

A subsequent test, run for 35 days resulted in a head drop of 49.9 to 48.9 cm. Plug length was still 13.5 cm. The permeability calculated from these data was 90×10^{-9} cm/sec (85×10^{-6} darcy).

Experimental Apparatus

Two main items of apparatus, a permeameter and a constant pressure pump, were designed for this research and four each were constructed by the Central Machine Shop, University of Arizona Instrument Shops. In addition, a data acquisition system was assembled and software written to collect the required data. Design and construction was performed using English units, as is the case in most American machine shops, and English units will be cited in this section where appropriate.

Permeameter Design

An assembly drawing of the permeameter design is shown in Figure 3.9; small black rectangles indicate O-ring seals. The permeameter is

Figure 3.9 Radial permeameter assembly drawing. Small black rectangles indicate O-ring seals.

designed to accept a 6-inch (15.24 cm) diameter, 12-inch (30.48 cm) long cylindrical rock specimen with 1-inch diameter holes drilled along its axis. There is enough travel in the piston to accept samples between 11 inches (27.94 cm) and 12 1/4 inches (31.12 cm) long, using a 1/4-inch (10.64 cm) thick platen at the bottom of the pressure cell. Shorter specimens require a thicker platen. Longer specimens may interfere with the cell cap. The specimen diameter should be as close to 6 inches (15.24 cm) as possible to match the diameter of the piston. Aluminum platens, as indicated on Figure 3.4, are usually closer to the stiffness properties of rock; stainless steel platens were used for most of this work because they are more chemically inert.

A nominal axial stress of up to 21 MPa (3000 psi) may be applied to the rock cylinder by tightening the bolts, forcing the top and bottom plates together. The load applied is measured with a load cell. A loading platen on top of the load cell has a hemispherical top which matches a hemispherical seat in the bottom of the top plate.

Fluid may be pumped into the top hole, the bottom hole, and about the annulus between the rock cylinder and the pressure cell.

(Fittings through the cell to the annulus are not shown on the assembly drawing because they are out of the plane of the section.) Neoprene gaskets are cut as needed from a 1/16-inch (0.16 cm) thick sheet and used to seal the ends of the rock cylinder, isolating the annulus from the top hole and bottom hole. These gaskets are shown as heavy lines on the assembly drawing.

Nominal maximum fluid pressure is 21 MPa (3000 psi). The permeameter was designed to operate at room temperature, but will perform at temperatures of up to 80°C. It may be possible to use even higher temperatures, but additional safety analyses should be performed, particularly if temperatures above the vaporization point of water are involved.

Access to the interior of the specimen is provided by removing the piston plug and the bottom plug. This may be done while the specimen is under an axial stress and, if pressure is maintained about the annulus, under a confining stress.

A centering pin in the bottom plug is used to align the specimen when it is placed in the permeameter; the pin is removed during testing.

The specimen is coated with epoxy on the outside to prevent fluid seepage from the annulus through the rock to the center holes. An axial stress is applied by tightening the bolts and a confining stress applied by pressurizing water in the annulus between the specimen and the pressure cell. At this point, pressure in the top and bottom holes of the specimen may be zero. The neoprene gaskets at the ends of the specimen maintain the confining pressure. Sealing by the gaskets depends upon an axial stress higher than the confining stress. It is not possible to maintain a higher confining stress than axial stress. Using an axial stress of 22.8 MPa it is possible to maintain a confining stress of 19.6 MPa within 2% over a period of 24 hours. The confining stress is applied with a manually operated pump,

which is then disconnected so that there is no supply of water to the annulus. Thus, pressure is either maintained or drops as water leaks through the seals. A pressure drop of 0.01 MPa corresponds to a leakage of about 0.007 cc of water through the seals.

Good sealing will be obtained only if the ends of the specimen are parallel. Care must be taken to ensure parallelism when specimens are prepared, as discussed under sample preparation techniques.

Design Details. The material used to make the permeameter is AISI-4140 steel. This steel has a tensile strength of 145,000 psi (1000 MPa) and a yield point of 131,000 psi (900 MPa). The bolts were heat-treated to obtain a tensile strength of 190,000 psi (1310 MPa). None of the other pieces were heat-treated. SAE Grade 8, 1-inch (2.54 cm) diameter, 14 thread-per-inch nuts are used on the bolts. These have a minimum tensile strength of 150,000 psi (1035 MPa) (Baumeister and Marks, 1967, pp. 8-35, Table 30) and were purchased commercially. The bolts are made by threading a nut on one end of a piece of 1-inch round stock and welding it in place. The other end is then threaded and the bolt sent to be heat treated.

Table 3.7 lists the parts necessary to construct one permeameter. Flareless tube fittings and 1/8-inch diameter high-strength stainless steel tubing are used to connect the permeameter to other equipment. For this work, Hoke Gyrollok brand fittings and needle valves (D3712G2Y) were used. The tubing was 1/8-inch O.D. seamless, annealed 316 stainless steel tubing with an allowable working stress of 12,641 psi (87 MPa) (ASTM A-213). Tubing with a higher working

Table 3.7 Radial Permeameter Parts List

Part	Number Needed	Made From
SAE Grade 8 1" Nuts	18	Purchase commercially
1" Washers	12	Purchase commercially
Bolts	6	1" round stock
Top Plate	1	15-1/4" diameter, 3" thick piece
Bottom Plate	1	15-1/4" diameter, 2" thick piece
Loading Platen	1	1-1/4" thick, 3-1/2" diameter piece
50 Ton Load Cell	1	Purchase commercially
Piston Plug	1	2-1/4" round stock
Piston	1	6-1/4" round stock
Cell Cap	1	7-1/4" O.D. tubing, 0.875" wall
Pressure Cell	1	8-3/4" O.D. tubing, 1-1/4" wall
Bottom plug	1	3" round stock
A-320 O-Ring (for Piston Plug)	2	Purchase commercially
A-331 O-Ring (for Bottom Plug)	1	Purchase commercially
A-358 O-Ring (for Piston)	2	Purchase commercially
A-362 O-Ring (for Cell Cap)	2	Purchase commercially
A-363 O-Ring (for Bottom Plate)	1	Purchase commercially

NOTE: Material used is to be AISI-4140 steel. Parts may be made from any available stock, but stock purchased must be sufficiently over the final dimensions to allow for clean-up and machining. Dimensions given in this table are stock dimensions, not final dimensions.

stress than necessary for safety was used to make the system as rigid as possible (that is, to minimize expansion of the tubing as pressure is applied).

Design calculations were based on a 3000 psi (21 MPa) axial stress applied to a rock cylinder by tightening the bolts and a 3000 psi (21 MPa) fluid pressure.

The highest stresses occur in the bolt threads, which have a factor of safety (FS) of 2.6 assuming a stress concentration on threads of 4 (Spotts, 1971, p. 227) and a single nut. The non-threaded portion of the bolts has $FS = 10.6$.

The top plate, 3" thick (7.62 cm), 15-1/4" (38.74 cm) diameter was designed using formulae from Roark and Young (1975, p. 334, Table 24, Load Case 1a). The loading on the plate was approximated as a line load at the inner circumference of the plate and the bolts were approximated as a simply supported outer edge. This resulted in $FS = 5.9$. The bottom plate 2" (5.08 cm) thick, 15-1/4" (38.74 cm) diameter was designed similarly except that a 3000 psi (21 MPa) stress on a 6-inch (15.24 cm) diameter rock cylinder was approximated as an annular line load of radius 3 inches (7.62 cm). This assumes the plate will tend to rotate about the outer edge of the cylinder. This design has $FS = 5.4$.

The top plate is thicker than the bottom plate because the inner load on the top plate is much more concentrated than the inner load on the bottom plate, resulting in higher bending stresses.

The critical point on the cell cap is at the threads, which hold the cap into the pressure cell. For 3000 psi (21 MPa) exerted upward on the bottom of the cap, FS = 43.1.

The piston plug may also have 3000 psi (21 MPa) exerted upward on its 1-1/2-inch (3.81 cm) diameter base; this results in FS = 78.4. Similarly, 3000 psi (21 MPa) exerted on the bottom plug results in FS = 32.5.

Eighteen 3/8-inch cap screws must resist the force being exerted on the cell cap. This results in FS = 30.8 with respect to the metal in the cylinder. The stress in the cap screws is 16,200 psi (112 MPa), based on a stress-bearing area of 0.0733 square inches (.047 sq cm) (Baumeister and Marks, 1967, p. 8-14, Table 1).

The pressure cell has an outside diameter of 6-3/4 inches (17.15 cm), 1-inch (2.54 cm) thick walls, and an overall length of 16 inches (40.64 cm). It was designed using Equation 174 of Timoshenko (1976, p.208) and has FS = 11.

The critical points of the design are that the rock cylinder must fit in the cell and the O-ring seals must hold 3000 psi (21 MPa) water pressure. The dimensions given above are nominal. Machining to close tolerances is required only for the O-ring seals. Tolerances may be obtained by referring to manufacturer's specifications. The inside of the pressure cell does not have to be machined to close tolerances except at the ends. The top plug, bottom plug, and pressure cell were tapped to accept 1/8-inch NPT (National Pipe Thread) fittings. The bolts were threaded to fit the commercially purchased nuts. All other

threads were 10 threads per inch. Holes were tapped in the top plug, the bottom plug, and the cell cap to accept a spanner wrench. In the case of the cell cap a spanner wrench was made from a piece of pipe. The outside of the permeameters were painted for corrosion resistance. Engine paint resistant to temperatures up to 315°C was used. Parts not painted were cadmium plated.

Steel pallets were constructed on which to place the permeameters, and a pallet truck used to move them about. Holes for lifting are tapped on the top plate for drop-forged eyebolts. The weight of the assembly is about 500 lbs. (230 kg), and access to the bottom is obtained by turning the entire permeameter over when it is assembled, using an overhead crane.

Pump Design

Water must be supplied to a specimen in the permeameter at a constant pressure and a very slow rate. To be able to compare experiments it is desirable to set the pressure at a fixed value and let flow rates be controlled by the permeability of the rock/plug system, as opposed to injecting water at a constant rate and letting pressure fall where it may.

To achieve this a constant pressure pump was designed and four each were constructed by the Central Machine Shop, University of Arizona Instrument Shops. Figure 3.10 is an assembly drawing of the basic pump design.

Figure 3.10 Constant pressure pump assembly drawing. Gas admitted to the top cylinder forces the large piston down, pressurizing water in the bottom cylinder. Pressure intensification is $11\frac{1}{2}$.

The design is quite simple. Compressed nitrogen is supplied to a large diameter cylinder, forcing a piston downward. A smaller piston is thus forced into a cylinder containing water, forcing water out of the bottom of the small cylinder at constant pressure. The fitting connected to the bottom of the water cylinder is connected with tubing to a fitting on the permeameter.

Pressure intensification is approximately 11-1/2. A nitrogen pressure of 200 psi (1.38 MPa) yields a water pressure of 2300 psi (15.86 MPa). At these values the gas cylinder has a factor of safety of 176 and the water cylinder a factor of 34.

The pumps are made of stainless steel, and the safety factors were calculated using a tensile strength of 85,000 psi (586 MPa).

The gas cylinder and water cylinder are prevented from flying apart by eight 3/4-inch (1.91 cm) diameter rods which connect the cylinders by means of flanges welded to their ends. The other end of each cylinder is capped by a round plate held on with cap screws. The capping plates are drilled and tapped for 1/8-inch NPT fittings and use an O-ring to provide a static seal.

At the flange end of the cylinders sliding seals are necessary as the pistons must slide back and forth. Two O-rings, separated by spacers, and a packing nut are used to provide these seals. In the case of the gas cylinder "Bal Seal" brand teflons O-rings are used. Standard teflon O-rings are used to provide the seal on the water cylinder to avoid the use of grease which could contaminate the water.

The pumps have performed well. The main limitation is that constant pressures below about 150 psi (1 MPa) cannot be maintained well because of O-ring friction. O-ring friction is responsible for pressure fluctuations of 10 to 20 psi (0.1 to 0.2 MPa) at higher pressures as well.

The pistons must be precisely machined and the O-ring seals at the cylinder ends require precise machining. However, the cylinders do not require precision machining throughout most of their length; it is sufficient that there is enough clearance for the pistons to travel freely. In addition, the pistons are chromed and the surface finished to a roughness of less than 2 microns to lower friction at the O-rings.

The volume of water pumped must be measured precisely. The piston has a stroke of 10 inches (25.40 cm) and a diameter of 0.980 inches (2.49 cm). A travel of 0.001 inches (0.003 cm) corresponds to a volume pumped of 0.0124 cc. Measurement of distance traveled is made using a linear encoder. The linear encoder is an electronic device which is interfaced with the microcomputer controlled data acquisition system and used to measure piston travel.

Provision is also made on the pumps for mounting a long-range dial indicator which measures to the nearest 0.001 inches (0.003 cm).

Data Acquisition System

Data are collected using an automatic data logging system. A Model PC-100B microcomputer made by Applied Microtechnology, Tucson, Arizona, monitors transducers to measure the necessary values.

The volume of water pumped into the sample is measured by the pump piston displacement with a Heidenhain Pos-Econ Model 501 linear encoder. This digital device connects to a circuit card designed by Applied Microtechnology.

The amount of water flowing out of the sample is collected in a flask which sits on a Gould Model UC-3 force transducer. This analog device is connected to an analog-to-digital voltage converter card in the microcomputer. Reading the force transducer yields the amount of water which has flowed out of the sample. Evaporation is controlled by a thin layer of vacuum pump oil on top of the water.

Fluid pressure is measured using National semiconductor Model LX-1450AF and LX-1460AF pressure transducers. The Model LX-1450AF has a range of 0 - 2000 psi (0-14 MPa) and the Model LX-1460 AF a range of 0 - 3000 psi (0-21 MPa). The lower pressure range is used to measure pressure in the top hole and the higher pressure range to measure pressure in the annulus. The pressure transducers are also analog devices and are connected to the analog-to-digital voltage converter card.

As connected, the linear encoder has an accuracy of 0.0008 inches (0.0020 cm), the force transducers of 0.02 gm, and the pressure transducers of 10 and 15 psi (0.07 and 0.10 MPa) for the LX-1450AF and the LX-1460AF, respectively.

Axial stress is monitored using fifty ton (45,455 kg) capacity load cells. These are not connected to the data acquisition system. Each load cell is connected by a cable and junction box to a strain

indicator unit which, when read, allows the total axial load on a sample to be calculated. Axial stress depends on the exact sample diameter. Loads are accurate to about 90 lbs (40 kg). This equipment was furnished by Terrametrics, Inc., Golden, Colorado.

Experimental Procedure

Sample Preparation and Loading

Six-inch (15.24 cm) diameter samples are obtained either by lab coring of boulders collected from the field or by field drilling. The cylinders obtained are then cut to length, 12 inches (30.48 cm), with a diamond saw and the ends ground flat and parallel.

Grinding is one of the more important steps, as flat, parallel ends are necessary to obtain good end seals and to provide a uniform stress distribution. Sample ends are prepared to specifications set forth by the International Society for Rock Mechanics (1978) for preparing samples for uniaxial compressive strength testing. This specification states that the ends shall be flat to 0.02 mm and shall be parallel to within 0.10 mm in 50 mm. Samples are prepared and flatness and parallelism checked with a dial gauge.

Next, 1-inch (2.54 cm) diameter holes are drilled along the sample axis from each end to a depth of one-third the total sample length. Centering is aided by means of a jig made for this purpose. The holes are drilled with a core drill. When the desired depth is reached the core drill is withdrawn and the core broken off. A blind bit is then used to flatten the bottom of the hole.

In order to prevent seepage of water into the sides and ends of the sample, several coats of epoxy (Scotch Weld Structural Adhesive 2216) are applied. Next, the sample is placed in the permeameter and a small axial load is applied to keep the top plate secure. The permeameter is turned over, the bottom plug removed, and the bottom hole filled with distilled water. Enough water is poured into the bottom hole so that when the bottom plug is replaced, water is forced from the valve, ensuring that no air is entrapped.

The permeameter is righted and connected to a pump, ready for saturation and testing.

Testing

When the sample is first ready for testing it has a rock bridge in place. The testing procedure is to first apply an axial and confining stress and to then apply a vacuum to the top hole. At this time the bottom hole is filled with water and the valve closed. The vacuum draws the air from the top hole and the sample's pore space. Distilled water is then injected into the top hole through a manifold which allows the water to be injected without admitting air to the top hole. Hence, the air has been withdrawn from the sample and water is now being injected to saturate it.

Once the sample has been saturated, as evidenced by water flowing from the bottom hole of the sample at the same rate as it is injected into the top hole, testing begins.

Table 3.8 summarizes the nominal test schedule. With the sample under an axial stress of 23 MPa and a confining stress of 20 MPa, a fluid pressure of 10.0 MPa is applied to the top hole by the constant pressure pump. Flow occurs through the sample to the bottom hole, which is at zero pressure. Flow from the bottom hole is collected in a flask and weighed; flow into the top hole is measured by pump piston displacement.

During the test, axial stress is maintained by the permeameter bolts and confining stress is maintained by fluid pressure in the annulus. No pump is connected to the annulus. Any leakage results in a drop in annulus pressure and is detected by this pressure drop. Annular pressure is kept higher than top and bottom hole pressures.

Following the test at 10.0 MPa top hole pressure, tests are performed at 7.0 MPa and 3.5 MPa to provide data on the variation in flow rate with fluid pressure.

Following the tests at the three different top hole fluid pressures, the rock bridge is cored from the sample. Axial and confining stress are maintained during this operation.

A plug of cement is then placed. The cement is mixed according to American Petroleum Institute specifications (American Petroleum Institute, 1977). A rubber stopper is placed at the location of the bottom of the rock bridge. The cement is then covered with water and allowed to cure.

Following curing the rubber stopper is removed and the same series of tests performed on the rock bridge is performed on the

Table 3.8 Nominal Test Schedule

This table summarizes the nominal test schedule for one experiment on one-rock-type/one-plug-type combination.

Tasks

1. Load permeameters, check seals
2. Saturate, establish flow
3. Test at axial stress = 23 MPa, confining stress = 20 MPa
 - Injection Pressure = 10.0 MPa
 - Injection Pressure = 7.0 MPa
 - Injection Pressure = 3.5 MPa
4. Core out sample, place plug
5. Cure cement
6. Re-establish flow
7. Test at axial stress = 23 MPa, confining stress = 20 MPa
 - Injection Pressure = 10.0 MPa
 - Injection Pressure = 7.0 MPa
 - Injection Pressure = 3.5 MPa
8. Reduce stress; axial stress = 15.0 MPa, confining stress = 13.5 MPa
 - Injection Pressure = 10.0 MPa
 - Injection Pressure = 7.0 MPa
 - Injection Pressure = 3.5 MPa
9. Reduce stress; axial stress = 8.5 MPa, confining stress = 7.0 MPa
 - Injection Pressure = 3.5 MPa
 - Injection Pressure = 1.7 MPa

cement plug. Flow through the plug will thus be directly comparable with flow through the intact rock.

Next the axial and confining stresses to which the sample is subjected are reduced and the test series repeated. This will test the effect of varying stress fields on the plug. Axial stress is reduced to about 15 MPa and confining stress to about 13.5 MPa.

Following this test series axial and confining stress are again reduced, to 8.5 and 7.0 MPa, respectively. To avoid inducing tensile stresses, and to maintain the end seals, injection pressures of 3.5 and 1.7 MPa are used.

CHAPTER 4

EXPERIMENTAL RESULTS

Ten sets of experiments were performed, each taking several months. Nine of the experiments used cement system 1 as the plugging material; bentonite tablets were used in the other one. Data collected were as follows:

- (1) Date: Dates over which data were collected. Each experiment consisted of a sequence of tests at an axial stress/confining stress/top pressure combination. An individual test ususally was performed overnight or even for several days; some tests took only a few hours.
- (2) Elapsed time: Total time test ran.
- (3) Axial stress: Axial stress on the rock sample. Ideally constant, in fact the axial stress varied slightly throughout a test. Values reported are averages. Variation is on the order of 1%, and is linked to variation in confining stress.
- (4) Confining stress: Stress applied about the annulus of a sample. Confining stress varied by about 2%, occasionally more. Usually confining stress decreased as a test proceeded, probably due to slight leakage through the end seals of the sample. Due to the Poisson effect, this caused a smaller decrease in axial stress.

- (5) Top pressure: Pressure at which water is injected into the top hole of the sample. The value shown is the average over the test. Top pressure may vary by 0.1–0.2 MPa due to O-ring friction in the pump. Top pressure may also be referred to as injection pressure in the following text.
- (6) Bottom pressure: Pressure in the bottom hole of the sample. A tube leads from the plug to a flask where water flowing out is collected. The flask is open to the atmosphere, so bottom pressure is always zero (gauge).
- (7) Flow rate in: This is the volume of water injected into the top hole divided by the elapsed time.
- (8) Flow rate out: This is the volume of water flowing out of the bottom hole divided by the elapsed time.

In steady-state conditions the amount of water flowing into the sample should equal the amount flowing out, so that flow rate in equals flow rate out. In these experiments this mass balance was usually within 10%. Discrepancies were due to end seal leakage and to losses when making line connections and disconnections. The confining stress was supplied by a manual pump which was connected to the annulus to replenish water lost by end seal leakage. The water lost resulted in annular pressure drop. The amount of water required to replenish annular pressure was not recorded in the earlier experiments, but was recorded in the later ones. Sometimes the mass

balance was very good if the volume of water added to the annulus to replenish pressure was accounted for, but in some cases this did not totally explain a mass imbalance. Mass balances were generally better at higher flow rates.

The confining stress (water pressure in the annulus) was kept higher than the top pressure and the bottom pressure (bottom pressure was always zero). Thus, leakage could occur from the annulus to the top hole, to the bottom hole, or to both, but no leakage to the annulus could occur. There was no permanently connected pump to replenish annular water, so annular pressure (confining stress) fell when leakage occurred.

If annular water leaked into the top hole and flowed out to the bottom flask, it had to flow through the rock. This resulted in less "flow in water" as measured by the top hole injection pump. In this case the flow rate out is probably closest to the true value, and flow rate in is low. Conversely, if annular water leaked into the bottom hole, it did not flow through the rock. In this case, the flow rate in is closest to the true value and flow rate out is high.

Thus, the flow rate in and the flow rate out bracket the true value of flow rate through the rock when the difference between them is due to annular leakage.

In other cases of mass balance discrepancy water may not be accounted for due to changes in water storage in the rock. In this case the greatest of the in or out values places an upper bound on the true value.

Of course, line leakage will result in water loss. Lines are frequently inspected and little, if any, line losses are expected to have gone unnoticed. In any case, line losses will result once again in the highest flow rate being an upper bound on the true value.

The data collected are presented in tables and graphs. Within the body of this chapter is a summary table of each experiment and a graph of the results. The graph is a least squares fit of a power law curve to the data collected showing variation of flow rate in vs. top pressure at various triaxial stress states.

Details of each experiment are shown in tables presented in Appendix A.

Tests on Cement Plugs

Oracle Granite

A specimen of Oracle Granite was the first one tested. As such, the experiment had as its purpose not only the gathering of data, but also developing experimental procedures. Figure 4.1 shows the specimen configuration. In this first test the specimen was not coated with epoxy, and flow could occur between the annular region and the top and bottom holes.

Tests with Rock Bridge in Place. The first tests were performed with a rock bridge in place. The axial stress was 18.6 MPa. It was quickly apparent that there was rapid hydraulic connection between the top hole of the specimen and the annular space, and the hydraulic connection between the bottom hole and the annulus was much

All dimensions in millimeters.

Figure 4.1 Sample OAZ-M1 - Dimensions.

"tighter". This difference was due to a thin, partially healed fissure, less than 1 mm in aperture, which intersected the top hole, but not the bottom hole. The fissure was barely visible upon visual inspection prior to testing, and was not detected during routine core logging.

The first test performed was to determine the flow rate from the annulus to the top hole of the specimen in convergent flow. The piston plug was removed from the permeameter and the top hole bailed dry. Water was then pumped into the annulus and the time for the top hole to fill was recorded. Flow to the bottom hole was negligible. The results of the convergent flow test are summarized in Table 4.1. The results are presented in the order in which the tests were performed.

It was noted during this phase of the testing that flow occurred mostly through hairline fractures. While watching the water level rise in the top hole during the test, it could be clearly seen that water was seeping into the hole along fine fractures - fractures not discernible when the specimen was first examined. The flow was not a pervasive flow through a medium with random distribution of interconnected pores. Following the convergent flow test the specimen was tested in divergent flow. In this test, fluid was pumped under pressure into the top hole and the amount flowing to the annulus and to the bottom hole was measured. Again, flow to the bottom hole was negligible. Test results are summarized in Table 4.2.

Table 4.1 Oracle Granite - Test results for Convergent
Flow with rock Bridge

<u>Pressure (MPa)</u>	<u>Flow Rate (cc/min)</u>
0.69	0.99
1.72	2.49
2.41	2.98
3.45	3.92
1.03	1.24
1.38	1.61
0.69	0.87

Axial stress = 18.6 MPa

Table 4.2 Oracle Granite - Test results for Divergent
Flow with rock Bridge

<u>Pressure (MPa)</u>	<u>Flow Rate (cc/min)</u>
0.69	15.04
1.38	27.94
2.07	100.26

Axial stress = 18.6 MPa

The flow rates measured in divergent flow are more than an order of magnitude greater than for convergent flow. This is because in convergent flow the fluid pressure induces compressive tangential stresses in the cylindrical specimen whereas in divergent flow tensile tangential stresses are induced. Tensile tangential stresses tend to open fractures and voids, increasing permeability; compressive tangential stresses tend to close fractures and voids, decreasing permeability.

Next the bottom hole was tested in convergent flow. For this test a pressure of 4.83 MPa was applied to both the top hole and the annulus, and no pressure to the bottom hole. In this configuration, flow occurs both radially into the bottom hole from the annulus and axially into the bottom hole from the top hole. The measured flow rate was 0.75×10^{-3} cc/min. This flow rate will be compared to the flow rate under the same test conditions, but with a cement plug replacing the rock bridge.

Tests without Rock Bridge. Following the tests with the rock bridge in place, the bridge was cored from the sample. The specimen then had the shape of a hollow rock cylinder, 30.5 cm long, 15.2 cm in diameter, with a 2.5 cm diameter center hole extending the length of the cylinder.

The specimen was tested under both convergent and divergent flow conditions under an axial stress of 18.6 MPa. The results are summarized in Table 4.3 and 4.4.

Table 4.3 Oracle Granite - Test results for Convergent Flow - Hollow Cylinder

<u>Pressure (MPa)</u>	<u>Flow Rate (cc/min)</u>
0.34	4.17
0.69	7.43
1.03	10.53
0.34	3.41
0.69	6.10
1.03	7.93

Axial stress = 18.6 MPa

Table 4.4 Oracle Granite - Test results for Divergent Flow - Hollow Cylinder

<u>Pressure (MPa)</u>	<u>Flow Rate (cc/min)</u>
0.34	4.33
0.69	8.68
1.03	13.56

Axial stress = 18.6 MPa

The difference in flow rates under convergent flow compared to divergent flow is smaller than expected when considered in conjunction with the test performed on the top hole.

Tests with Cement Plug. Following the tests on the hollow cylinder the center hole of the rock was plugged with Cement System 1, which was covered with water and allowed to cure for three days under atmospheric pressure and at a temperature of 24°C.

In order to place the plug, gravel, water, and a fine wire mesh screen were placed in the bottom of the center hole, filling one-third of its depth. The center third was then filled with the cement, replacing the rock bridge.

The test was performed identically to the test performed by pressurizing the top hole and annulus when the rock bridge was in place. As described previously, a fluid pressure of 4.83 MPa was applied to both the top hole and the annulus, and no pressure to the bottom hole, while the specimen was under an axial stress of 18.6 MPa. When the rock bridge was in place, a flow of 0.75×10^{-3} cc/min was measured.

A flow of 11.53×10^{-3} cc/min was measured in the test on the cement plug, an increase in the flow of more than one order of magnitude compared to the 0.75×10^{-3} cc/min measured when the rock bridge was in place.

Experimental Procedure Modifications. As mentioned above, this Oracle Granite/Cement Plug experiment was the first one performed. It was performed in the prototype radial permeameter. As a result some

modifications were made in the permeameter to facilitate machining, but the permeameter basically performed as expected.

More importantly, modifications were made in the way in which the experiments were performed. This experiment indicated that flow from the annulus to the center holes would likely dominate the flow from the top hole to the bottom hole. Therefore, it was at this point that the decision was made to coat the specimens with epoxy to prevent flow from the annulus, making the outside radius of the sample a no-flow boundary. The ends, which were already sealed with a neoprene gasket, were also coated with epoxy. Thus, the sample was to approximate a right-circular cylinder, the sides and ends of which were no-flow boundaries, the top hole being a flow source, and the bottom hole a flow sink. All subsequent tests used this configuration.

Charcoal Granite

Three samples of Charcoal Granite, CG-101, CG-102, and CG-103 have been tested using cement system 1. All showed similar results: a decrease in flow through the plugged sample as compared to flow through intact rock (sample with rock bridge) at the initial axial and confining stresses. As the axial and confining stresses were reduced, flow through the plugged sample increased. Only when axial and confining stresses were reduced to about one-third their initial values did flow through the plugged sample exceed flow through the intact rock at the initial stress level. The increased flow may have been due to either increased hydraulic conductivity along the

rock/plug interface or due simply to opening of pores and fractures in the rock or the plug as the stress levels decreased.

Flow rates measured during the experiments ranged from 0.5×10^{-3} to 6×10^{-3} cc/min.

Microscopic examination of the cement plug of sample CG-102 revealed a distinct crack along the interface between the plug and the rock. It is believed this crack resulted from drying of the cement during preparation for microscopic examination. It is quite likely that drying of expansive cements will result in shrinkage. Drying of the plug resulted in complete decoupling of the cement from the rock. No bond existed between the cement and the rock. In disks cut from the sample the plug section which had been tightly held in the central hole became loose after only a few days of drying and was retained in the hole only by irregularities left by the drilling operation.

Sample CG-101. The results of this experiment are presented in Table 4.5 and on Figure 4.2. Figure 4.3 shows the sample dimensions. Testing began on January 13, 1982, and was completed on May 13, 1982. The cement plug was poured on January 25, covered with water, and cured at atmospheric pressure until February 5, 1982, a total of 11 days. On April 14, 1982, the annular valve was opened at the wrong time, letting the confining pressure drop to zero. Confining pressure was immediately re-applied. Flow rates subsequently increased to almost four times their previous value, but within three days had returned to the previous values. This occurred at

Table 4.5 Summary of Test Results for Sample CG-101.

		Rock Bridge	Cement 1 Plug				
	σ_{ax} σ_c	22.8 19.7	23.0 19.6	23.0 19.6	15.5 13.8	15.6 13.8	8.5 6.9
	P_t						
Flow Rate In, Q (x 10 ⁻³ cc/min)	10.0	5.69	4.81	2.76		4.27	
	7.0	2.99	1.66	1.48	1.84	2.19	
	3.5	1.34	0.61	0.64	0.73	0.95	2.14
	1.7						0.89
Regression Coefficients	a	0.24	0.05	0.11	0.14	0.16	0.47
	b	1.35	1.90	1.37	1.33	1.40	1.21
	C.C.	0.99	0.96	0.99	1.00	0.99	1.00
	Curve	a	b	c	c	e	f
Flow Rate Out, Q (x 10 ⁻³ cc/min)	10.0	5.77	4.65	2.84		3.91	
	7.0	3.30	1.19	1.50	1.91	2.10	
	3.5	1.48	0.47	0.57	0.65	0.95	2.00
	1.7						0.86
Mass Balance (%)	10.0	1.4	-3.3	2.9		-8.4	
	7.0	10.4	-28.3	1.4	3.8	-4.1	
	3.5	10.4	-23.0	-10.9	-11.0	0.0	-6.5
	1.7						-3.4

σ_{ax} = axial stress (MPa); σ_c = confining stress (MPa); P_t = top hole injection pressure (MPa);
a and b are regression coefficients for the equation $Q = a(P_t)^b$. C.C. is the correlation coefficient.

Figure 4.2 Sample CG-101, flow rate in vs. injection pressure, Charcoal Granite. Solid line indicates rock bridge, dashed lines indicate Cement 1 plug. Letters indicate order of testing.

All dimensions in millimeters

Figure 4.3 Sample CG-101 - dimensions.

axial and confining stresses of 15.5 and 13.8 MPa, respectively, and the flow rates are curves d and e on the graph.

The summary table shows that mass balance magnitudes were 11% or less for all but the 7.0 and 3.5 MPa injection pressures, which had mass balances of about -25%.

Results are best reviewed by studying the graph of flow rate in vs. top pressure (Figure 4.2). Data from tests on the rock bridge are shown as a solid line, curve a. Dashed lines show data from tests on the cement plug. The letters a, b, c, d, e, and f are ordered in time (i.e., a was run first, then b, etc.).

Curve a, flow rate through the rock bridge, is the baseline. Curve b was derived next. It shows a lower flow through the cement plug than the rock bridge under similar axial and confining stresses. Curve c repeats the conditions of curve b. It was derived to check repeatability; obviously, curve c shows a lower flow rate than curve b. This is believed to be due to decreasing cement plug permeability resulting from forcing high pressure water through the plug.

Flow rates decreased from a to b to c. Next, axial and confining stresses were reduced and flow rates increased (curves d and e) as the reduction in stress allowed fractures and pores to open. The difference between curve d and e is due to the abnormal stress placed on the system by mistakenly opening the annular valve on April 14. Even such a severely abnormal stress state did not result in a flow rate greater than through the rock bridge. Only when axial and

confining stresses were reduced to 8.5 and 6.9 MPa, respectively, did the flow rate through the plug/rock system exceed flow through the intact rock.

Details of the testing are presented in Appendix A, Table A.1.

Sample CG-102. The results of this experiment are presented in Table 4.6 and on Figure 4.4. Figure 4.5 shows the sample dimensions. Testing began on January 20, 1982, and was completed on April 14, 1982. The cement plug was poured on February 6, covered with water, and cured at atmospheric pressure until February 13, a total of 7 days. The summary table shows that mass balance magnitudes were less than 17% except for one test at 3.5 MPa top pressure on the rock bridge, which had a mass balance of 25.0%.

Referring to the graph, Figure 4.4, curve a is again the rock bridge and the dashed lines represent tests on the cement plug, ordered temporally by letter. As with CG-101, sample CG-102 showed a reduced flow rate under the same axial and confining stress for the cement plug (curve b) as compared to the rock bridge (curve a), and an even lower rate after high pressure water had flowed through the plug (curve c). Reducing the axial and confining stresses increased the flow rate (curve d), but not until axial and confining stresses were reduced to about one-third their initial values did flow rate through the plug/rock system exceed the initial flow rate through intact rock.

Figures 4.6, 4.7, and 4.8 are photographs of the interface between the granite and the cement plug. After testing, the sample

Table 4.6 Summary of Test Results for Sample CG-102.

		Rock Bridge	Cement l Plug				
	σ_{ax}	22.8	22.9	22.8	15.6	15.6	8.6
	σ_c	19.7	19.6	19.7	13.8	13.8	7.0
	P_t						
Flow Rate In, Q (x 10 ⁻³ cc/min)	10.1	4.79	4.24	2.69	4.77		
	7.0	3.06	1.86	1.57	2.73		
	3.5	1.31	0.78	0.68	1.18	1.05	2.26
	1.7						0.98
Regression Coefficients	a	0.28	0.11	0.13	0.23		0.53
	b	1.22	1.55	1.29	1.30		1.16
	C.C.	1.00	0.97	1.00	1.00		1.00
	Curve	a	b	c	d		e
Flow Rate Out, Q (x 10 ⁻³ cc/min)	10.1	5.38	4.82	2.73	4.52		
	7.0	3.30	2.04	1.70	2.35		
	3.5	1.64	0.92	0.79	1.01	1.06	2.10
	1.7						1.03
Mass Balance (%)	10.1	12.1	12.6	1.4	-5.0		
	7.0	9.1	9.9	9.1	-13.4		
	3.5	25.0	16.6	16.1	-14.4	-1.0	-7.0
	1.7						5.2

σ_{ax} = axial stress (MPa); σ_c = confining stress (MPa); P_t = top hole injection pressure (MPa);
a and b are regression coefficients for the equation $Q = a(P_t)^b$. C.C. is the correlation
coefficient.

Figure 4.4 Sample CG-102, flow rate in vs. injection pressure, Charcoal Granite. Solid line indicates rock bridge, dashed lines indicate Cement 1 plug. Letters indicate order of testing.

Figure 4.5 Sample CG-102 - dimensions.

Figure 4.6 System 1 Cement plug in sample CG-102.

Figure 4.7 Diametric view of cement plug, sample CG-102.

Figure 4.8 Photomicrograph of plug in sample CG-102, showing cement plug, upper, crack believed to be due to sample preparation, and rock, lower.

was removed from the permeameter and submerged in water. On May 12 it was removed from the water and sectioned with an oil-cooled diamond saw. This was completed on May 14. Oil was wiped from the sections and the sections were kept on a shelf at room temperature, open to the atmosphere until the photographs were taken on May 17. Humidity during this time ranged between 5% and 30% (from newspaper weather reports, Tucson Daily Star). On May 14 the samples were examined with a binocular microscope, but no pictures were taken.

Figure 4.6 shows the top half of the plug. The plug was dense and uniform throughout except for a 4.5 mm thick zone of laitance at the top. The small crack at the top right was not noted during the May 14 examination and apparently opened as a result of the dry storage conditions.

Figure 4.7 is a view of the plug in the plane of a disc cut from the sample. The interface appears as a white line with no discernable crack. A photomicrograph of the plug and the rock is shown in Figure 4.8. The crack along the interface occurred during preparation of the thin section.

Details of the testing are given in Appendix A, Table A.2.

Sample CG-103. The results of this experiment are presented in Table 4.7 and on Figure 4.9. Figure 4.10 shows the sample configuration. Testing began on January 28, 1982, and was completed on June 1, 1982. The cement plug was poured on February 13, covered with water, and cured at atmospheric pressure, 21°C, until February 20, a total of 7 days. The summary table shows that mass balance magnitudes were 13%

Table 4.7 Summary of Test Results for Sample CG-103.

		Rock Bridge	Cement 1 Plug			
	σ_{ax}	22.8	22.8	22.8	15.4	8.6
	σ_c	19.6	19.6	19.5	13.7	7.1
	P_t					
Flow Rate In, Q ($\times 10^{-3}$ cc/min)	10.1	5.59	6.17	2.91	5.20	
	7.0	3.25	2.24	1.50	1.94	
	3.4	1.25	0.56	0.54	0.73	2.14
	1.8					0.92
Regression Coefficients	a	0.23	0.04	0.08	0.08	0.42
	b	1.37	2.16	1.53	1.74	1.33
	C.C.	1.00	0.99	1.00	0.96	1.00
	Curve	a	b	c	d	
Flow Rate Out, Q ($\times 10^{-3}$ cc/min)	10.1	6.18	5.76	2.74	5.24	
	7.0	3.51	2.20	1.45	1.94	
	3.4	1.54	0.49	0.61	0.75	2.24
	1.8					0.97
Mass Balance (%)	10.1	10.6	-6.6	-5.8	0.8	
	7.0	8.0	-1.8	-3.3	0.0	
	3.4	23.2	-12.5	13.0	2.7	4.7
	1.8					5.4

σ_{ax} = axial stress (MPa); σ_c = confining stress (MPa); P_t = top hole injection pressure (MPa);
a and b are regression coefficients for the equation $Q = a(P_t)^b$. C.C. is the correlation
coefficient.

Figure 4.9 Sample CG-103, flow rate in vs. injection pressure, Charcoal Granite. Solid line indicates rock bridge; dashed lines indicate Cement 1 plug. Letters indicate order of testing.

All dimensions in millimeters

Figure 4.10 Sample CG-103 - dimensions.

or less except for the 3.5 MPa test on the rock bridge, which had a mass balance of 23.2%.

Test results for CG-103 are similar to those for CG-101 and CG-102. Referring to Figure 4.9, curve a is again for the rock bridge. After plugging, flow rates under the same axial and confining stresses were again less than for the rock bridge, curves b and c. Reducing the axial and confining stresses caused an increase in flow rates, curves d and e. Curves b and c are a plot of test results under the same axial and confining pressures and, as noted for samples CG-101 and CG-102, the decrease in flow rate from curve b to curve c is believed to be due to decreasing cement permeabilities as high pressure water flowed through it.

After steady-state testing was completed, a pulse test was performed on the plugged sample. The objective of this test was to gain familiarity with the test, to determine the time it took to perform, and to evaluate whether it might be useful in comparing plug performance to that of intact rock. Two tests were performed, both under an axial stress of 8.9 MPa and a confining stress of 7.3 MPa.

Test results are presented in Figures 4.11 and 4.12. The first test, on June 9, 1982, was started with the sample at an equilibrium pressure of 2.3 MPa. That is, pressure throughout the sample was 2.3 MPa, with a pressure of 2.3 MPa in both the top and bottom holes. It took 8 days to reach this equilibrium from the established gradient of 1.8 MPa top hole pressure and 0.0 MPa bottom hole pressure.

Figure 4.11 Pulse test data, CG-103, Cement 1 plug, June 9, 1982.

Figure 4.12 Pulse test data, CG-103, Cement 1 plug, June 10, 1982.

At the start of the test, pressure in the top hole was quickly raised to 5.5 MPa and the top valve closed. The bottom valve was already closed. As Figure 4.11 shows, pressure in the top hole decreased much more rapidly than pressure in the bottom hole increased. This occurred as water from the top hole flowed through the rock to the bottom hole. Much of the pressure decay in the top hole was apparently accommodated by water storage in the rock, which is believed to be the reason there was less pressure rise in the bottom hole.

Figure 4.12 shows the results of a second, shorter test performed on June 10, 1982. The results are similar.

Following the pulse tests the top hole pressure was released, dye poured into the top hole, and the top hole repressurized. The dye used was Magnaflux Spotcheck SKL-W Water Washable Penetrant.

Injection took place under an axial stress of 8.9 MPa, a confining stress of 6.8 MPa, and an injection pressure (top hole pressure) of 3.4 MPa. Bottom hole pressure was atmospheric. After ten days a slight coloration from the dye was observed in the flask collecting water from the bottom hole.

The sample was removed from the permeameter and sawed in half lengthwise. In the sectioned sample dye was clearly visible for the first 6 mm on top of the cement plug and for 19 mm along the interface on one side of the 102 mm long cement plug. The dye in the top 6 mm of the plug is interpreted as outlining a zone of laitance.

In order to better see the dye, Magnaflux ZP-9B developer was sprayed on the surface of the specimen. The developer provides a white background against which the red dye is more visible. After spraying on the developer, the dye was seen to have penetrated the plug for 12 mm, being more intense in the top 6 mm. However, the dye was observed throughout the rock, being most apparent in the top of the specimen around the injection hole. Most of the dye had flowed around the plug, through the rock. Dye coloration in the plug, below the top 12 mm, was less than in the rock, indicating more flow through the rock than through the plug. This accords with the observations of reduced flow through the sample after plug emplacement. Figure 4.13 is a sketch of the sample showing dye penetration.

There was little dye along the rock-plug interface, except for that already noted.

Details of the testing are given in Appendix A, Table A.3.

Sentinel Gap Basalt

Two samples of basalt, both drilled from the same block, have been tested using cement system 1 as the plug material. Both samples were drilled parallel to the axis of the column from which the block came.

The samples exhibited very low flow rates when the rock bridge was in place, less than 0.05×10^{-3} cc/min. Since flow rates were so low, their variation with axial and confining stress could not be measured. In addition, flow rates measured were somewhat erratic,

Figure 4.13 CG-103, sketch of dye test. Dye pervaded the rock and penetrated 12 mm into the plug and 19 mm along one side of the interface.

probably reflecting the lower limits of sensitivity of the measuring apparatus.

Flow rates increased greatly after emplacement of the cement plug, to rates on the order of 0.2×10^{-3} cc/min. Flow through the basalt with cement plug is greater than through intact basalt, but still less than the flow rates measured for the Charcoal Granite samples. The erratic nature of the measurements is believed to be due to stick-slip in the pumps, to having to disconnect the water lines the the permeameters several times for gauge calibration, and to leakage from the annulus.

Because of the extremely low flow rates, even very small errors are reflected as major discrepancies in the mass balance. It is probable that the measurement error equals or exceeds the measured values, making the "instantaneous" mass balance fairly meaningless. A glance at the data tables in Appendix A will confirm, however, that even an integrated measurement over the total duration of the experiments, integration which should average out random measurement errors, does not improve the mass balance because the flow out consistently exceeds the flow in. It is probable that this is due to a small leakage flow from the annulus, as is confirmed by a systematic, although very minor, pressure drop in the annulus during the course of the tests. The annulus pressure is "maintained" by an occasional repressurization. Measurements of the water injected into the annulus show that accounting for such annulus injections does not improve the mass balance.

SGE-2-2. The results of the experiment performed on sample SGE-2-2 are presented in Table 4.8 and on Figure 4.14. The sample configuration is shown in Figure 4.15.

The sample was allowed to saturate for seven days with water being injected under pressure in both the top and bottom holes. On May 27, 1982, testing began. The basalt exhibited very low flow rates. With the rock bridge in place and under an axial stress of 22.7 MPa, a confining stress of 19.0 MPa, and an injection pressure of 10.3 MPa, the flow rates in and out were 0.01×10^{-3} and 0.07×10^{-3} cc/min, respectively. A greater flow out was observed throughout the test and is likely due at least in part to slight leakage through the end seals. Since the rock was of very low permeability and had very low flow rates, the slight end seal leakage was a large part of the total flow. The amounts of water pumped into the annulus to replenish pressure were recorded, but this still did not account for the total discrepancy between the amounts flowing into the sample (as measured by the constant pressure pumps) and the amounts flowing out. This is probably due to inaccuracies in the measurement of the water necessary to replenish the annulus. Inaccuracies result because the injection pump used to replenish the annulus has to be used for other purposes, and hence has to be reconnected and disconnected for each replenishment. The slight water losses incurred during this process appear to be a significant fraction of the total flow in this system.

Since flow rates through the sample with rock bridge were so low, at the lower limits of the sensitivity of the equipment, the axial and

Table 4.8 Summary of Test Results for Sample SGE-2-2

	Rock Bridge	Cement System 1 Plug			Cement System 1 Plug After Drying			
σ_{ax} (MPa)	22.7	23.4	14.9	7.5	8.9	9.0	14.5	23.2
σ_c (MPa)	19.0	19.6	13.8	6.9	7.1	7.0	11.0	19.5
P_t (MPa)	10.3	10.2	9.9	6.9	7.0	7.0	10.1	10.0
Q_{IN} ($\times 10^{-3}$ cc/min)	0.01	0.05 [*]	0.06	0.03	52.85 ^a	58.70 ^b	94.87	82.27
Q_{OUT} ($\times 10^{-3}$ cc/min)	0.07	0.24 [*]	0.15	0.12	55.46 ^a	58.85 ^b	96.34	81.90

^{*}Last 10 readings.

^{a,b}Annular pressure released suddenly, then restored, between readings for a and b.

Figure 4.14 Flow rate vs. time, sample SGE-2-2. Arrows indicate (a) cement plug emplacement, 7/7; (b) stress change, 9/14; and (c) stress change, 10/25.

Figure 4.15 Sample SGE-2-2 - dimensions.

confining stresses and injection pressure were not varied. After testing the rock bridge at the single injection pressure of 10.3 MPa for 39 days, the rock bridge was cored from the sample and a plug of cement system 1 emplaced.

The cement plug was tested under axial and confining stresses of 23.4 MPa and 19.6 MPa, respectively, and an injection pressure of 10.2 MPa. The averages of the last ten flow rate measurements were 0.05×10^{-3} and 0.24×10^{-3} cc/min, respectively. This is higher than the intact basalt, but still lower than the measurements for any of the intact or plugged Charcoal Granite samples. Lowering the axial and confining stresses to 15.0 and 13.8 MPa, respectively, resulted in flow rates in and out of 0.06×10^{-3} and 0.15×10^{-3} cc/min, respectively, using an injection pressure of 10.0 MPa. These flow rates are similar to the ones at the higher axial and confining stress level, indicating no measurable variation in permeability with variations in axial and confining stress.

Finally, axial and confining stresses were lowered to 7.5 MPa and 6.9 MPa, respectively, and top injection pressure lowered to 6.9 MPa. Flow rates in and out were 0.03×10^{-3} and 0.12×10^{-3} cc/min, respectively.

The sample was next removed from the permeameter and placed in an oven at a temperature of 54°C for 42 days. This subjected the cement plug both to drying and to higher temperatures. It was removed from the oven and stored at room temperature and ambient humidity for six days before being replaced in the permeameter on Dec. 27, 1982, for

saturation. Testing was resumed on January 12, 1983, and continued until March 16, 1983.

Figure 4.16 presents the test results obtained between January 12 and March 2. During this time the sample was subjected to axial and confining stresses of 8.8 MPa and 7 Mpa, respectively, and 2 MPa injection pressure. The initial flow rate was about 900×10^{-3} cc/min. This decreased to a flow rate of about 15×10^{-3} cc/min, presumably as constituents of the cement rehydrated. The 15×10^{-3} cc/min flow rate obtained for nine days and was considered a limiting value.

Tests were then performed at 8.9 and 7.1 MPa axial and confining stress, respectively, and at an injection pressure of 7.0 MPa. Flow rates in and out were 52.85×10^{-3} and 55.46×10^{-3} cc/min, respectively, column a in Table 4.8. On March 4 the annular pressure was released and annular pressure dropped suddenly to about 4.12 MPa but was quickly restored. Flow rates were then slightly higher, column b.

Tests were then performed at an injection pressure of 10 MPa for (14.5,11.0) and (23.2,19.5) MPa axial and confining stresses, respectively, to compare with similar conditions prior to testing. As Table 4.8 shows, in all cases flow rates through the plug after drying were over two orders of magnitude greater than before drying.

Also worth noting is that the increase of triaxial stress state between columns c and d resulted in a lower flow rate for the higher stress level. Details of the testing are presented in Appendix A, Table A.4.

Figure 4.16 Sample SGE-2-2, flow rate vs. time, Cement 1 plug, after drying, June 12 - March 2, 1983.

SGE-2-3. Results of the experiment on sample SGE-2-3 are presented in Table 4.9 and on Figure 4.17. Figure 4.18 shows the sample configuration.

Testing began on June 13, 1982, and continued until October 14, 1982. At that time dye was injected into the top hole. Flow rates were very low from the start of the test, indicating the intact rock is of very low permeability. With the rock bridge in place a triaxial stress state of about 12 MPa axial stress and 10 MPa confining stress was applied. Measured flow rates under an injection pressure of 9.8 and 7.0 MPa were 0.01×10^{-3} to 0.02×10^{-3} cc/min in and out, respectively. These flow rates are at the lower limits of resolution of the equipment. Since the flow rates were so low it was not considered worthwhile to vary the triaxial stresses and it was also not worthwhile to test at lower injection pressures.

On July 7, 1982, the rock bridge was drilled from the sample and a plug of cement system 1 emplaced and cured seven days with the rock sample under 23.1 MPa axial stress and 19.6 MPa confining stress. The plug was placed and cured under a higher triaxial stress state than that under which the rock bridge was tested to allow variations of the triaxial stresses during plug testing.

As Figure 4.17 shows, flow rates were considerably higher after plug emplacement than through the sample with rock bridge. The average of all data taken after plug emplacement (see Table A.5, Appendix A), 7/19-9/28, gave flow rates of 0.44×10^{-3} and 0.64×10^{-3} cc/min in and out, respectively. However, if only the last 10

Table 4.9 Summary of Test Results for Sample SGE-2-3

	<u>Rock Bridge</u>		<u>Cement System 1 Plug</u>		
σ_{ax} (MPa)	12.3	12.2	23.1	14.5	9.6
σ_c (MPa)	10.2	9.9	19.6	10.4	5.2
P_t (MPa)	9.8	7.0	9.9	10.1	3.4
Q_{IN} ($\times 10^{-3}$ cc/min)	0.01	0.01	0.27*	0.30	0.10
Q_{OUT} ($\times 10^{-3}$ cc/min)	0.02	0.00	0.35*	0.30	0.11

*Last ten readings.

Figure 4.17 Flow rate vs. time, Sample SGE-2-3. Arrows indicate (a) cement plug emplacement, 7/7; (b) stress change, 9/28; (c) stress change, 10/4; and (d) stress change, 10/6.

Figure 4.18 Sample SGE-2-3 - dimensions.

measurements, 8/17-9/28, are considered, flow rates of 0.27×10^{-3} and 0.35×10^{-3} cc/min are obtained. This is probably a better estimate of the long term, stabilized flow rate and it is these values which are presented in the Summary, Table 4.9. If the water pumped to the annulus (4.65 cc) is added to the water pumped into the top hole (15.17 cc) the total (19.82 cc) compares quite well with the amount of water which flowed out of the bottom hole (19.57 cc).

Lowering the triaxial stress state to 15.2 and 10.4 MPa, axial and confining stresses, respectively, had little effect on the flow rate, a value of 0.30×10^{-3} cc/min being obtained for both flow rate in and flow rate out.

As the triaxial stress state was lowered further some problems were encountered with end seal leakage. This was overcome by applying a greater differential between the axial and confining stresses, and the final test was performed at an axial stress of 10.3 MPa and a confining stress of 5.2 MPa. Using an injection pressure of 3.4 MPa, flow rates of 0.10×10^{-3} and 0.11×10^{-3} cc/min in and out, respectively, were obtained.

If it is assumed that flow rate varies linearly with injection pressure then a measured flow rate of 0.10×10^{-3} cc/min at an injection pressure of 3.4 MPa may be extrapolated to a flow rate of 0.29×10^{-3} cc/min at an injection pressure of 10 MPa, similar to the flow rates obtained in the previous tests. This assumes permeability is independent of triaxial stress state, and this seems to be true in the ranges considered in this experiment, at least within the sensitivity of measurement.

In summary, the basalt of SGE-2-3 has a very low permeability, as reflected by the low flow rates. Flow rates after plug emplacement were roughly 30 times that for the intact rock. Decreasing the tri-axial stress state on the plugged sample did not increase the measured flow rate.

Following plug testing, Magnaflux Spotcheck Water Washable Penetrant SKL-W was injected in the top hole for 24 days under a pressure of 5.1 MPa . During this time axial stress was 9.6 MPa and confining stress was 5.2 MPa. Figure 4.19 show the results of this test. The rock has been sprayed with Zyglo ZP-9B developer to highlight the penetrant. The hole is 2.6 cm in diameter and the plug 9.2 cm long. The dye has penetrated a 1.1 cm zone of laitance at the top of the plug and has penetrated along the left interface between the rock and the plug for an additional 0.3 cm. There is some penetration of the rock adjacent to the plug top and some penetration of the very top of the sample around the empty top hole.

In this test the penetrant indicates that the plug-rock interface is a slightly preferential migration path. Invasion of the rock by the penetrant at the plug top and at the sample top is believed due to increased rock permeability at these points due to stress interaction effects between the rock and the plug and between the rock and the loading piston.

Details of the testing are given in Appendix A, Table A.5.

Figure 4.19 Sample SGE-2-3, dye test.

Topopah Spring Tuff

One sample of the Topopah Spring Tuff, designated NTS-TPTS-101, was tested. Results are presented in Tables 4.10 and 4.11, and on Figures 4.20 and 4.21. Figure 4.22 shows the sample dimensions.

This sample contained two lithophysal cavities in the bottom and a steeply dipping joint intersected the bottom part of the sample, Figure 4.23. In addition, a joint which was not throughgoing intersected the middle of the sample. The cavities were filled with epoxy and the sample well coated with epoxy. Nevertheless, annular leakage was a continuing problem with this sample. The sample was unloaded from the permeameter and re-epoxied twice in an effort to correct the leakage. In order to eliminate two interfaces, the stainless steel platens used on the sample ends were epoxied to the sample.

Testing of the rock bridge began on December 18, 1982, and continued until February 24, 1983. The rock bridge was cored from the sample and a cement plug placed on February 25. Testing resumed on March 8.

Results of the rock bridge testing show a decrease in flow rate with increasing triaxial stress state, Table 4.10 and Figure 4.20. Although some annular leakage occurred, the mass balance for this part of the test was generally better than 10% in magnitude.

Resumption of testing after plug emplacement showed greatly increased flow rates, Table 4.11. Flow rates were initially over an order of magnitude greater than for the rock bridge under a similar injection pressure. In addition, annular leakage was higher, great

Table 4.10 Summary of Test Results for Sample NTS-TPTS-101

		<u>Rock Bridge</u>			<u>Cement Plug</u>
		σ_{ax}	8.6	15.7	23.4
		σ_c	6.6	13.2	19.6
		P_t			
Flow Rate In, Q (x 10 ⁻³ cc/min)	10.0		167.15	135.20	
	7.0		101.83	84.38	87.29
	6.1	165.65			
	3.5	72.75	43.48	33.98	
	1.8	37.12			
Regression Coefficients	a	17.37	8.73	6.54	
	b	1.22	1.28	1.32	
	C.C.	0.99	1.00	1.00	
	Curve	a	b	c	
Flow Rate Out, Q (x 10 ⁻³ cc/min)	10.0		166.24	138.62	
	7.0		102.41	88.97	239.42
	6.1	157.75			
	3.5	76.47	49.34	47.22	
	1.8	39.43			
Mass Balance (%)	10.0		-0.5	2.5	
	7.0		0.6	5.4	174.4
	6.1	-4.8			
	3.5	5.1	13.5	39.0	
	1.8	6.2			

σ_{ax} = axial stress (MPa); σ_c = confining stress (MPa); P_t = top hole injection pressure (MPa); a and b are regression coefficients for the equation $Q = a(P_t)^b$. C.C. is the correlation coefficient.

Table 4.11 Test Results for Sample NTS-TPTS-101, Cement System 1 Plug

Date	Elapsed Time (min)	Axial Stress (MPa)	Confining Stress (MPa)	Top Pres-sure (MPa)	Bottom Pres-sure (MPa)	Flow Rate In ($\times 10^{-3}$ cc/min)	Flow Rate Out ($\times 10^{-3}$ cc/min)	Notes	V _A (cc)	V _I (cc)	V _O (gm)
Plug placed 4:47 pm, 15 Feb 83.											
3/8	10	18.9	7.0	7.0	0	6178.00	6218.00		0.90	61.78	62.18
3/8	13.72	18.9	7.0	7.0	0	5000.00	5084.55		1.00	68.60	69.76
3/8	42.13	19.0	7.0	7.0	0	2026.58	2073.58		1.14	85.38	87.37
3/8	37.19	19.1	7.6	7.0	0	1684.05	1898.09		NR	62.63	70.59
3/18	92.26	19.1	7.6	7.0	0	564.71	695.10		11.04	52.10	64.13
3/22	97.03	19.1	7.6	7.0	0	367.82	543.44		15.90	35.69	52.73
3/23	99.07	19.2	7.6	7.1	0	363.68	504.49		13.18	36.03	49.98
3/24	136	19.1	7.6	7.0	0	373.38	487.13		15.24	50.78	66.25
3/28	159	19.1	7.6	7.1	0	251.51	369.18		17.39	39.99	58.70
3/30	78	19.1	7.6	7.1	0	145.38	290.26		10.61	11.34	22.64
4/1	138	19.1	7.6	7.1	0	126.81	236.74		13.53	17.50	32.67
4/8	<u>155</u>	<u>19.1</u>	<u>7.6</u>	<u>7.0</u>	<u>0</u>	<u>87.29</u>	<u>239.42</u>		<u>24.56</u>	<u>13.53</u>	<u>37.11</u>
TOTALS:									124.49	535.35	674.11

NOTES:

- V_A = volume of water added to annulus
- V_I = volume of water pumped into top hole
- V_O = volume of water flowing from bottom hole

Figure 4.20 Sample NTS-TPTS-101, flow rate in vs. top pressure for rock bridge.

Figure 4.21 Sample NTS-TPTS-101, flow rate vs. time, Cement System 1 plug.

Figure 4.22 Sample NTS-TPTS-101 - dimensions.

Figure 4.23 Sample NTS-TPTS-101, showing fractures and lithophysal cavities. Center hole diameter is 26 mm.

enough that water had to be continually supplied to the annulus to maintain confining stress.

Four individual tests were performed on March 8. Tests were then performed for durations of up to 159 minutes at intervals of a few days. When not being tested the sample was left in the permeameter under a hydrostatic pressure of about 7 MPa (i.e., confining stress, top pressure, bottom pressure, and pressure throughout the rock were all 7 MPa). Overall mass balance was 25.9%, calculated using simply the amount of water pumped in and the amount flowing out. If the amount added to the annulus is included in the amount pumped in, mass balance is about 2%.

The first test performed on March 8 had a flow rate of about 6200×10^{-3} cc/min. By the fourth test on March 8 this had declined to about 1750×10^{-3} cc/min. Figure 4.21 presents the measured flow rates for the cement plug, starting with the fourth test of March 8.

The measured flow rates decreased markedly with time. The last values measured, 87×10^{-3} and 239×10^{-3} cc/min, April 8, are plotted on Figure 4.20 with the rock bridge curves. Flow rates at this time were of the same order of magnitude as for the intact rock.

Following the test on April 8 the sample was removed from the permeameter of examination. There were two pinhole leaks in the epoxy, explaining the annular pressure loss. Since annular pressure was being maintained at 7.6 MPa, communication with the top hole should have caused top pressure to increase. Since it did not it may

be inferred that the annular leakage was through the sample to the bottom hole.

Details of the testing are given in Appendix A, Table A.6.

Catalina Granite

Two samples of Catalina Granite were tested, CCR-P-100 and CCR-D-100. The first, CCR-P-100, had a 3.9 cm diameter center hole which was percussion drilled in the field. This sample was obtained by over-coring with a diamond bit. Sample CCR-D-100 was 15.2 cm diameter core diamond drilled in the field which had holes drilled into each end in the laboratory with a diamond bit, leaving a rock bridge in place.

Sample CCR-P-100. Figure 4.24 shows the sample dimensions.

Since the center hole was percussion drilled in the field, there was no rock bridge to test. The sample was plugged with System 1 Cement, which was cured 24 days.

Table 4.12 shows the test results. The sample was first tested at axial and confining stresses of 7.7 and 2.0 MPa, respectively, Measured flow rates in and out were 8.73×10^{-3} and 7.84×10^{-3} cc/min, respectively.

The sample was then removed from the permeameter and the plug allowed to dry for 27 days at a temperature of 21°C. Humidity was 50-70% the first six days of drying and 35-40% thereafter. The sample was then reloaded in the permeameter and the plug tested again. This time measured flow rates in and out were 11.91×10^{-3} cc/min and 12.09×10^{-3} cc/min, respectively. The measured flow rates for the dried

Figure 4.24 Sample CCR-P-100 - dimensions.

Table 4.12 Test Results for Sample CCR-P-100

Date	Elapsed Time (min)	Axial Stress (MPa)	Confining Stress (MPa)	Top Pressure (MPa)	Bottom Pressure (MPa)	Flow Rate In ($\times 10^{-3}$ cc/min)	Flow Rate Out ($\times 10^{-3}$ cc/min)	Notes	V _A (cc)	V _I (cc)	V _O (gm)
Cement 1 Plug, Before Drying											
8/3-8/3	423	7.9	2.0	2.0	0	10.35	9.60		0.00	4.38	4.06
8/3-8/4	1070	7.8	2.0	2.0	0	8.67	8.23		0.26	9.28	8.81
8/4-8/4	346	7.8	2.1	2.0	0	2.86	5.61		0.00	0.99	1.94
8/4-8/5	1076	7.8	2.1	2.1	0	9.40	7.27		0.00	10.11	7.82
8/5-8/5	265	7.8	2.1	1.9	0	8.34	8.38		0.00	2.21	2.22
8/5-8/6	1219	7.8	2.1	1.9	0	7.91	NR	a	0.00	9.64	NR
8/6-8/7	1313	7.7	2.0	2.1	0	8.40	7.82		0.00	11.03	10.27
8/7-8/9	2704	7.7	2.0	1.9	0	7.27	7.17		0.00	19.60	19.33
8/9-8/10	1466	7.7	2.0	2.2	0	NR	8.10	a	0.00	NR	11.88
8/10-8/11	1362	7.8	2.0	2.2	0	10.79	8.58		0.00	14.69	11.68
8/11-8/12	1476	7.7	2.0	2.1	0	10.36	8.45		0.11	15.29	12.47
Weighted Averages:		7.7	2.0	2.0	0	8.73	7.84	b			
								Totals:	0.37	97.22	90.48
Cement 1 Plug, After Drying											
9/10-9/11	1386	7.5	2.2	1.9	0	11.93	10.49		0.00	16.54	14.54
9/11-9/12	1157	7.5	2.2	1.8	0	10.82	11.31		0.00	12.52	13.08
9/12-9/13	1318	7.5	2.1	1.8	0	10.86	11.39		0.00	14.31	15.01
9/13	387	7.5	2.1	1.8	0	10.72	12.79		0.00	4.15	4.95
9/13-9/14	1087	7.5	2.1	1.7	0	10.71	10.95		0.00	11.64	11.90
9/14-9/15	1365	7.4	2.1	1.7	0	10.53	11.00		0.00	14.37	15.01
9/15-9/15	250	7.4	2.1	1.7	0	10.44	NR	a	0.00	2.61	NR
9/15-9/16	1082	7.4	2.1	2.1	0	NR	13.61	a	0.00	NR	14.73
9/16-9/16	476	7.4	2.1	2.1	0	NR	13.68	a	0.00	NR	6.51
9/16-9/17	1040	7.4	2.0	1.9	0	12.15	12.55		0.00	12.64	13.05
9/17-9/18	1572	7.4	2.0	2.0	0	14.04	14.08		0.38	22.07	22.14

Table 4.12 Test Results for Sample CCR-P-100--Continued

Date	Elapsed Time (min)	Axial Stress (MPa)	Confining Stress (MPa)	Top Pressure (MPa)	Bottom Pressure (MPa)	Flow Rate In ($\times 10^{-3}$ cc/min)	Flow Rate Out ($\times 10^{-3}$ cc/min)	Notes	V _A (cc)	V _I (cc)	V _O (gm)
9/18-9/19	1320	7.4	2.1	2.1	0	14.02	NR	a	0.00	18.50	NR
9/18-9/20	2818	7.4	2.1	2.1	0	NR	14.30	a	0.00	NR	40.30
9/20-9/21	1401	<u>7.4</u>	<u>2.1</u>	<u>2.1</u>	<u>0</u>	<u>13.80</u>	<u>14.13</u>		<u>0.00</u>	<u>19.34</u>	<u>19.80</u>
Weighted Averages:		7.5	2.1	1.9	0	11.91	12.09	b			
Totals:									0.38	148.69	191.02
Begin Dye Injection											
9/22-9/23	1161	7.0	1.9	1.9	0	2.23	1.98		0.90	2.59	2.30
9/23-9/28	7343	7.0	1.9	1.8	0	0.79	0.78		0.55	5.78	5.76
9/28-9/29	1370	7.0	2.1	2.2	0	0.58	NR		0.00	0.79	NR
9/29-9/30	932	7.0	2.0	2.2	0	0.69	NR		0.00	0.64	NR
9/30-10/4	5832	7.0	1.9	2.1	0	0.65	0.63		0.38	3.79	3.70

NOTES:

- (a) Datum not included in average.
- (b) Averages weighted with respect to elapsed time.

NR = Not recorded

V_A is volume of water added to annulus.
V_I is volume of water pumped into top hole.
V_O is volume of water flowing from bottom hole.

plug were slightly higher than for the plug initially, but still of the same order of magnitude. These data indicate that drying impairs plug performance.

Following the flow measurements, Magnaflux Spotcheck Water Washable Penetrant, SKL-W (a red-colored dye) was injected into the top hole of the sample. Figure 4.25 shows the results of this test. The sample half on the left shows the rock and the darker dye patches. The sample half on the right has been sprayed with a white developer, Magnaflux Zyglo ZP-9B, which highlights the red dye. The dye has penetrated a 1.1 cm thick zone of laitance at the top of the cement plug but has neither penetrated the main body of the plug nor penetrated along the rock-plug interface.

Details of the testing are given in Appendix A, Table A.7.

Sample CCR-D-100. Figure 4.26 shows the dimensions of this sample. Holes 3.8 cm in diameter were drilled from each end of the sample to provide a sample with rock bridge. The 3.8 mm diameter holes were used for compatibility with Sample CCR-P-100. Following testing with the rock bridge in place a 2.5 cm diameter hole was drilled, using a diamond core bit, through the rock bridge and a plug of cement emplaced.

Results of the testing are presented in Table 4.13 and on Figure 4.27. Testing began on October 10, 1982, and was completed on April 8, 1983. The cement plug was poured on January 18, 1983, covered with water, and cured at atmospheric pressure until February 3, 1983, a total of 16 days. Mass balances were generally better than 5% in

Figure 4.25 Sample CCR-P-100, dye test, showing greater penetration of the rock than the plug. The dye has penetrated a 1.1 cm thick zone of laitance at the top of the cement plug, but has neither penetrated the main body of the plug, nor penetrated along the rock-plug interface.

All dimensions in millimeters.

Figure 4.26 Sample CCR-D-100 - dimensions.

Table 4.13 Summary of Test Results for Sample CCR-D-100

	σ_{ax} σ_c	<u>Rock Bridge</u>			<u>Cement Plug</u>		
		8.5 7.0	15.3 13.8	23.1 19.7	23.1 19.7	15.3 13.8	
	P_t						
	10.0		76.96	53.12	36.68	45.72	
Flow Rate In, Q (x 10 ⁻³ cc/min)	7.0	78.88	50.99	36.28	26.17	30.15	102.71
	3.5	36.57	24.72	17.74	13.52	14.01	30.11
	1.6	15.85					11.30
Regression Coefficients	a	9.47	6.38	4.79	4.11	3.42	5.28
	b	1.09	1.08	1.04	0.95	1.12	1.49
	C.C.	1.00	1.00	1.00	1.00	1.00	0.99
	Curve	a	b	c	d	e	f
	10.0		76.96	52.87	36.73	45.35	
Flow Rate Out, Q (x 10 ⁻³ cc/min)	7.0	75.38	50.83	36.57	26.05	29.79	103.13
	3.5	37.78	24.40	17.82	13.75	14.02	26.76
	1.6	12.71					8.11
	10.0		-4.1	-0.5	0.1	-0.8	
Mass Balance	7.0	-4.4	-0.3	0.8	-0.5	-1.2	0.4
(%)	3.5	3.3	-1.3	0.5	1.7	0.1	-11.1
	1.6	-1.3					-28.3

σ_{ax} = axial stress (MPa); σ_c = confining stress (MPa); P_t = top hole injection pressure (MPa); a and b are regression coefficients for the equation $Q = a(P_t)^b$. C.C. is the correlation coefficient.

Figure 4.27 Sample CCR-D-100, flow rate in vs. injection pressure. Solid lines indicate rock bridge, dashed lines indicate Cement 1 plug. See Table 4.13 for triaxial stress state of each curve.

magnitude, but were higher at the lowest triaxial stress state and low injection pressures.

This sample behaved similarly to the Charcoal Granite samples. In Figure 4.27 the solid lines are for testing with the rock bridge in place and the dashed lines represent results from the cement plug testing. As the triaxial stress state on the sample with rock bridge is increased the flow rate lessens as pores and fissures are closed (see discussion for CG-104, below). Upon plugging, flow rates are even lower, indicating the plug is less permeable than the rock. Only when the triaxial stress state is lowered to its lowest value does flow through the plugged sample exceed flow through the intact rock, and only at the higher injection pressures.

Tests on Bentonite Plugs

One specimen of Charcoal Granite, Sample CG-104, was tested using bentonite tablets as the plugging material. It was first tested with a rock bridge in place at different axial and confining stresses to measure the variation in flow rate at different triaxial stress states for the intact rock. Subsequently, three clay plugs were tested. Table 4.14 is a summary of the data collected during the experiment and Figures 4.28 and 4.29 present the data graphically. Figure 4.30 shows the sample dimensions. Table A.9 in Appendix A presents the details of the test.

The solid lines on the figures indicate flow rate vs. top pressure for the intact rock. Increased flow occurs at lower triaxial

Table 4.14 Summary of Test Results for Sample CG-104

	σ_{ax} σ_c	<u>Rock Bridge</u>			<u>First Clay Plug</u>	
		8.6 6.9	15.4 13.7	23.0 19.6	22.0 17.8	20.9 12.4
	P_t					
Flow Rate In, Q (x 10 ⁻³ cc/min)	10.0		19.35	8.44		
	7.0		11.08	4.66		
	3.8					0.15
	3.4	11.67	4.85	1.93		
	1.6	4.02				
	1.0				0.34	
Regression Coefficients	a	2.07	1.01	0.36		
	b	1.41	1.26	1.34		
	C.C.	1.00	0.99	0.99		
	Curve	a	b	c	d	e
Flow Rate Out, Q (x 10 ⁻³ cc/min)	10.0		19.83	8.65		
	7.0		11.65	4.74		
	3.8					1.27
	3.4	11.75	5.05	2.03		
	1.6	4.09				
	1.0				2.04	
Mass Balance (%)	10.0		2.5	2.5		
	7.0		5.1	1.8		
	3.8					
	3.4	0.7	4.1	5.2		
	1.6	1.7				
	1.0					

σ_{ax} = axial stress (MPa); σ_c = confining stress (MPa); P_t = top hole injection pressure (MPa);
a and b are regression coefficients for the equation $Q = a(P_t)^b$. C.C. is the correlation coefficient.

Table 4.14 Summary of Test Results for Sample CG-104--Continued

		Second Clay Plug	Third Clay Plug			
σ_{ax} σ_c		22.7* 19.1*	21.0 14.1	20.8 12.2	12.3 5.9	
<hr/>						
	P_t					
Flow Rate In, Q (x 10 ⁻³ cc/min)	2.0	1.98				
	1.9		2.20			
	1.5	1.42				
	1.3					0.24 = k ₂
	1.2		1.40			
	1.0			0.88	2.65 = k ₁	
	0.5			0.51		
		f	g	h	k	
<hr/>						
Flow Rate Out, Q (x 10 ⁻³ cc/min)	2.0	1.87				
	1.9		2.19			
	1.5	1.57				
	1.3					0.26
	1.2		1.51			
	1.0			0.93		
	0.5			0.55		

*Average for tests made 10/23-11/10 and 11/10-11/13

σ_{ax} = axial stress (MPa); σ_c = confining stress (MPa); P_t = top hole injection pressure (MPa); a and b are regression coefficients for the equation $Q = a(P_t)^b$. C.C. is the correlation coefficient.

Figure 4.28 Sample CG-104, flow rate in vs. injection pressure, Charcoal Granite. Solid lines indicate tests on rock bridge. Triangles and circles indicate tests on bentonite plug for both flow rate in and flow rate out. Letters indicate order of testing.

Figure 4.29 Sample CG-104 test results on second and third clay plugs (dots and dashed lines; solid lines are for rock bridge).

All dimensions in millimeters.

Figure 4.30 Sample CG-104 - dimensions. Clay plug formed of bentonite tablets placed on 3 mm diameter glass beads. Mirafi 140N filter at top and bottom of glass bead column.

stress levels, probably as a result of microfissures widening in the rock. (This variation in flow rate with triaxial stress state in intact Charcoal Granite will be compared with that in plugged Charcoal Granite in the next chapter.)

Following the intact rock testing the rock bridge was cored from the sample and a clay plug emplaced using bentonite tablets. Figure 4.30 shows a sketch of the plug. Ten bentonite tablets ("Volclay Tablets", American Colloid Company) were dropped through water on top of a column of 3 mm diameter glass beads in the bottom hole. Mirafi 140N filter cloth was placed at the bottom and top of the glass bead column. After swelling two days the plug was 109 mm long. On 8/22/82 a top pressure of 2 MPa was placed on the clay plug. The plug would not hold this pressure so the pressure was lowered to zero (gauge) and the plug allowed to stand overnight. The plug was then able to hold 0.1-0.3 MPa. No data were collected at this time due to equipment problems. Some piping of the clay occurred throughout the test.

On 9/1 a top pressure of about 1 MPa was placed on the plug and the plug tested for two weeks. The test results for this period are represented by points d on Figure 4.28. Flow rates are of the same order of magnitude as for intact rock. During this test there was considerable leakage from the annulus. On 9/15 the annular pressure was lowered and the test continued.

The results of the test at a lower annular pressure are represented by points e. Even though the triaxial stress state for points e is lower than for curve c for intact rock, the flow rate

through the plugged sample is less than the flow rate through the rock bridge (i.e., points e fall below curve c).

On 9/18 leakage from the annulus increased the pressure on the clay plug until the plug failed by excessive piping at a top pressure of 4.2 MPa. The plug was allowed to stand two days at zero pressure (gauge); upon reloading it again failed by excessive piping at 2.0-2.5 MPa.

The sample was removed from the permeameter. The clay had been forced down into the void space of the glass bead column. The clay was carefully cleaned from the sample and the sample placed back in the permeameter.

On 10/12/82 the second clay plug was placed. Glass beads were used to fill the bottom hole, as before, but a filter layer using 200 mesh brass screen and filter paper was placed on top of the beads. The purpose of the brass screen was to provide strength. Ten bentonite tablets were allowed to swell eleven days to form the plug.

The results of testing this second clay plug are shown on Table 4.14 and as curve f on Figure 4.29. Flow rates through the plugged sample were higher than, but within the same order of magnitude as, flow rates through intact rock at a similar triaxial stress state. The second plug also failed by excessive piping.

The sample was again removed from the permeameter and the clay cleaned from the sample. In order to observe what happened to the ends as the sample was loaded it was placed in a uniaxial compression machine and stressed to 14.19 MPa. Subsequently, probably as a result

of this loading, a hairline fracture was observed in the top half of the sample, Figure 4.31. The fracture extended halfway down the sample and cut the top along a diameter.

Since a clay plug would extend across the bottom of the fracture a new plug was installed. Glass beads were again used to fill the bottom hole. Two pieces of 200 mesh stainless-steel screen and three pieces of Whatman GF/F filter paper were placed on the glass beads and ten Volclay Tablets used to form the plug. This time the tablets were allowed to swell three days.

The test results for this third clay plug are also shown in Table 4.14. Curves g and h, Figure 4.29, indicate flow rates at axial and confining stresses of (21.0,14.1) and (20.8,12.2) Mpa, respectively. Lower confining stress was applied than in previous tests to prevent annular leakage. Again, flow rates were of the same order of magnitude as for intact granite. The plug was allowed to sit under zero top pressure for eight days between tests g and h.

Lowering the triaxial stress state to 12.3 MPa axial stress and 5.9 MPa confining stress resulted in increased flow, K1. Allowing the plug to sit under zero pressure for three days resulted in reduced flow, K2.

Upon removal from the permeameter the third clay plug was seen to have been forced down into the bottom third of the specimen. The plug extended from a depth of 153 mm below the sample top to the sample bottom. This probably occurred between 12/22/82 and 1/8/83, when the top pressure was increased from 1.2 to 2.0 MPa. The plug failed by

Figure 4.31 Fracture in CG-104. Scale is 1 mm per division.

piping, probably on 1/8/83, and top pressure was reduced to zero so the plug could reswell. This is the time between curves g and h.

CHAPTER 5

ANALYSIS OF EXPERIMENTAL RESULTS

Experimental results have been analyzed using FRESURF I, a finite element model used to solve both two dimensional and axisymmetric flow problems (ONWI-78, 1981). The program was obtained from Dr. Shlomo P. Neuman (1976), Hydrology Department, University of Arizona, Tucson, and is discussed in Neuman and Witherspoon (1970).

The finite element mesh used is shown in Figure 5.1. This mesh is for a sample, six inches (15.24 cm) in diameter, twelve inches (30.48 cm) long, and with top and bottom holes one-third the sample's length. In practice the mesh is adjusted slightly to match individual sample dimensions.

The sample was modeled as two materials, the rock and the plug. If the sample with rock bridge case was being modeled, permeability of the two materials was kept equal. Both the plug and the rock were assumed to be isotropic and homogeneous. The side and ends of the sample are no-flow boundaries (heavy lines in Figure 5.1). The boundaries of the top and bottom holes are constant-head boundaries, the top hole at the head matching the injection pressure, the bottom hole at zero (gauge). The exact manner of calculation is most easily explained by an example, and is discussed in the next section for Charcoal Granite Sample CG-101.

Figure 5.1 Finite element mesh used with program FRESURF I to simulate radial permeameter tests of rock bridge and plug flow rates. Plug position and length adjusted as appropriate for specific calculations. Heavy lines are no-flow boundaries.

Analysis of Tests on Cement Plugs

Charcoal Granite

Sample CG-101. Analysis is performed by first calculating the rock permeability. In order to use FRESURF I, permeabilities must be input; the program calculates flow rates and heads. Figure 5.2 shows the results of such a calculation. The flow rate as a function of permeability was calculated for the sample geometry of CG-101 at injection pressures of 3.5, 7.0, and 10.0 MPa, the top hole injection pressures used in the experiment. As Figure 5.2 shows, the flow rate is a linear function of the permeability at a given injection pressure. This is to be expected as the calculation is based on Darcy's Law.

Permeabilities input must be such that the calculated flow rates span the measured flow rate, because the next step is to use the measured flow rate to read the rock permeability from the graph. Alternatively, any two flow rates will define a linear relation between flow rate and permeability at a given injection pressure, and that relation can be used to calculate the permeability.

In either case, the measured flow rates for Sample CG-101 indicate that the sample has permeabilities of 3.6×10^{-9} , 4.0×10^{-9} , and 5.4×10^{-9} cm/min (59.4×10^{-9} , 65.9×10^{-9} , and 89.0×10^{-9} darcy) for top hole injection pressures of 3.5, 7.0, and 10.0 MPa, respectively. The permeability increases with increasing injection pressure because the higher pore water pressure tends to increase the

Figure 5.2 Sample CG-101, calculated flow rate vs. permeability for injection pressure, P_T , of 10.0, 7.0, and 3.5 MPa. $\sigma_{ax} = 22.8$ MPa, $\sigma_c = 19.6$ MPa.

size of the connected pore space in the sample, increasing its permeability.

Permeability is also a function of the triaxial stress state of the sample, which for CG-101 with the rock bridge in place was 22.8 and 19.7 MPa axial and confining stress, respectively.

Figure 5.3 shows the variation in flow rate with variation in plug permeability. The abscissa is the ratio of plug permeability to intact rock permeability, K_p/K_R . K_R , the intact rock permeability, is that permeability determined for the sample with rock bridge in place. At $K_p/K_R = 1$ (10^0), the plug and rock permeabilities are equal, the case for intact rock. The 10.0 MPa injection pressure curve was calculated using $K_R = 5.4 \times 10^{-9}$ cm/min (89.0×10^{-9} darcy), and the 7.0 and 3.5 MPa curves using their corresponding intact rock permeabilities. The measured flow rates through the plugged samples at 10.0, 7.0, and 3.5 MPa, with axial and confining stresses of 23.0 and 19.6 MPa, respectively, are shown as arrows pointing to the $K_p/K_R = 1$ line. All measured flow rates through the plugged samples fell below the theoretical curves, possibly due to stress redistributions resulting from the coring out of the rock bridge and the expansiveness of the cement used as the plug material.

Samples CG-102 and CG-103. The experimental results from Sample CG-102 and Sample CG-103 are similar to those for CG-101. Rock permeabilities for CG-102 were calculated to be 3.3×10^{-9} , 4.2×10^{-9} and 4.6×10^{-9} cm/min (54.4×10^{-9} , 69.2×10^{-9} , and 75.8×10^{-9} darcy) for injection pressures of 3.5, 7.0, and 10.1 MPa, respectively

Figure 5.3 Sample CG-101, variation in flow rate with variation in the ratio of plug permeability, K_p , to rock permeability, K_R . For each curve at a different injection pressure, P_T , of 10.0, 7.0, and 3.5 MPa, the corresponding rock permeability, K_R , from the previous figure was used.

(Figure 5.4). Curves showing the relation between the flow rate and the ratio K_p/K_R are shown on Figure 5.5. Once again the measured flow rates through the plugged sample fell below the theoretical curves. Triaxial stress state on the plugged sample was 22.8 MPa axial and 19.7 MPa confining stress, the same as for the rock bridge.

Figures 5.6 and 5.7 show similar results for Sample CG-103. Permeabilities for this sample were calculated to be 3.5×10^{-9} , 4.5×10^{-9} and 5.3×10^{-9} cm/min (57.7×10^{-9} , 74.2×10^{-9} and 87.4×10^{-9} darcy) for injection pressures of 3.5, 7.0, and 10.1 MPa, respectively; the measured flow rates through the plugged sample were all less than the K_p/K_R theoretical curves.

Table 5.1 is a summary of the permeability values calculated for CG-101, CG-102, and CG-103 with the rock bridge in place.

Sample CG-104. Charcoal Granite Sample CG-104, which was plugged with bentonite tablets, was initially tested to determine the variation in flow rate with variation in triaxial stress state with a rock bridge in place. A summary of the results of this experiment and a graph of the flow rate vs. top hole injection pressure for different triaxial stress states are shown in Table 4.14 and on Figure 4.28.

Table 5.2 summarizes the results of testing on the intact rock (sample with rock bridge) in a slightly different manner. The first stress invariant, I_1 , is calculated for each axial stress and confining stress combination,

$$I_1 = \sigma_{ax} + 2\sigma_c$$

Figure 5.4 Sample CG-102, flow rate vs. permeability for injection pressures, P_T , of 10.1, 7.0, and 3.5 MPa.

Figure 5.5 Sample CG-102, variation in flow rate with variation in the ratio of plug permeability, K_p , to rock permeability, K_R . For each curve at a different injection pressure, P_T , of 10.1, 7.0 and 3.5 MPa, the corresponding rock permeability, K_R , from the previous figure was used.

Figure 5.6 Sample CG-103, flow rate vs. permeability for injection pressures, P_T , of 10.1, 7.0 and 3.4 MPa.

Figure 5.7 Sample CG-103, variation in flow rate with variation in the ratio of plug permeability, K_P , to rock permeability, K_R . For each curve at a different injection pressure, P_i , of 10.0, 7.0 and 3.4 MPa, the corresponding rock permeability from the previous figure was used.

Table 5.1 Summary of Permeability Values Calculated for the Charcoal Granite

Sample	I_1 (MPa)	P_T (MPa)			
		3.4	7.0	10.0	10.1
CG-101	62.2	59.4×10^{-9}	65.9×10^{-9}	89.0×10^{-9}	
CG-102	62.2	54.4×10^{-9}	69.2×10^{-9}		75.8×10^{-9}
CG-103	62.0	57.7×10^{-9}	74.2×10^{-9}		87.4×10^{-9}

NOTES: (1) Permeability units are darcy.

(2) I_1 is the first stress invariant, $I_1 = \sigma_1 + \sigma_2 + \sigma_3$. In this case I_1 is the sum of the axial stress and twice the confining stress on the sample.

Table 5.2 Estimated and Measured Flow Rates and Permeabilities
for Sample CG-104 with Rock Bridge

σ_{ac}, σ_c (MPa)	$I_1 = \sigma_{ax} + 2\sigma_c$ (MPa)	P_t (MPa)				
		1.6	3.4	7.0	10.1	
86.6, 6.9	22.4	4.02	11.67	(32.40)	(54.40)	Flow Rate, I_1 ($\times 10^{-3}$ cc/min)
15.5, 13.7	42.9	(1.85)	4.85	11.08	19.35	
23.0, 19.6	62.2	(0.69)	1.93	4.66	8.44	
		$K=10^{\log 0-5.22}$	$K=10^{\log 0-5.55}$	$K=10^{\log 0-5.86}$	$K=10^{\log 0-6.02}$	Equations from CG-103 (Q in cc/min; K in cm/min)
86.6, 6.9	22.4	399×10^{-9}	542×10^{-9}	(737×10^{-9})	(857×10^{-9})	
15.5, 13.7	42.9	(183×10^{-9})	225×10^{-9}	252×10^{-9}	305×10^{-9}	
23.0, 62.2	62.2	(69×10^{-9})	90×10^{-9}	106×10^{-9}	133×10^{-9}	Permeabilities (darcy)

σ_{ax} = axial stress, σ_c = confining stress, I_1 = first stress invariant, P_t = top pressure
 4.02 - measured value
 (1.85) - estimated value

where, σ_{ax} = axial stress, and

σ_c = confining stress.

The flow rates for various top hole injection pressures associated with each value of I_1 are tabulated. Values in parentheses were calculated from the power law curves in Figure 4.28, whose coefficients are given in Table 4.14. All the other flow rate values are measured values.

The permeabilities of Sample CG-104 have been determined from the flow rate data. These values are also shown on Table 5.2. Since CG-104 has almost the same dimensions as CG-103, and the same top hole injection pressures were used, the equations relating flow rate and permeability developed using FRESURF I for Sample CG-103 were used to calculate the permeabilities of Sample CG-104. These equations are also shown on Table 5.2.

Figure 5.8 shows the variation in sample permeability with the first stress invariant at each top hole injection pressure. As the sample is subjected to higher stress conditions, that is, as I_1 increases, the sample permeability decreases, probably due to decreasing pore sizes and fracture widths within the sample. Permeability increases as the injection pressure increases at a given stress level, I_1 , because increasing the injection pressure decreases the effective stress; increasing injection pressure tends to open pores and microfractures.

Comparison of CG-103 and CG-104. Tests on CG-103 with the rock bridge in place were performed only at an axial and confining stress

Figure 5.8 Sample CG-104, rock bridge, permeability vs. first stress invariant, I_1 .

level of 22.8 and 19.6 MPa, respectively ($I_1 = 62.0$ MPa). At this triaxial stress level, flow rates at injection pressures of 3.4, 7.0, and 10.1 MPa were measured, and a power law curve fit to those data used to estimate what the flow rate would have been at an injection pressure of 1.6 MPa. Permeability values determined for these flow rates are shown as the points on Figure 5.9.

Curves were then drawn through each point to show the relationship between the permeability of CG-103 as a function of I_1 . It was assumed that each curve at each injection pressure had the same shape as for CG-104. The curves shown on Figure 5.9 were traced from Figure 5.8 by matching the point on Figure 5.9 with the corresponding curve and 11 on Figure 5.8. The graphs were shifted parallel to the permeability axis to make the match.

By so doing the permeability, and thus the flow rate, for intact rock at lower stress levels may be estimated for CG-103. This estimated flow rate for the sample with rock bridge may then be compared with the flow rate through the plugged sample at these stress levels.

Figure 4.11 shows the manner in which flow through the plugged sample varied with triaxial stress state at various confining pressures. At the highest stress levels, flow through the plugged sample was less than flow through the sample with rock bridge (intact rock). The flow rate through the plugged sample increased as the triaxial stress state was lowered. As will be shown below, the increased flow at lower stress states is most likely due to increased rock permeability.

Figure 5.9 Sample CG-103, rock bridge, permeability vs. first stress invariant, I_1 .

Consider the flow rate of 0.92×10^{-3} cc/min measured for Sample CG-103 at a triaxial stress state of 8.6 and 7.1 MPa, axial and confining stress and 1.8 MPa injection pressure (Table 4.7). For this stress state, $I_1 = 22.8$ MPa. From Figure 5.9, at an injection pressure of 1.6 MPa and $I_1 = 22.8$ MPa, the rock permeability equals 22.3×10^{-9} cm/min (368×10^{-9} darcy).

The estimated flow rate through the sample with rock bridge may be calculated using the appropriate equation from Table 5.2. This yields $Q = 3.7 \times 10^{-3}$ cc/min as the estimated flow rate through CG-103 with the rock bridge in place under 8.6 and 7.1 MPa axial and confining stress. The flow through the plugged sample under this triaxial stress state and a slightly higher injection pressure, 1.8 MPa, was measured as 0.92×10^{-3} cc/min.

Table 5.3 shows the estimated flow rates in through CG-103 with the rock bridge in place compared to the measured flow rates in through the plugged sample. In all cases the estimated flow rate through the sample with rock bridge are higher than the flow rate measured for the plugged sample. This strongly suggests that the increases in flow rate with decreasing triaxial stress state is due to increased permeability of the rock itself. These calculations indicate that even at decreased stress levels the overall permeability of the cement plug, interface included, is less than that of the intact rock.

Discussion. Sample CG-101 and CG-102 show similar results to Sample CG-103 (see Figures 4.4 and 4.9), and it may be inferred that

Table 5.3 Sample CG-103. Comparison of Measured Flow Rate through Plugged Sample with Estimated Flow Rate through Sample with Rock Bridge

$\sigma_{ax} \rightarrow$	15.4 MPa	8.6 MPa
$\sigma_c \rightarrow$	13.7 MPa	7.1 MPa
$I_1 \rightarrow$	42.8 MPa	22.8 MPa

P_t (MPa) $\downarrow$	Plugged Sample	Rock Bridge	Plugged Sample	Rock Bridge
10.1	5.20	(16.54)		
7.0	1.94	(9.85)		
3.4	0.73	(4.19)	2.14	(10.86)
1.8			0.92	
1.6				(3.70)

Flow Rate In (x 10 ⁻³ cc/min)	
---	--

σ_{ax} = axial stress, σ_c = confining stress, I_1 = first stress invariant

5.20 - measured value
(16.54) - estimated value

the increased flow through these samples is also due to increased rock permeability.

The dependence of rock permeability on the stress state has been described by Brace, Walsh, and Frangos (1968). They found that the permeability of Westerly Granite varied from 350 nanodarcy at 100 bars pressure to 4 nanodarcy at 4000 bars pressure, and that Darcy's law apparently held even at the lowest permeability values. Further, permeability is strongly dependent on the effective stress state, rather than the total stress state, so that increasing the pore water pressure increases the permeability of a rock.

Bernaix (1969) investigated the variation in rock permeability with effective stress by using a hollow cylindrical sample. Water was injected in convergent flow from the annulus about the sample to the center hole, and in divergent flow from the center hole to the annulus. The convergent flow condition induces compressive stresses in the sample and yields lower permeabilities than the divergent flow condition, which induces tensile stresses, widening cracks and pores.

(Paterson (1978, p. 80) indicates that Terzaghi's concept of effective stress is clearly obeyed in low permeability rock at low strain rates. At higher strain rates, laboratory observations of departures from the effective stress rule may be entirely due to the actual pore pressures within a sample being different from the measured pore pressure at the surface of the sample.)

Sentinel Gap Basalt

The two experiments in which a cement plug was placed in samples of Sentinel Gap Basalt were analyzed in a similar manner to the Charcoal Granite samples.

Sample SGE-2-2. The permeability of this sample was calculated to be 1.04×10^{-11} cm/min (0.17×10^{-9} darcy) using the flow rate in (Q_{in}) data. The permeability did not vary with the triaxial stress state within the sensitivity of the equipment.

Figure 5.10 shows the variation in flow rate with K_p/K_R ratio for two different injection pressures. The two lower horizontal lines correspond to the Q_{in} plug data and the two upper horizontal lines to the Q_{out} plug data. For the Q_{in} data, K_p/K_R values of 54 and 63 yield overall plug permeabilities of 5.6×10^{-10} and 6.6×10^{-10} cm/min (9.2×10^{-9} and 10.9×10^{-9} darcy). The Q_{out} data lead to plug permeabilities of 2.7×10^{-9} and 3.6×10^{-9} cm/min (44.5×10^{-9} and 59.4×10^{-9} darcy). Thus, the overall plug permeability is likely between 0.6×10^{-9} and 3.6×10^{-9} cm/min (10×10^{-9} to 60×10^{-9} darcy). This compares with a permeability of 95×10^{-9} darcy measured for the cement core in the Ruska permeameter (Chapter 3).

Drying of the plug in an oven ($T = 54^\circ\text{C}$, 42 days) caused the permeability of the plug to increase greatly. Test results are shown in Table 4.18, and on Figure 4.16. Since the flow through the plug was much greater than flow through the basalt, the plug permeability can be calculated using the one-dimensional form of Darcy's law:

Figure 5.10 Sample SGE-2-2, variation in flow rate with variation in the ratio of plug permeability, K_P , to rock permeability, K_R .

$$K = \frac{QL}{HA} \quad (5.1)$$

where, K = permeability

Q = flow rate

L = length of plug

H = head differential

A = area of plug

The initial flow rate was (using Q_{in}) 917.04×10^{-3} cc/min at $P_t = 1.6$ MPa, which corresponds to a permeability of 1.9×10^{-4} darcy. After 50 days the flow rate in had decreased to 15.39×10^{-3} cc/min with $P_t = 2.1$ MPa, with a corresponding permeability of 2.4×10^{-6} darcy. The permeability of the plug decreased two orders of magnitude in 50 days. This is thought to be due to swelling of some of the plug components upon rewetting.

After the flow rate had stabilized the triaxial stress state on the sample was increased. Table 5.4 shows the permeabilities calculated from the flow rates at these stress states. At first the injection pressure only was increased and the permeability did not change significantly. At the intermediate triaxial stress state (14.5 MPa axial, 11.01 MPa confining stress) and an injection pressure of 10.1 MPa the permeability increased slightly, to 3.1×10^{-6} darcy, but at the highest triaxial stress state the measured permeability value declined to 2.7×10^{-6} darcy.

Drying significantly increased the permeability of the plug, from 60×10^{-9} darcy before drying to about 3000×10^{-9} darcy afterwards.

Table 5.4 Sample SGE-2-2: Permeability of Cement System 1 Plug After Drying

	<u>Initial</u>	<u>50 Days</u>	<u>More Than 50 Days</u>			
σ_{ax} (MPa)	8.7	8.8	8.9	9.0	14.5	23.2
σ_c (MPa)	7.2	7.0	7.1	7.0	11.0	19.5
P_t (MPa)	1.6	2.1	7.0	7.0	10.1	10.0
K (Darcy)	1.9×10^{-4}	2.4×10^{-6}	2.5×10^{-6}	2.8×10^{-6}	3.1×10^{-6}	2.7×10^{-6}

NOTES: σ_{ax} = axial stress, σ_c = confining stress, P_t = injection pressure, K = permeability

However, a permeability of 3000×10^{-9} darcy (= 3 microdarcy) is still a very low permeability.

Sample SGE-2-3. The rock permeability of SGE-2-3 was calculated as 1.06×10^{-11} cm/min (0.17×10^{-9} darcy) using the flow rate in data. Figure 5.11 presents the K_p/K_R vs. Flow Rate curves. Measured flow rates at both 10.0 MPa and 3.4 MPa yield $K_p/K_R = 420$, and thus a plug permeability of 4.45×10^{-9} cm/min (73×10^{-9} darcy). These results compare well with those of Sample SGE-2-2, and the cement permeability in the Ruska permeameter.

The dye injection test indicates that the rock/plug interface is a preferential fluid migration path, although one of very low permeability.

Oracle Granite

As discussed in Chapter 4, the Oracle Granite specimen was the first one tested, and tests were performed in a different manner than for the preceding samples. As such, the analysis of the test results is of a different form than for the preceding samples.

In the first series of test flow rates between the top hole and the annulus were measured in both convergent and divergent flow. The flow occurred through a hairline fracture in the top part of the rock.

In a second series of tests flow rates were measured between the annulus and top hole and the bottom hole in convergent flow. In this test flow occurs from the annulus and the top hole to the bottom hole.

Figure 5.11 Sample SGE-2-3, variation in flow rate with variation in the ratio of plug permeability, K_P , to rock permeability, K_R .

The flow from the first series and second series of tests may be compared by calculating the rock permeability using the equation (Bernaix, 1969):

$$K = \frac{Q \ln(R_2/R_1)}{2\pi LP} \quad (5.2)$$

where, K = permeability

Q = flow rate

R_1 = inside radius

R_2 = outside radius

L = length

P = head differential

This equation is for pure radial flow in a homogeneous, isotropic, porous medium. This is not strictly applicable to the first series of tests because flow occurred along a fracture. The equation yields the permeability of an equivalent porous medium, that is, a medium which, if it occupied the top third of the specimen, would allow the same flow rate as occurred through the actual rock, including fracture, in the top third of the specimen. Tables 5.5 and 5.6 give the equivalent permeabilities for both the convergent and divergent flow modes. The data are given in the order of testing and tests using the convergent flow mode were performed first. As annular pressure is increased the equivalent permeability decreases as the fracture closes. Lessening the annular pressure results in increased equivalent permeability, but not to previous levels, probably reflecting inelastic behavior of the original fracture.

Table 5.5 Oracle Granite; Top Hole, Radial Permeability in
Convergent Flow with Rock Bridge

<u>Annular Pressure (MPa)</u>	<u>Permeability (microdarcy)</u>
0.69	68.2
1.72	68.8
2.41	58.8
3.45	54.0
1.03	57.2
1.38	55.4
0.69	59.9

Axial stress = 18.6 MPa

Table 5.6 Oracle Granite; Top Hole, Radial Permeability in
Divergent Flow with Rock Bridge

<u>Top Hole Pressure (MPa)</u>	<u>Permeability (microdarcy)</u>
0.69	1036
1.38	962
2.07	2302

Axial stress = 18.6 MPa

In divergent flow the equivalent permeabilities are more than an order of magnitude greater than for convergent flow, reflecting the tendency of the higher pressure in the top hole to create tensile tangential stresses in the rock, widening the fracture.

The equivalent permeability of the bottom hole may also be calculated, using Bernaix's equation. Again, the equation is not strictly applicable, because, although there is not a fracture present, the flow is not purely radial. Some flow comes from the top hole through and around the rock bridge. However, if all flow is assumed to come in a purely radial path through the bottom third of the sample the equivalent permeability will be an upper bound. With these caveats, the "upper bound equivalent permeability" may be calculated as 0.0086 microdarcy for the rock in the bottom third of the sample (and by inference, for the intact Oracle Granite). This compares with a value of around 60 microdarcy for the equivalent permeabilities of the part of the sample containing the fracture.

These calculations illustrate the great increase in water flow through fractured rock as compared to intact rock. Even a hairline fracture results in equivalent permeabilities orders of magnitude greater than for intact rock, in this case almost four orders of magnitude.

Brace, 1980, indicates that the in situ permeability of crystalline rocks ranges from 1 to 100,000 microdarcy and that in situ values for crystalline rocks are high because of natural fractures. "Based on observed variation in wells, permeability at particular sites in crystalline rock is not predictable with a factor of 10×10^{-5} ."

Table 5.7 Oracle Granite; Radial Permeability in Convergent Flow - Hollow Cylinder

<u>Annular Pressure (MPa)</u>	<u>Permeability (microdarcy)</u>
0.34	165.2
0.69	145.0
1.03	137.7
0.34	135.1
0.69	119.1
1.03	103.7

Axial stress = 18.6 MPa

Table 5.8 Oracle Granite; Radial Permeability in Divergent Flow - Hollow Cylinder

<u>Center Hole Pressure (MPa)</u>	<u>Permeability (microdarcy)</u>
0.34	171.5
0.69	169.4
1.03	177.3

Axial stress = 18.6 MPa

Following the tests with the rock bridge in place, tests were performed on the hollow cylinder (bridge cored out). Tables 5.7 and 5.8 give the equivalent permeabilities calculated from Bernaix's equation. The difference between the rock's equivalent permeability under convergent flow compared to divergent flow is smaller than expected when considered in conjunction with the test performed in the top hole. It reflects the fact that the fracture did not penetrate the entire sample, but only the upper part. The values do fall between the convergent and divergent top hole tests on the sample with rock bridge in place, as they should.

A plug of cement system 1 was installed and tested in a manner similar to the convergent flow test on the bottom hole of the sample with rock bridge. As discussed in Chapter 4, a flow rate of 11.53×10^{-3} cc/min was measured in the test on the cement plug compared to 0.75×10^{-3} cc/min measured when the rock bridge was in place. Since the increased flow was coming through the plug it is not appropriate to calculate equivalent permeabilities as has been done previously. But if all flow is assumed to be coming through the cement plug an upper bound on the plug permeability may be calculated using Darcy's Law:

$$Q = \frac{KH}{LA} \quad (5.3)$$

where, Q = flow rate

K = permeability

H = head differential

L = plug length

A = cross-sectional area of plug

This calculation yields a cement plug permeability of about 8 microdarcy, which is still less than the equivalent permeability calculated for the section of rock with the fracture. Thus, the cement plug has a permeability about three orders of magnitude greater than the intact rock, but still almost an order of magnitude less than the part of the rock with a small fissure.

Topopah Spring Tuff

The test performed on the Topopah Spring Tuff sample was most interesting because flow rates after plugging were at first much higher than for the sample with rock bridge, but after a month had decreased to a flow rate similar to that of the rock bridge.

To calculate permeabilities for this sample an equation derived using FRESURF I for Sample SGE-2-3 was used,

$$\log K = C_1(\log(Q) - 5.975) \quad (5.4)$$

where, K = permeability in microdarcy

Q = scaled flow rate in cc/min (see text),

$C_1 = 16.487$, a constant to convert permeability units of cm/min to darcy at a water temperature of 22°C

This equation somewhat overestimates the permeability of NTS-TPTS-101 because this sample has shorter flow paths than SGE-2-3. A comparison of the two samples (see Figures 4.18 and 4.22) shows that

the shortest flow path, through the rock bridge, is 8.8 cm for NTS-TPTS-101 and 10.2 cm for SGE-2-3, a difference of 16% with respect to NTS-TPTS-101. The longest flow paths, around the periphery from the top hole to the bottom hole, have lengths of 40.1 cm and 42.4 cm for NTS-TPTS-101 and SGE-2-3, respectively, a difference of 6%. Thus, the error in using this equation is between 6% and 16%, probably closer to 16%, and the permeability calculated is an upper bound because a longer flow path requires a higher permeability for a given flow rate.

The equation was derived using an injection pressure of 9.8 MPa, and the measured flow must be linearly scaled to that pressure. A measured flow rate at $P_t = 3.5$ MPa would be multiplied by $(9.8/3.5)$ and the resulting scaled flow rate used in the calculation. This simply implies that flow rate is a linear function of head, an assumption implicit in Darcy's Law if the permeability is constant.

Table 5.9 gives the results of this calculation. Upper bound permeabilities ranged from 4.8 microdarcy to 1.7 microdarcy, exhibiting the expected pattern of being highest for lower triaxial stress states and higher injection pressures and lower for higher triaxial stress states and lower injection pressures.

After plug emplacement flow rate through the sample increased by over an order of magnitude. The initial flow rate in after plug emplacement was 6178×10^{-3} cc/min, which corresponds to a plug permeability of 2500 microdarcy assuming all flow through the rock and using the one-dimensional form of Darcy's Law.

After one month the flow rate had decreased to 87×10^{-3} cc/min, at 7.0 MPa injection pressure, similar to the flow rate measured for the rock bridge at the highest triaxial stress state and 7.0 MPa injection pressure (Table 4.10). In addition, the triaxial stress state on the plugged sample was lower than the highest triaxial stress state on the sample with rock bridge, the confining stress being quite a bit lower to control leakage from the annulus. It may be inferred that the plug permeability was approaching that of the rock, about 2 microdarcy, since the flow rates were similar.

This sort of behavior was observed for a dried plug in Sample SGE-2-2, discussed previously. In that case the cement plug was dried and then had a permeability of 190 microdarcy, which reduced after 50 days to 3 microdarcy, a value obviously close to the 2 microdarcy final value for the NTS-TPTS-101 plug.

The reason for the reduction in plug permeability with time is unknown. This plug was not dried. It is speculated that water flow through the plug causes continued hydration of the cement and thus reduces its permeability. For this sample it is likely that flow was dominantly along the rock-plug interface. When the high flow rates were first observed the permeameter was turned over and the bottom plug removed so that the cement plug could be observed. Water was injected into the top hole and seepage of water could be clearly seen coming from the circumference of the bottom of the cement plug.

The initial high flow rates may be due to alkali-aggregate reactivity between the rock and the concrete. Bates (1969) has

Table 5.9 Sample NTS-TPTS-101, Rock Bridge; Upper Bound Permeability

	$\sigma_{ax} \rightarrow$	8.6	15.7	23.4
	$\sigma_c \rightarrow$	6.6	13.2	19.6
	$P_t \downarrow$			
	10.0		2.9	2.3
	7.0		2.5	2.1
permeability	6.1	4.6		
(microdarcy)	3.5	3.6	2.1	1.7
	1.8	3.5		

NOTES: σ_{ax} = axial stress (MPa); σ_c = confining stress (MPa); P_t = top hole injection pressure (MPa).

Permeabilities were calculated using the formula obtained for Sample SGE-2-3 at $P_t = 9.8$ MPa; $\log K = \log Q_{in} = 5.975$, where Q_{in} is the flow rate in cm/min. Permeabilities were corrected to darcy using a temperature of 22°C for the water. See text for further discussion.

described this phenomenon as the process in which alkalies liberated as cement hardens reacts with the minerals of the aggregate. Quartz, feldspar, calcite, and most dark silicate minerals do not react to a significant degree, but aggregate containing certain poorly crystalline siliceous material may react. Such materials include opalline shale, opalline and chalcedonic chert, siliceous limestone, and siliceous cryptocrystalline volcanic rocks, especially rhyolite, dacite, and andesite. In addition, an alkali carbonate reaction involving dolomite in certain calcitic dolomites and dolomitic limestones may also occur.

The reaction process is such that sodium and potassium released as the cement hardens react with the poorly crystalline silica, forming an alkalic silica gel. The gel absorbs water from the cement paste, generating expansive stresses that may exceed the tensile strength of the concrete. Indeed, certain cements are specially manufactured to produce high expansive stresses upon curing and are used as non-explosive demolition agents in areas where blasting cannot be employed (Ishii et al., 1982).

In the present instance the rock is a siliceous, rhyolitic tuff with glass and cryptocrystalline silica (devitrified material) as components. Thus, alkali-aggregate reactions are likely to have occurred, particularly along the rock/plug interface.

Corrective measures to preclude these reactions are to limit the alkali content of the cement and to add pozzolanic materials to the cement (Mather, 1964). If the alkali content of the cement is low

enough, no cracking of the cement will occur. Addition of finely ground reactive material - a pozzolan - will cause the reaction to first occur between the alkalies and the pozzolan, using up the alkali and spreading the reaction and reaction products throughout the cement. Deleterious effects of alkali-aggregate reactions may take two or three years to become apparent.

Catalina Granite

Catalina Granite samples CCR-P-100 and CCR-D-100 were tested to evaluate the effects of differing drilling methods. The hole in CCR-P-100 was drilled using a percussion drill; the hole in CCR-D-100 was drilled using a diamond core drill. In addition, the cement plug in CCR-P-100 was subjected to drying at room temperature for 27 days.

Table 5.10 summarizes the results for the two samples. Sample CCR-P-100 had a flow rate value before drying slightly lower than the flow rate after drying. The drying slightly impaired plug performance, but not to the degree that oven drying of the plugged Sample SGE-2-2 impaired its performance. The low temperature at which CCR-P-100 was dried would not have driven off as much moisture as oven drying.

Sample CCR-D-100 was first tested with a rock bridge in place. Dimensions were similar to CCR-P-100 (Figures 4.24 and 4.26). As Table 5.10 shows, flow rates in through the intact rock of CCR-D-100 were greater than those for the cement-plugged CCR-P-100, indicating that the cemented percussion drilled hole was a lower permeability

Table 5.10 Test Results for Samples CCR-P-100 and CCR-D-100

σ_{ax} (MPa)	σ_c (MPa)	Top Pressure (MPa)	Bottom Pressure (MPa)	Flow Rate In ($\times 10^{-3}$ cc/min)	Flow Rate Out ($\times 10^{-3}$ cc/min)	Comments
Sample CCR-P-100, Cement 1 Plug						
7.7	2.0	2.0	0	8.73	7.84	Before drying
7.5	2.1	1.9	0	11.91	12.09	After drying
Sample CCR-D-100, Rock Bridge						
8.5	7.0	1.6	0	15.85	12.71	Measured
(8.5)	(7.0)	(2.0)	(0)	(20.11)	-	Estimated
Sample CCR-D-100, Cement 1 Plug						
8.6	7.1	1.6	0	11.30	8.11	Measured
(8.6)	(7.1)	(2.0)	(0)	(14.85)	-	Estimated

σ_{ax} = axial stress; σ_c = confining stress. Lines with figures in parentheses show estimated flow rate in at 2.0 MPa top pressure. Estimates were made from curves at the same axial and confining stresses, Figure 4.27. Regression coefficients are given on Table 4.13.

element than the rock bridge. This is also suggested by the dye test illustrated in Figure 4.25, in which the dye penetrated the rock more than the plug.

A 2.6 cm diameter hole drilled in CCR-D-100 was plugged with cement. Flow rate in values were less than for CCR-D-100 with rock bridge, but slightly greater than for the flow rate in values for CCR-P-100. Comparison is complicated by the fact that the cement plug in CCR-P-100 was 3.8 cm in diameter whereas the one in CCR-D-100 was 2.6 cm in diameter. Since the cement plug lowered flow rates, a larger plug in CCR-D-100 could be expected to lower flow rates even more. Thus, the difference in flow rate through the plugged percussion-drilled hole and the plugged diamond-drilled hole is not significant, indicating that percussion drilling does not introduce a damage zone to the rock about the hole significantly greater than does a diamond drilling. This accords with the results obtained by Mathis (1982).

Tests on Bentonite Plugs

Charcoal Granite

Test results for the Charcoal Granite with rock bridge have already been discussed, in the section regarding Charcoal Granite under the Analysis of Tests on Cement Plugs. In this section permeabilities for the rock under a wide range of triaxial stress conditions and injection pressures were calculated using equations derived for Sample CG-103, which has slightly different dimensions.

For the analysis in this section, FRESURF I was used to calculate the permeability of intact rock for CG-104 under a triaxial stress

state of 23.0 MPa and 19.6 MPa axial and confining stresses, respectively, and an injection pressure of 3.4 MPa. The permeability is 5.42×10^{-9} cm/min (0.085 microdarcy), which is within 0.3% of the estimated value in the preceding section.

Figure 5.12 shows flow rate vs. K_p/K_R at an injection pressure of 3.8 MPa. This graph was developed using data for the first clay plug, Table 4.14; the plug length was 10.9 cm.

Measured flow rates through the first clay plug were less than for the intact rock, indicating the clay is less permeable than the rock; that is, the clay is less permeable than 0.085 microdarcy. This is a much lower permeability than the 50-100 microdarcy permeabilities measured for the clay plug in the falling head test (Chapter 2), and is thought to result from applying a high pressure on the clay plug, thereby hydraulically compacting it prior to attainment of pore pressure equilibrium.

Alternatively, piping of the clay may have resulted in plugging of the 1/8-inch diameter tubing or the valve leading from the permeameter to the bottom flask. This would have the effect of increasing the flow path by less than an order of magnitude, probably about 5 to 6 times. If this is the case it illustrates the ability of the clay to migrate into fine fissures and plug them. (Of course, if the clay continues to pipe it will eventually all wash out. Piping in this instance, however, is a result of the abnormally high gradients used in the experiment.)

The second and third clay plugs exhibited higher flow rates at lower injection pressures than the first one (Table 4.14). Linearly scaling the flow rates to estimate their value at 3.8 MPa, the highest scaled flow rate obtained is 10.07×10^{-3} cc/min, estimated for the measured value k_1 of 2.65×10^{-3} cc/min at 1.0 MPa injection pressure.

From Figure 5.12, this corresponds to a K_p/K_R of 69, yielding a clay plug permeability of $0.37\text{E-}06$ cm/min (6 microdarcy), assuming a plug length of 10.9 cm. Actually the plug had been forced into the bottom of the sample at this time, and measurement of the sample after it was removed from the permeameter indicated a plug length of 16.3 cm. The longer flow path would require a higher permeability for the given flow rate, and the actual plug permeability is estimated at $(16.3/10.9)(0.37 \times 10^{-6}) = 0.55 \times 10^{-6}$ cm/min (9 microdarcy). This indicates a plug permeability about two orders of magnitude greater than the granite.

Influence of Relative Plug-Rock Permeabilities

The influence of the relative plug-rock permeabilities on the flow pattern in a sample was evaluated using FRESURF I. For this work the sample was assumed to be six inches (15.24 cm) in diameter and twelve inches (30.24 cm) long.

Only the upper quarter of the sample need be modeled due to axial symmetry about the Z-axis and mirror-plane symmetry about the R-axis. The mesh used was the upper half of the mesh shown in Figure 5.1.

Figure 5.12 Sample CG-104, variation in flow rate with variation in the ratio of plug permeability, K_P , to rock permeability, K_R .

Figure 5.13 presents a flow net for the case of intact rock, where "plug" permeability (here a rock bridge) and rock permeability are equal ($K_p = K_R$). The aspect ratios of the rectangles in this flow net vary due to the axial symmetry. For this work the head in the top hole was assigned a relative magnitude of 100 and equipotential lines drawn at 5% intervals of total head drop. The R-axis is the line of 50% head drop, and of course the lower half of the sample (not shown) would have the same appearance, but equipotentials would range from 50% along the R-axis to 0% at the bottom hole.

The program calculates the head at each node, and the equipotentials were drawn by linear interpolation between nodes. Stream lines were drawn at 5% intervals of total flow. Flow is calculated by FRESURF I at each constant potential node, which in this instance are the nodes along the top hole and along the R-axis. Flow was distributed linearly about each constant potential node, assuming the flow assigned to each node occurred between points halfway to the adjacent nodes. Linear interpolation was used to calculate the position of the 5% contours along the constant head boundaries and the stream lines sketched orthogonal to the equipotential lines. Orthogonality is assured by the isotropy of the model.

As Figure 5.13 shows, only about 5% of the total flow occurs through the plug region for $K_p = K_R$. Most of the flow occurs through the rock surrounding the plug region. As a base, consider the relative flow magnitude for $K_p = K_R$ as 1.00. (In the case actually modelled, the head was assigned as 100 cm, and a permeability of

Figure 5.13 Flow net for intact rock, $K_p = K_R$. About 5% of the flow occurs through the "plug region". Equipotential lines show percent head with respect to center hole. Stream lines show percent flow occurring between the stream line and the Z-axis. Relative flow magnitude = 1.00.

10^{-5} cm/sec used. The total flow rate was calculated as 0.951×10^{-2} cc/sec. Any consistent length and time units may be used.)

Figure 5.14 shows the case in which the plug is one order of magnitude more permeable than the rock, $K_p = 10K_R$. In this instance about 25% of the flow occurs through the plug. The relative flow magnitude is 1.50; that is, flow is 1 1/2 times that for the intact rock case above. Calculations for a plug two orders of magnitude more permeable than the rock indicate about 75% of the flow occurs through the plug and the relative flow magnitude is 6.24.

Finally, Figure 5.15 shows the case for a plug one order of magnitude less permeable than the rock ($K_p = 0.1K_R$). Less than 5% of the flow occurs through the plug, and the relative flow magnitude is 0.94. Calculations for a plug two orders of magnitude less permeable than the rock indicate less than 5% of the flow occurs through the plug and a relative flow magnitude of 0.93, similar to the "one order of magnitude less" case.

The implications of the above calculations are straightforward. First, a plug one order of magnitude less permeable than the rock reduces the flow through the system by only 6%. A further reduction in plug permeability to two orders of magnitude less than the rock results in only another 1% reduction in flow through the plug-rock system. Making a plug less permeable than the surrounding rock offers little gain in overall rock-plug system performance.

Second, a plug one order of magnitude greater in permeability than the rock results in only a one and one-half fold increase in

Figure 5.14 Flow net for plug more permeable than rock, $K_P = 10K_R$. About 25% of the flow occurs through the plug. Equipotential lines show percent head with respect to center hole. Stream lines show percent flow occurring between the stream line and the Z-axis. Relative flow magnitude = 1.50.

Figure 5.15 Flow net for plug less permeable than rock, $K_p = 0.1K_R$. Less than 5% of the flow occurs through the plug. Equipotential lines show percent head with respect to the center hole. Stream lines show percent flow occurring between the stream line and the Z -axis. Relative flow magnitude = 0.94.

flow rate. A plug two orders of magnitude more permeable than the rock results in about a six-fold increase in flow rate. Thus, a plug one or two orders of magnitude greater in permeability than the surrounding rock does not permit even one order of magnitude increase in flow through the system modeled, which represents a plug and the immediately surrounding rock. Since a borehole and its immediately surrounding rock is only a small part of the total rock mass, the effect of a plug permeability one or two orders of magnitude greater than the rock is even less pronounced.

CHAPTER 6

SUMMARY AND CONCLUSIONS

Cement and clay plugs have been tested under varying stress conditions in boreholes drilled in granite, basalt, and tuff. In addition, a plug in a granite sample and a plug in a basalt sample were subjected to temperature/moisture variations. One test in a granite sample compared drilling damage induced by percussion drilling to that induced by diamond drilling.

Summary of Results

Testing of cement plugs in the Charcoal Granite and in the Sentinel Gap Basalt indicates that flow rates through a plugged rock sample are similar to those through the intact rock for the Charcoal Granite, but are greater through the plugged samples of basalt compared to intact basalt.

Table 6.1 is a summary of the rock and plug permeability data obtained. The permeability of the Charcoal Granite ranged from 52 to 85 nanodarcy, depending on the effective stress state of the rock. Results for the three samples tested using cement plugs were similar. Flow rates through the plugged samples were less than through the samples with rock bridge in place, Figures 4.2, 4.4, and 4.9. Only when the triaxial stresses on the sample were lowered to about 1/3 their initial value did flow through the plugged sample

Table 6.1 Summary of Rock and Plug Permeability Data

Rock Type	Rock Permeability ($\times 10^{-9}$ darcy)	Equivalent Plug Permeability* ($\times 10^{-9}$ darcy)	Comments
Charcoal Granite	52-85	Less than rock	Cement plugs
Sentinel Gap Basalt	0.16-0.17	10-73	Cement plugs
Oracle Granite w/ fracture	60,000		
w/o fracture	9	8,000	Cement plug
Topopah Spring Tuff	1700-4800	$2.5 \times 10^6 - 2000$	Cement plug
		95	Cement core tested (see Ch. 3)
Charcoal Granite	85	9,000	Bentonite plug
		50,000 - 100,000	Falling head test (see Ch. 3)

*Permeabilities were calculated using both flow through the plug body and flow along the rock/plug interface.

exceed flow through the intact rock at the highest stress level. As the data from Sample CG-104 show (Figures 4.28, 5.8, and 5.9), this is most likely due to increased rock permeability with decreasing stress level rather than increased flow through the plug or along the rock/plug interface.

A permeability of 0.16-0.17 nanodarcy was measured for the intact Sentinel Gap Basalt. Replacing the rock bridge by a cement plug resulted in increased flow rate (Figures 4.14 and 4.17), and the measured permeability of the cement plugs was between 10 and 73 nanodarcy. Lowering the triaxial stress state on the plugged basalt samples did not significantly affect the flow rate, indicating that a cement plug placed in a rock mechanically similar to this basalt will not be adversely affected by a decrease in stress state. (The basalt used in this experiment is a stiff rock, having a Young's modulus of 11.5×10^6 MPa, compared to 6.89×10^3 MPa for the cement. The basalt would not be expected to undergo large strains as it is unloaded.)

The permeability measured for the cement plugs in the basalt samples, 10 to 73 nanodarcy, is slightly lower than the range of the measured Charcoal Granite permeabilities. It is also close to the 95 nanodarcy permeability measured for a cement core in a constant head test (Chapter 3). A hole in basalt plugged with cement is similar to a very small granite plug cutting the basalt.

Results obtained for the Oracle Granite are somewhat at variance with those obtained for the Charcoal Granite. An intact rock permeability of 9 nanodarcy was measured. In addition, an equivalent

porous medium permeability of 60,000 nanodarcy was measured for a portion of the rock containing a fracture, illustrating the great increase in permeability of a fractured rock compared to intact rock. The cement permeability measured in this test was 8000 nanodarcy.

Since the boundary conditions on this sample were different from all the other samples tested - it was the first sample tested and the sides were not sealed with epoxy - comparisons are complicated. The intact rock was almost an order of magnitude less permeable than the Charcoal granite. This was somewhat unexpected, since the Oracle Granite was much coarser-grained than the Charcoal Granite and it was expected that coarser-grained rocks would be more permeable, based on the greater permeabilities measured for the phaneritic Charcoal Granite as compared to the aphanitic Sentinel Gap Basalt. Examination of the photomicrographs (Figures 3.2 and 3.3) also would seem to indicate that the fissured Oracle Granite should not be less permeable than the Charcoal Granite. It is, however, possible that ground water flowing through the rock has effectively sealed many of the microfissures with mineral deposits such as calcite.

The permeability calculated for the cement plug placed in the Oracle Granite is two orders of magnitude greater than the measured permeability of any of the cement plugs placed in the Charcoal Granite and Sentinel Gap Basalt, as well as the cement core.

Further testing of the Oracle Granite is necessary if the reason for the variance in data between it and the Charcoal Granite is to be

established. However, a permeability of 8000 nanodarcy (8 microdarcy) is still a very low permeability, less than the permeability of what is generally considered "impervious" clay (Sowers and Sowers, 1970, p. 93).

The permeability of the Topopah Spring Tuff was measured as 1700-4800 nanodarcy. Plugging of the tuff resulted in an initial cement plug permeability of 2.5×10^6 nanodarcy (2.5 millidarcy), but the permeability decreased to about the same as for the tuff after a month. The initial high permeability of the plug is believed to have resulted from an alkali-aggregate reaction between the cement and the plug. The reason for the reduction in permeability with time is not known.

Several clay plugs were placed in a Charcoal Granite sample. All had permeabilities of less than 9000 nanodarcy, which is in agreement with the range of permeability of "impervious" clay reported by Sowers and Sowers (1970, p93) of less than 100,000 nanodarcy. Permeability of the clay plug tested in the falling head test was 50,000 to 100,000 nanodarcy. The lower permeability of the plugs placed in the Charcoal Granite is believed to be due to compaction of the clay by hydraulic pressure as the injection pressure was increased.

Two samples were subjected to drying to ascertain the effects of temperature/moisture variations. Sample CCR-P-100 was dried at room temperature for 27 days. This was found to slightly impair the performance of its cement plug. Sample SGE-2-2 was dried for 42 days at a temperature of 54°C. This severely impaired plug performance, increasing plug permeability from about 10 to 60 nanodarcy to a value

of 190,000 nanodarcy. As flow continued the plug became less permeable, reaching a value of 2500 nanodarcy after 50 days. Increasing the triaxial stress state on the sample did not greatly affect plug permeability (Table 5.4).

The effect of different drilling methods was evaluated using samples CCR-P-100 and CCR-D-100. The center hole in Sample CCR-P-100 was drilled using a percussion drill and the center hole in Sample CCR-D-100 was drilled using a diamond core bit. Flow rates through both samples after plugging were similar, indicating the percussion-drilled hole does not have a surrounding damage zone significantly different than the diamond-drilled hole. Flow rates through both plugged samples were less than the flow rate through intact rock (Sample CCR-D-100 with rock bridge).

Conclusions

Cement Plugs

The cement plugs tested performed about as well as intact Charcoal Granite, but not as well as intact basalt. A plug of this cement, if properly placed in a fractured rock mass (and all rock masses are fractured to some degree), could reasonably be expected to be considerably less permeable than the rock mass. The highest permeability measured was the equivalent porous medium permeability of the fractured portion of the Oracle Granite.

Based on the dye tests performed, the rock/plug interface zone is not a preferential migration path in the granites tested. Some dye

did penetrate along the plug/basalt interface in Sample SGE-2-3, but this was a sample of intact basalt. It is expected that if a fracture were intersected the dye would flow into it, leaving the interface region. Variation of the triaxial stress state on the two basalt samples did not significantly affect flow through the cement plugs, nor was the basalt permeability measurably affected. Increased flow rates in the Charcoal and Catalina granites with decreasing triaxial stress state is due to variation of rock permeability, rather than plug permeability.

The rock samples used had a higher Young's modulus than the cement plugs. Decreasing the triaxial stress state on a rock/plug combination in which the rock is softer than the plug could yield different results.

Finally, (1) More work is needed to ascertain why the results obtained in the test using Oracle Granite are at variance with the tests on the other rock types that used cement as the plug material; (2) Damage about a borehole induced by percussion drilling is comparable to that produced by diamond drilling, and is very small in both cases; (3) Temperature/moisture variations seem more important in degrading plug quality than do stress variations; (4) Low alkali cement, or another type of sealant, should be used in rocks containing amorphous or cryptocrystalline silica, such as the Topopah Spring Tuff. This may be even more important for shaft and tunnel linings than borehole seals.

Bentonite Plugs

Plugs formed by bentonite tablets are more permeable than intact rock, but probably no more permeable than a fractured rock mass. The bentonite tablets are easy to place and form a clay seal of low permeability.

Discussion

The main conclusion reached as a result of these experiments is that currently existing materials are capable of forming high quality seals when placed under laboratory conditions. Variation of triaxial stress state about a borehole does not significantly affect seal performance if the rock is stiffer than the seal material. Temperature/moisture variations, specifically, heating in air and allowing the cement to dry, degraded cement plug performance significantly over even the relatively short term of six weeks. Performance partially recovered upon resaturation.

This work has involved testing seals placed in intact rock. In a field situation the rock being sealed would be a fractured rock mass. As the experiments involving Oracle Granite showed, fractures in a rock mass greatly increase its permeability. A skillfully sealed borehole may reasonably be expected to be as impermeable as a fractured rock mass, and fluid flowing through the seal would likely leave the seal through fractures intersecting the borehole. Of course, site specific verification of this expectation must be performed.

The influence of relative plug-rock permeabilities, discussed at the end of Chapter 5, also provide insight to important seal parameters. As long as the seal is not more than one order of magnitude more permeable than the rock mass through which it passes, the flow through the plug and the rock immediately surrounding it is not greatly affected. Since a sealed borehole and its surrounding rock are only a small part of the total rock mass, the effect is even less pronounced. In addition, the model used is for a plug sealing the center third of a rock cylinder. One of the simplest ways to decrease flow through the system would be to simply increase the length of the plug.

Significant remaining questions include field emplacement techniques; field verification of plug quality; plug performance over long time periods, particularly with respect to temperature/moisture variations and chemical stability; and radionuclide sorption capabilities of the plug material. Scale effects are also important, as shafts and drifts must be sealed as well as larger diameter boreholes.

Continuing on the subject of scale effects, cement and clay materials have a very small grain size with respect to the borehole dimensions used in these experiments, so size effects would not be expected in this regard. However, a larger plug involves more volume, and there is a greater chance of having a defect in the plug. In addition, scale effects upon emplacement techniques could be significant. For example, a large pour of cement to form a shaft plug would result in a greater thermal effect from the heat of hydration than

placing a cement borehole plug due simply to the greater volume involved.

In both shafts and tunnels scale effects include both the greater volume of material involved and the greater interface area between the plug and the rock. Scale effects due to volume would be related to the cube of the opening size, whereas interface effects would vary as the square of the opening size. Thus, defects involving the interface could be expected to have lesser impact on the system performance than defects involving the plug body.

Suggestions for Further Research

Suggestions for further research are:

(1) The highest priority for further laboratory research is to more closely simulate field emplacement techniques and to evaluate plug longevity and failure modes.

(2) Field tests to evaluate emplacement techniques and quality verification procedures should be conducted. The effect of leaving steel casing in a hole should be evaluated. In this regard a test facility in which holes could be drilled into underground workings to allow access to both ends of the hole is highly desirable.

(3) The need for further laboratory tests at higher stress levels should be evaluated. Heating of the rock due to waste emplacement as well as stress redistributions due to mining may lead to higher stress levels than used in these experiments. In addition, the effect of various rock/plug stiffness combinations on sealing performance should be evaluated.

(4) Numerical analysis should be performed to evaluate the effective stress distribution throughout a plugged sample. This would be an important addition to the data base regarding borehole sealing. The effective stress distribution will depend on the stiffness of both the rock and plug material and on the permeability of the rock and plug material. The stiffness of the rock and plug material will determine the stress distribution due to the imposed triaxial stress state. The relative permeabilities of the rock and plug material will determine the pore pressure distribution due to the water flowing through the rock and may be subtracted point-wise from the stress distribution due to the imposed triaxial stress state to determine the effective stress distribution.

(5) Plugs should be tested in the laboratory under varying pressure, temperature, and moisture conditions. In particular, plugs should be placed under water and in holes filled with drilling mud, and cured under simulated downhole fluid pressures.

(6) Tests of borehole plugs in fractured rock samples should be performed to evaluate the relative flow amounts through the plug as compared to the fractures. In addition, fracture grouting experiments would help ascertain the effectiveness of sealing the rock around boreholes.

(7) The effects of water chemistry on curing of cement, swelling of clay, and longevity of plug materials should be evaluated in the context of long-term sealing against radionuclide migration.

(8) A borehole plug is likely to involve both cement, for its strength and low permeability properties, and clay, for its sorptive properties and ability to deform without cracking. Experiments should include interaction effects of multi-component plugs.

(9) Plugging experiments should be performed on salt, shale, and clay, which are also potential repository host rocks.

(10) Additional experiments should be performed using clay. More experiments on bentonite tablets would expand the data base. Experiments on compacted clay would provide useful data on a potential shaft sealing and tunnel backfill method.

(11) Additional tests on cement should use cement formulations thought to have good longevity characteristics.

(12) Plugging techniques useful in horizontal holes and "up" holes (holes drilled upward from underground workings) should be evaluated.

(13) Size effects should be investigated. Cement and clay may be used to fill both shafts and tunnels. This has the effect of increasing plug volume with respect to interface area. In the case of cement, temperatures due to the heat of hydration would be higher in a shaft than in a borehole as a result of the greater mass of cement required.

(14) Any actual repository will require site specific testing of the rocks and the seal materials to be used. Development of reliable, standardized testing procedures is necessary.

APPENDIX A

TEST RESULTS

Table A.1 Test Results for Sample CG-101

Date	Elapsed Time (min)	Axial Stress (MPa)	Confining Stress (MPa)	Top Pressure (MPa)	Bottom Pressure (MPa)	Flow Rate In ($\times 10^{-3}$ cc/min)	Flow Rate Out ($\times 10^{-3}$ cc/min)	Mass Balance (%)	Notes
<u>Tests on Rock Bridge</u>									
1/13-1/14	1215	22.8	19.6	10.1	0	5.40	5.40	0.0	
1/14-1/15	1367	22.9	19.8	10.0	0	6.36	6.02	-5.3	
1/15-1/16	1437	<u>22.8</u>	<u>19.7</u>	<u>9.9</u>	<u>0</u>	<u>5.29</u>	<u>5.85</u>	<u>10.6</u>	
Weighted Averages:		22.8	19.7	10.0	0	5.69	5.77	1.4	b
1/17-1/18	1107	22.8	19.8	6.7	0	2.78	3.31	19.1	a
1/18-1/19	1637	22.8	19.6	6.9	0	3.14	3.48	10.8	
1/19-1/20	1237	22.9	19.8	6.9	0	3.00	3.38	12.7	
1/20-1/21	1042	22.9	19.7	6.9	0	2.85	3.21	12.6	
1/21-1/22	1354	<u>22.9</u>	<u>19.6</u>	<u>6.9</u>	<u>0</u>	<u>2.91</u>	<u>3.06</u>	<u>5.2</u>	
Weighted Averages:		22.9	19.7	6.9	0	2.99	3.30	10.4	b
1/22-1/23	1588	22.9	19.6	3.5	0	0.93	1.49	60.2	a
1/23-1/24	1296	22.8	19.6	3.6	0	1.37	1.50	9.5	
1/24-1/25	1110	<u>22.9</u>	<u>19.6</u>	<u>3.6</u>	<u>0</u>	<u>1.31</u>	<u>1.45</u>	<u>11.0</u>	
Weighted Averages:						1.34	1.48	10.4	b
<u>Tests on Cement 1 Plug</u> (poured at 3:40 pm, 1/25/82)									
2/5-2/6	1203	23.0	19.9	10.1	0	6.44	12.38	92.2	a
2/6-2/7	1678	22.9	19.9	10.1	0	6.23	4.83	-22.5	
2/7-2/8	1325	23.0	19.7	10.0	0	5.71	4.20	-26.4	
2/8-2/9	1342	23.0	19.6	10.0	0	5.18	4.02	-22.4	
2/9	151	23.0	19.6	10.1	0	5.17	3.05	-41.0	

Table A.1 Test Results for Sample CG-101--Continued

Date	Elapsed Time (min)	Axial Stress (MPa)	Confining Stress (MPa)	Top Pressure (MPa)	Bottom Pressure (MPa)	Flow Rate In ($\times 10^{-3}$ cc/min)	Flow Rate Out ($\times 10^{-3}$ cc/min)	Mass Balance (%)	Notes
2/9-2/10	1526	23.0	19.6	10.0	0	4.20	3.10	-26.2	
2/10-2/11	1309	22.8	16.8	9.8	0	0.32	?	?	a,c
2/12	209	22.9	19.7	10.0	0	11.29	12.58	11.4	
2/12-2/13	1031	22.9	19.6	9.8	0	9.15	9.15	0.0	
2/13-2/14	1714	23.0	19.6	10.1	0	6.45	7.47	15.8	
2/14-2/15	1141	23.0	19.6	10.1	0	5.17	5.28	2.1	
2/15-2/16	1528	23.0	19.6	10.3	0	4.48	4.66	4.0	
2/16-2/17	1062	23.0	19.5	10.2	0	3.86	4.01	3.9	
2/17-2/18	1450	23.0	19.8	10.1	0	3.51	4.19	19.4	
2/18-2/19	1565	23.0	19.7	9.9	0	3.28	3.31	0.9	
2/19-2/20	1277	23.0	19.6	9.8	0	3.07	2.93	-4.6	
2/20-2/21	1155	23.0	19.6	10.2	0	3.20	3.59	12.2	
2/21-2/22	1336	23.1	19.7	10.1	0	3.07	3.72	21.2	
Weighted Averages:		23.0	19.7	10.1	0	4.81	4.65	-3.3	b
2/22-2/23	1105	23.1	19.4	7.0	0	1.94	1.75	-9.8	
2/23-2/24	1370	23.0	19.7	7.0	0	1.77	1.01	-42.9	
2/24-2/25	1484	23.0	19.6	7.0	0	1.71	1.20	-29.8	
2/25-2/26	1329	23.0	19.7	6.9	0	1.67	1.27	-24.0	
2/26-2/27	1539	23.0	19.6	6.9	0	1.62	1.29	-20.4	
2/27-3/1	2893	23.0	19.6	6.9	0	1.62	1.19	-26.5	
3/1-3/2	1383	23.0	19.7	6.9	0	1.60	1.07	-33.1	
3/2-3/3	1539	23.0	19.7	6.9	0	1.53	1.23	-19.6	
3/3-3/4	1356	23.0	19.6	6.9	0	1.55	0.84	-45.8	
Weighted Averages:		23.0	19.6	6.9	0	1.66	1.19	-28.3	b

Table A.1 Test Results for Sample CG-101--Continued

Date	Elapsed Time (min)	Axial Stress (MPa)	Confining Stress (MPa)	Top Pressure (MPa)	Bottom Pressure (MPa)	Flow Rate In ($\times 10^{-3}$ cc/min)	Flow Rate Out ($\times 10^{-3}$ cc/min)	Mass Balance (%)	Notes
3/4-3/5	1449	23.0	19.5	3.4	0	0.14	0.01	-92.9	a
3/5-3/6	1542	22.9	19.6	3.6	0	0.71	-0.08	-	a,d
3/6-3/8	2875	22.9	19.6	3.5	0	0.65	0.02	-96.9	a
3/8-3/9	1429	22.9	19.5	3.5	0	0.69	0.02	-97.1	a
3/9-3/11	2872	22.9	19.5	3.5	0	0.66	0.52	-21.2	
3/11-3/12	1692	22.9	19.1	3.6	0	0.67	0.44	-34.3	e
3/12-3/13	1237	22.9	19.6	3.6	0	0.65	0.61	-6.2	
3/13-3/15	2806	22.9	19.6	3.4	0	0.56	0.35	-37.5	
3/15-3/16	1519	22.9	19.6	3.5	0	0.49	0.49	0.0	
Weighted Averages:		22.9	19.5	3.5	0	0.61	0.47	-23.0	b
3/16-3/17	1443	23.0	19.6	9.9	0	14.16	?	?	a,f
3/17-3/18	1201	23.0	19.6	10.1	0	3.18	3.27	2.8	
3/18-3/19	1689	23.0	19.6	9.9	0	2.57	2.54	-1.2	
3/19-3/20	1255	23.0	19.7	10.1	0	2.62	2.83	8.0	
Weighted Averages:		23.0	19.6	10.0	0	2.76	2.84	2.9	b
3/20-3/22	2797	23.0	19.2	7.0	0	1.51	1.58	4.6	
3/22-3/23	1540	23.0	19.6	7.1	0	1.43	1.36	-4.9	
Weighted Averages:		23.0	19.3	7.0	0	1.48	1.50	1.4	b
3/23-3/24	1451	23.0	19.5	3.4	0	0.56	0	-100.0	a
3/24-3/25	1020	22.9	19.6	3.4	0	0.68	?	?	a,g

Table A.1 Test Results for Sample CG-101--Continued

Date	Elapsed Time (min)	Axial Stress (MPa)	Confining Stress (MPa)	Top Pressure (MPa)	Bottom Pressure (MPa)	Flow Rate In ($\times 10^{-3}$ cc/min)	Flow Rate Out ($\times 10^{-3}$ cc/min)	Mass Balance (%)	Notes
3/25-3/26	1161	22.9	19.7	3.5	0	0.81	1.39	71.6	
3/26-3/27	1000	22.9	19.7	3.4	0	0.56	0.10	-82.1	
3/27-3/29	3030	22.9	19.6	3.4	0	0.58	0.83	43.1	
3/29-3/30	1418	22.9	19.7	3.4	0	0.82	-0.44	-153.7	d
3/30-3/31	1500	22.9	19.6	3.4	0	0.84	0	-100.0	
3/31-4/1	1735	22.9	19.7	3.4	0	0.55	1.25	127.3	
4/1-4/2	1016	22.9	19.6	3.4	0	0.52	0	-100.0	
4/3-4/5	2542	22.9	19.6	3.4	0	0.55	0.74	34.5	
Weighted Averages:		22.9	19.6	3.4	0	0.64	0.57	-10.9	b
4/5-4/6	1592	15.2	13.8	3.4	0	0.93	0.01	-98.9	a
4/6-4/7	1020	15.3	13.8	3.5	0	0.75	-0.01	-101.3	a,d
4/7-4/8	1804	15.3	13.8	3.5	0	0.73	0.81	11.0	a
4/8-4/9	1131	15.3	13.8	3.5	0	0.68	-0.01	-101.5	a,d
4/9-4/10	1491	15.3	13.8	3.5	0	0.75	0.77	2.7	
4/10-4/12	2989	15.3	13.7	3.5	0	0.72	0.59	-18.1	
Weighted Averages:		15.3	13.7	3.5	0	0.73	0.65	-11.0	b
4/12-4/13	1325	15.5	13.8	7.0	0	1.78	1.95	9.6	
4/13-4/14	1039	15.5	13.8	7.1	0	1.91	1.87	-2.1	
Weighted Averages:		15.5	13.8	7.0	0	1.84	1.91	3.8	b

NOTE: At 5:00 pm on 4/14 the annular valve was opened at the wrong time, letting the confining pressure drop to zero. The confining pressure was again applied (13.8 MPa) and the test continued.

Table A.1 Test Results for Sample CG-101--Continued

Date	Elapsed Time (min)	Axial Stress (MPa)	Confining Stress (MPa)	Top Pressure (MPa)	Bottom Pressure (MPa)	Flow Rate In ($\times 10^{-3}$ cc/min)	Flow Rate Out ($\times 10^{-3}$ cc/min)	Mass Balance (%)	Notes
4/14-4/15	1046	15.5	13.9	7.0	0	7.35	7.33	-0.3	a
4/15-4/17	2414	15.6	13.8	6.9	0	3.15	2.99	-5.1	a
4/17-4/19	3257	15.6	13.8	6.7	0	2.32	2.32	0.0	a
4/19-4/20	1450	15.6	13.8	6.9	0	2.19	2.20	0.5	
4/20-4/21	1364	15.6	13.7	6.9	0	2.12	2.03	-4.2	
4/21-4/22	1472	15.6	13.7	6.9	0	2.26	2.06	-8.8	
Weighted Averages:		15.6	13.7	6.9	0	2.19	2.10	-4.1	b
4/22-4/23	1394	15.6	13.9	9.9	0	4.25	3.97	-6.6	
4/23-4/26	3959	15.7	13.5	-	0	2.19	2.67	21.9	a,h
4/26-4/27	1607	15.7	14.1	10.2	0	4.28	3.85	-10.0	
Weighted Averages:		15.7	14.0	10.1	0	4.27	3.91	-8.4	b
4/27-4/28	1617	15.7	13.3	3.3	0	0.54	0.92	70.4	a
4/28-4/29	1206	15.7	13.8	3.6	0	0.95	0.95	0.0	
4/29-5/2	4465	15.7	13.8	3.6	0	0.95	0.95	0.0	
Weighted Averages:		15.7	13.8	3.6	0	0.95	0.95	0.0	b
5/2-5/4	2826	8.4	7.1	3.6	0	2.39	1.92	-19.7	a
5/4-5/6	2714	8.5	6.9	3.5	0	2.14	2.00	-6.5	
Weighted Averages:		8.5	6.9	3.5	0	2.14	2.00	-6.5	b
5/6-5/7	1423	8.5	6.8	1.7	0	0.96	1.15	19.8	a
5/7-5/8	1477	8.5	6.8	1.7	0	0.89	1.08	21.3	a

Table A.1 Test Results for Sample CG-101--Continued

Date	Elapsed Time (min)	Axial Stress (MPa)	Confining Stress (MPa)	Top Pressure (MPa)	Bottom Pressure (MPa)	Flow Rate In ($\times 10^{-3}$ cc/min)	Flow Rate Out ($\times 10^{-3}$ cc/min)	Mass Balance (%)	Notes
5/8-5/10	2975	8.5	7.0	1.7	0	0.90	0.91	1.1	
5/10-5/13	3993	<u>8.5</u>	<u>6.8</u>	<u>1.7</u>	<u>0</u>	<u>0.89</u>	<u>0.83</u>	<u>-6.7</u>	
Weighted Averages:		8.5	6.9	1.7	0	0.89	0.86	-3.4	b

NOTES:

- (a) Datum not included in average.
- (b) Averages weighted with respect to elapsed time.
- (c) During this test (2/10-2/11) annular pressure dropped from 19.7 MPa to 13.8 Mpa, probably due to excess leakage through end seals. The flask collecting fluid from the bottom hole overflowed.
- (d) Bottom flask weighed less at end of test than at beginning, indicating flow back into the sample. Possibly misread scale.
- (e) Some leakage from annular valve.
- (f) Bottom flask overflowed.
- (g) Bottom flask not replaced. No measurement.
- (h) N_2 tank exhausted. P_t fell from 9.9 to 1.8 MPa. σ_c fell from 13.9 to 13.1 MPa as P_t fell.

Table A.2 Test Results for Sample CG-102

Date	Elapsed Time (min)	Axial Stress (MPa)	Confining Stress (MPa)	Top Pressure (MPa)	Bottom Pressure (MPa)	Flow Rate In ($\times 10^{-3}$ cc/min)	Flow Rate Out ($\times 10^{-3}$ cc/min)	Mass Balance (%)	Notes
<u>Tests on Rock Bridge</u>									
1/20-1/21	997	21.2	19.7	10.1	0	4.12	4.24	2.9	a
1/21-1/22	1402	21.2	19.8	10.1	0	5.27	4.02	-23.7	a
1/25-1/26	1274	23.0	19.7	9.4	0	3.30	3.77	14.2	a,c
1/26-1/27	1376	23.0	19.8	10.1	0	4.64	4.91	5.8	
1/27-1/28	1065	23.0	19.8	10.1	0	4.91	6.12	24.6	
1/28-1/29	1267	<u>23.0</u>	<u>19.7</u>	<u>10.1</u>	<u>0</u>	<u>4.85</u>	<u>5.26</u>	<u>8.5</u>	
Weighted Averages:		23.0	19.7	10.1	0	4.79	5.38	12.1	b
1/29-1/30	1372	<u>22.9</u>	<u>19.7</u>	<u>7.0</u>	<u>0</u>	<u>3.06</u>	<u>3.30</u>	<u>9.1</u>	
Weighted Averages:		22.9	19.7	7.0	0	3.06	3.30	9.1	b
1/30-1/31	32	22.9	19.7	3.5	0	57.81	78.25	35.4	a
1/31-2/1	1239	22.9	19.7	3.5	0	1.32	0.29	-78.0	a
2/1-2/2	1506	22.8	19.7	3.5	0	1.30	1.57	20.8	
2/2/-2/3	972	<u>22.9</u>	<u>19.6</u>	<u>3.5</u>	<u>0</u>	<u>1.33</u>	<u>1.75</u>	<u>31.6</u>	
Weighted Averages:		22.8	19.6	3.5	0	1.31	1.64	25.0	b

Table A.2 Test Results for Sample CG-102--Continued

Date	Elapsed Time (min)	Axial Stress (MPa)	Confining Stress (MPa)	Top Pressure (MPa)	Bottom Pressure (MPa)	Flow Rate In ($\times 10^{-3}$ cc/min)	Flow Rate Out ($\times 10^{-3}$ cc/min)	Mass Balance (%)	Notes
Tests on Cement 1 Plug (poured at 2:10 pm, 2/6/82)									
2/13-2/14	1098	22.8	19.7	10.1	0	7.40	7.52	1.6	
2/14-2/15	1280	22.8	19.7	9.9	0	5.84	7.89	35.1	
2/15-2/16	1750	22.9	19.4	10.2	0	5.51	6.67	21.1	
2/16-2/17	1147	22.9	19.6	9.9	0	4.38	5.30	21.0	
2/17-2/18	1361	22.9	19.8	10.2	0	4.40	4.90	11.4	
2/18-2/19	1597	22.9	19.7	10.2	0	4.01	4.48	11.7	
2/19-2/20	Data not recorded; flow continued.								
2/20-2/21	1185	22.9	19.6	10.0	0	3.49	3.86	10.6	
2/21-2/22	1335	23.0	19.9	10.0	0	3.32	3.87	16.6	
2/22-2/23	1070	23.0	19.5	10.0	0	3.38	3.53	4.4	
2/23-2/24	1383	22.9	19.7	10.0	0	3.18	3.39	6.6	
2/24-2/25	1481	22.9	19.6	10.0	0	3.15	3.29	4.4	
2/25-2/26	1364	22.9	19.6	9.9	0	3.07	3.20	4.2	
Weighted Averages:		22.9	19.7	10.0	0	4.24	4.82	12.6	b
2/26-2/27	1589	22.9	19.6	6.8	0	1.81	2.13	17.7	
2/27-3/1	2728	22.9	19.7	7.0	0	1.92	2.02	5.2	
3/1-3/2	1458	22.9	19.6	7.0	0	1.91	-0.09	-	a,d
3/2-3/3	1511	22.9	19.7	7.0	0	1.83	2.02	10.4	
3/3-3/4	1337	22.9	19.6	7.0	0	1.82	2.00	9.9	
Weighted Averages:		22.9	19.7	7.0	0	1.86	2.04	9.9	b

Table A.2 Test Results for Sample CG-102--Continued

Date	Elapsed Time (min)	Axial Stress (MPa)	Confining Stress (MPa)	Top Pressure (MPa)	Bottom Pressure (MPa)	Flow Rate In (x 10 ⁻³ cc/min)	Flow Rate Out (x 10 ⁻³ cc/min)	Mass Balance (%)	Notes
<u>Tests on Cement 1 Plug (continued)</u>									
3/4-3/5	1515	22.9	19.6	3.3	0	0.25	0.73	192.0	a
3/5-3/6	1533	22.8	19.7	3.6	0	0.85	1.06	24.7	
3/6-3/8	2787	22.8	19.6	3.5	0	0.76	0.90	18.4	
3/8-3/9	1541	<u>22.8</u>	<u>19.5</u>	<u>3.5</u>	<u>0</u>	<u>0.76</u>	<u>0.80</u>	<u>5.3</u>	
Weighted Averages:		22.8	19.6	3.5	0	0.78	0.92	16.6	b
3/9-3/11	2835	22.8	19.7	10.0	0	2.76	2.77	0.4	
3/11-3/13	2926	<u>22.9</u>	<u>19.6</u>	<u>9.9</u>	<u>0</u>	<u>2.63</u>	<u>2.69</u>	<u>2.3</u>	
Weighted Averages:		22.9	19.7	10.0	0	2.69	2.73	1.4	b
3/13-3/15	2769	22.9	19.7	6.8	0	1.46	1.69	15.8	
3/15-3/16	1494	<u>22.9</u>	<u>19.5</u>	<u>7.0</u>	<u>0</u>	<u>1.77</u>	<u>1.71</u>	<u>3.4</u>	
Weighted Averages:		22.9	19.6	6.9	0	1.57	1.70	9.1	b
3/16-3/18	2755	22.8	19.6	3.4	0	0.42	0.84	100.0	a
3/18-3/19	1523	22.8	19.7	3.4	0	0.68	0.75	10.3	
3/19-3/20	1462	<u>22.8</u>	<u>19.6</u>	<u>3.4</u>	<u>0</u>	<u>0.68</u>	<u>0.83</u>	<u>22.1</u>	
Weighted Averages:		22.8	19.7	3.4	0	0.68	0.79	16.1	b
3/20-3/22	2707	15.3	13.8	3.4	0	1.01	0.99	-2.0	a
3/22-3/23	1541	15.4	13.8	3.4	0	1.94	0.95	-51.0	a
3/23-3/24	1468	15.5	13.6	3.3	0	1.14	1.05	-7.9	
3/24-3/25	1059	15.5	13.9	3.5	0	1.23	0.88	-28.5	

Table A.2 Test Results for Sample CG-102--Continued

Date	Elapsed Time (min)	Axial Stress (MPa)	Confining Stress (MPa)	Top Pressure (MPa)	Bottom Pressure (MPa)	Flow Rate In ($\times 10^{-3}$ cc/min)	Flow Rate Out ($\times 10^{-3}$ cc/min)	Mass Balance (%)	Notes
<u>Tests on Cement 1 Plug (continued)</u>									
3/25-3/26	1187	15.5	13.8	3.5	0	1.24	1.10	-11.3	
3/26-3/27	1016	<u>15.5</u>	<u>13.9</u>	<u>3.6</u>	<u>0</u>	<u>1.12</u>	<u>0.98</u>	<u>-12.5</u>	
Weighted Averages:		15.4	13.8	3.5	0	1.18	1.01	-14.4	b
3/27-3/29	3038	15.5	13.9	7.0	0	2.83	2.36	-16.6	
3/29-3/30	1419	15.6	13.8	7.0	0	2.63	-2.70	-	a,d
3/30-3/31	1451	<u>15.6</u>	<u>13.8</u>	<u>7.0</u>	<u>0</u>	<u>2.53</u>	<u>2.34</u>	<u>-7.5</u>	
Weighted Averages:		15.5	13.8	7.0	0	2.73	2.35	-13.7	b
3/31-4/1	1798	15.7	13.9	10.1	0	5.12	4.56	-10.9	
4/1-4/2	960	15.8	14.0	10.0	0	4.81	4.67	-2.9	
4/3-4/5	2588	<u>15.8</u>	<u>13.9</u>	<u>10.1</u>	<u>0</u>	<u>4.51</u>	<u>4.44</u>	<u>-1.6</u>	
Weighted Averages:		15.8	13.9	10.1	0	4.77	4.52	-5.0	b
4/5-4/6	1584	15.6	13.6	3.4	0	0.74	1.22	64.9	a
4/6-4/7	1099	<u>15.7</u>	<u>13.8</u>	<u>3.5</u>	<u>0</u>	<u>1.05</u>	<u>1.06</u>	<u>1.0</u>	
Weighted Averages:		15.7	13.8	3.5	0	1.05	1.06	1.0	b
4/7-4/8	1638	8.5	7.1	3.4	0	2.28	2.03	-11.0	
4/8-4/9	1129	<u>8.6</u>	<u>6.9</u>	<u>3.4</u>	<u>0</u>	<u>2.24</u>	<u>2.21</u>	<u>-1.3</u>	
Weighted Averages:		8.5	7.0	3.4	0	2.26	2.10	-7.0	b

Table A.2 Tests Results for Sample CG-102--Continued

Date	Elapsed Time (min)	Axial Stress (MPa)	Confining Stress (MPa)	Top Pressure (MPa)	Bottom Pressure (MPa)	Flow Rate In ($\times 10^{-3}$ cc/min)	Flow Rate Out ($\times 10^{-3}$ cc/min)	Mass Balance (%)	Notes
4/9-4/10	1489	8.6	6.8	1.7	0	0.77	1.10	42.9	a
4/10-4/12	2963	8.5	6.9	1.8	0	1.00	1.03	3.0	
4/12-4/13	1304	8.6	6.9	1.7	0	0.92	1.03	12.0	
4/13-4/14	1073	8.6	6.9	1.7	0	0.99	1.02	3.0	
Weighted Averages:		8.6	6.9	1.7	0	0.98	1.03	5.2	b

Notes:

- (a) Datum not included in average
- (b) Averages weighted with respect to elapsed time
- (c) Ran out of N₂; top pressure fell from 1460 to 1280 psi.
- (d) Negative flow rate out indicates flow back into sample. Possibly misread instrument.

Table A.3 Test Results for Sample CG-103

Date	Elapsed Time (min)	Axial Stress (MPa)	Confining Stress (MPa)	Top Pressure (MPa)	Bottom Pressure (MPa)	Flow Rate In ($\times 10^{-3}$ cc/min)	Flow Rate Out ($\times 10^{-3}$ cc/min)	Mass Balance (%)	Notes
Tests on Rock Bridge									
1/28-1/29	998	22.8	19.6	10.2	0	5.80	7.51	29.5	a
1/29-1/30	1547	22.8	19.6	10.2	0	5.69	6.53	14.8	
1/30-1/31	1611	22.8	19.6	10.2	0	5.76	6.29	9.2	
1/31-2/1	1297	<u>22.8</u>	<u>19.7</u>	<u>10.1</u>	<u>0</u>	<u>5.26</u>	<u>5.61</u>	<u>6.7</u>	
Weighted Averages:		22.8	19.6	10.2	0	5.59	6.18	10.6	b
2/1-2/2	1132	22.8	19.8	6.9	0	3.27	3.55	8.6	
2/2-2/3	1034	<u>22.7</u>	<u>19.6</u>	<u>6.8</u>	<u>0</u>	<u>3.23</u>	<u>3.46</u>	<u>7.1</u>	
Weighted Averages:		22.8	19.7	6.9	0	3.25	3.51	8.0	b
2/3-2/4	1320	22.7	19.5	3.4	0	1.30	1.55	19.2	
2/4-2/5	1121	22.7	19.6	3.5	0	1.32	1.46	10.6	
2/5-2/5	1362	22.7	19.6	3.5	0	1.24	1.53	23.4	
2/6-2/7	1720	22.7	19.6	3.5	0	1.27	1.58	24.4	
2/7-2/8	1277	22.7	19.7	3.4	0	1.22	1.49	22.1	
2/8-2/9	1326	22.7	19.6	3.4	0	1.22	1.49	22.1	
2/9-2/10	1759	22.7	19.6	3.4	0	1.22	1.53	26.2	
2/10-2/11	1317	<u>22.7</u>	<u>19.6</u>	<u>3.4</u>	<u>0</u>	<u>1.22</u>	<u>1.64</u>	<u>34.4</u>	
Weighted Averages:		22.7	19.6	3.4	0	1.25	1.54	23.2	b
Tests on Cement 1 Plug (Poured at 1:25 pm, 2/13/82)									
2/20-2/21	1213	22.9	19.8	10.0	0	14.81	-	-	a,c
2/22-2/23	1024	23.0	19.5	10.2	0	10.64	-	-	a,c
2/23	363	22.9	19.6	10.2	0	9.48	20.92	120.7	a

Table A.3 Test Results for Sample CG-103--Continued

Date	Elapsed Time (min)	Axial Stress (MPa)	Confining Stress (MPa)	Top Pressure (MPa)	Bottom Pressure (MPa)	Flow Rate In ($\times 10^{-3}$ cc/min)	Flow Rate Out ($\times 10^{-3}$ cc/min)	Mass Balance (%)	Notes
2/23-2/24	1002	22.9	19.6	10.2	0	8.83	15.75	78.4	a
2/24	480	22.9	19.7	10.3	0	8.21	13.77	67.7	a
2/24-2/25	982	22.9	19.7	10.3	0	7.83	6.51	-16.9	
2/25-2/26	1404	22.9	19.6	10.3	0	7.31	6.92	-5.3	
2/26-2/27	1587	22.9	19.6	10.3	0	6.84	7.57	10.7	
2/27-3/1	2642	22.8	19.5	6.5	0	3.02	3.86	27.8	a,d
3/1-3/2	1579	22.9	19.8	10.0	0	5.45	4.56	-16.3	
3/2-3/3	1385	22.9	19.7	10.0	0	5.05	4.74	-6.1	
3/3-3/4	1262	22.9	19.6	10.0	0	4.91	4.25	-13.4	
Weighted Average:		22.9	19.7	10.1		6.17	5.76	-6.6	b
3/4-3/5	1568	22.8	19.7	6.9	0	2.93	3.13	6.8	
3/5-3/6	1534	22.8	19.6	6.9	0	2.72	1.68	-38.2	
3/6-3/8	2779	22.8	19.6	6.9	0	2.47	2.45	-0.8	
3/8-3/9	1576	22.8	19.6	6.9	0	2.53	1.89	-25.3	
3/9-3/11	2841	22.8	19.6	6.9	0	2.34	2.92	24.8	
3/11-3/13	2941	22.8	19.6	6.9	0	0.34	1.17	244.1	
3/13-3/15	2725	22.8	19.7	6.9	0	3.08	2.17	-29.5	
3/15-3/16	1470	22.8	19.6	6.9	0	2.28	2.39	4.8	
Weighted Averages:		22.8	19.6	6.9	0	2.24	2.20	-1.8	b
3/16-3/18	2845	22.8	19.4	3.2	0	0.52	0.33	-36.5	a
3/18-3/19	1571	22.8	19.6	3.4	0	0.77	0.80	3.9	
3/19-3/20	1337	22.7	19.6	3.4	0	0.78	0.95	21.8	
3/20-3/22	2768	22.7	19.6	3.4	0	0.75	0.95	26.7	
3/22-3/23	1090	22.7	19.6	3.4	0	0.80	0.38	-52.5	a,e

Table A.3 Test Results for Sample CG-103--Continued

Date	Elapsed Time (min)	Axial Stress (MPa)	Confining Stress (MPa)	Top Pressure (MPa)	Bottom Pressure (MPa)	Flow Rate In ($\times 10^{-3}$ cc/min)	Flow Rate Out ($\times 10^{-3}$ cc/min)	Mass Balance (%)	Notes
3/23-3/24	1478	22.7	19.6	3.4	0	0.45	0.01	-97.8	a,f
3/24-3/25	1047	22.7	19.6	3.4	0	0.20	0.00	-100.0	a,f
3/25-3/26	1212	22.7	19.6	3.4	0	0.14	0.00	-100.0	a,f
3/26-3/27	1026	22.7	19.5	3.4	0	0.11	0.01	-90.9	a,f
3/27-3/29	3041	22.7	19.7	3.4	0	0.28	0.76	171.4	a,f
3/29-3/30	1417	22.7	19.6	3.4	0	0.37	0.01	-97.3	a,f
3/30-3/31	1408	22.7	19.6	3.4	0	0.32	0.00	-100.0	a,f
3/31-4/1	1859	22.7	19.6	3.4	0	0.44	1.60	263.6	a,f
4/3-4/5	2656	22.7	19.6	3.4	0	0.28	0.37	32.1	a,f
4/5-4/6	1535	22.7	19.7	3.4	0	0.29	1.56	437.9	a,f
Weighted Averages:		22.7	19.6	3.4	0	0.43	0.61	41.9	b,h
4/6-4/7	1196	22.7	19.6	3.4	0	0.61	0.02	-96.7	a
4/7-4/8	1688	22.7	19.6	3.4	0	0.61	-0.01	-101.6	a,g
4/8-4/9	1082	22.7	19.7	3.4	0	0.59	0.00	-100.0	a
4/9-4/10	1485	22.9	19.6	3.4	0	0.61	0.00	-100.0	a
4/10-4/11	2919	22.9	19.6	3.2	0	0.56	0.64	14.3	
4/12-4/13	1241	22.9	19.6	3.4	0	0.58	1.00	72.4	
4/13-4/14	1140	22.9	19.7	3.4	0	0.57	0.01	-98.5	
4/14-4/15	1104	22.8	19.6	3.4	0	0.53	0.02	-96.2	
4/15-4/17	2415	22.7	19.5	3.4	0	0.56	.047	-16.1	
Weighted Averages:		22.8	19.6	3.3	0	0.56	0.49	-12.5	b

Table A.3 Test Results for Sample CG-103--Continued

Date	Elapsed Time (min)	Axial Stress (MPa)	Confining Stress (MPa)	Top Pres-sure (MPa)	Bottom Pres-sure (MPa)	Flow Rate In (x 10 ⁻³ cc/min)	Flow Rate Out (x 10 ⁻³ cc/min)	Mass Balance (%)	Notes
4/17-4/18	3236	22.8	19.5	10.1	0	2.93	2.70	-7.8	
4/19-4/21	2816	<u>22.8</u>	<u>19.6</u>	<u>10.1</u>	<u>0</u>	<u>2.88</u>	<u>2.78</u>	<u>-3.5</u>	
Weighted Averages:		22.8	19.5	10.1	0	2.91	2.74	-5.8	b
4/21-4/22	1445	22.8	19.4	6.9	0	1.44	1.65	14.6	
4/22-4/23	1390	22.8	19.6	7.7	0	1.55	1.54	-0.6	
4/23-4/26	3981	<u>22.8</u>	<u>19.4</u>	<u>7.0</u>	<u>0</u>	<u>1.50</u>	<u>1.34</u>	<u>-10.7</u>	
Weighted Averages:		22.8	19.4	7.1	0	1.50	1.45	-3.3	b
4/26-4/27	1571	22.8	19.8	3.2	0	0.32	0.55	77.4	a
4/27-4/29	2918	22.7	19.8	3.5	0	0.56	0.73	30.4	a
4/29-5/2	4483	<u>22.8</u>	<u>19.5</u>	<u>3.4</u>	<u>0</u>	<u>0.54</u>	<u>0.61</u>	<u>13.0</u>	
Weighted Averages:		22.8	19.5	3.4	0	0.54	0.61	13.0	b
5/2-5/4	2809	15.2	13.9	3.4	0	0.85	0.70	-17.6	a
5/4-5/6	2718	<u>15.3</u>	<u>13.8</u>	<u>3.4</u>	<u>0</u>	<u>0.73</u>	<u>0.75</u>	<u>2.7</u>	
Weighted Averages:		15.3	13.8	3.4	0	0.73	0.75	2.7	
5/6-5/7	1392	15.3	13.9	6.7	0	2.12	2.05	-3.3	a
5/7-5/8	1413	15.4	13.9	6.9	0	2.11	2.40	13.7	a
5/8-5/10	3050	15.4	13.8	6.9	0	0.26	1.71	557.7	a
5/10-5/13	4234	<u>15.4</u>	<u>13.7</u>	<u>6.8</u>	<u>0</u>	<u>1.94</u>	<u>1.94</u>	<u>0.0</u>	
Weighted Averages:		15.4	13.7	6.8	0	1.94	1.94	0.0	b

Table A.3 Test Results for Sample CG-103--Continued

Date	Elapsed Time (min)	Axial Stress (MPa)	Confining Stress (MPa)	Top Pressure (MPa)	Bottom Pressure (MPa)	Flow Rate In ($\times 10^{-3}$ cc/min)	Flow Rate Out ($\times 10^{-3}$ cc/min)	Mass Balance (%)	Notes
5/13-5/14	1255	15.4	13.7	10.0	0	0.53	1.20	126.4	a,f
5/14-5/17	4130	15.3	13.8	10.0	0	0.00	?	-	a,f,j
5/17-5/18	1531	15.3	13.7	10.1	0	0.00	0.00	-	a,f
5/18-5/19	1371	15.4	13.8	10.3	0	4.86	3.44	-29.2	a
5/19-5/20	1368	15.6	13.8	10.3	0	5.32	5.34	0.4	
5/20-5/21	1517	<u>15.6</u>	<u>13.9</u>	<u>10.3</u>	<u>0</u>	<u>5.10</u>	<u>5.15</u>	<u>1.0</u>	
Weighted Averages:		15.6	13.9	10.3	0	5.20	5.24	0.8	b
5/21-5/22	1547	15.5	13.5	3.5	0	0.60	1.38	130.0	a
5/22-5/23	1563	15.5	13.7	3.3	0	0.88	0.38	-56.8	a
5/23-5/24	1019	8.4	7.1	3.4	0	3.02	2.57	-14.9	a
5/24-5/25	1894	8.6	7.3	3.4	0	2.13	2.32	8.9	
5/25-5/26	1469	<u>8.6</u>	<u>7.3</u>	<u>3.4</u>	<u>0</u>	<u>2.15</u>	<u>2.13</u>	<u>-0.9</u>	
Weighted Averages:		8.6	7.3	3.4	0	2.14	2.24	4.7	b
5/26-5/27	1293	8.6	7.2	1.7	0	0.73	0.94	28.8	a
5/27-5/30	4411	8.6	7.0	1.8	0	0.92	0.97	5.4	
5/30-6/1	2753	<u>8.6</u>	<u>7.0</u>	<u>1.7</u>	<u>0</u>	<u>0.92</u>	<u>0.96</u>	<u>4.3</u>	
Weighted Averages:		8.6	7.0	1.8	0	0.92	0.97	5.4	b

NOTES:

- (a) Datum not included in average.
- (b) Averages weighted with respect to elapsed time.

Table A.3 Test Results for Sample CG-103--Continued

- (c) Bottom flask overflowed.
- (d) Ran out of N₂.
- (e) Linear encoder out of range.
- (f) Error in valving arrangement.
- (g) Negative flow rate out probably due to experimental error. Actual value is probably very small and positive.
- (h) Not included in summary table.
- (i) Bottom flask dropped; no measurement of flow rate out.

Table A.4 Test Results for Sample SGE-2-2

Date	Elapsed Time (min)	Axial Stress (MPa)	Confining Stress (MPa)	Top Pressure (MPa)	Bottom Pressure (MPa)	Flow Rate In ($\times 10^{-3}$ cc/min)	Flow Rate Out ($\times 10^{-3}$ cc/min)	Notes	V _A (cc)	V _I (cc)	V _O (gm)
5/19-5/20	1432	21.3	19.5	9.5	6.5	0.03	0	a	NR	0.04	0
5/20-5/21	1409	22.6	19.9	9.6	9.4	0.04	0	a	0.28	0.05	0
5/21-5/22	1607	22.6	19.5	9.7	9.4	0.03	0	a	0.41	0.05	0
5/22-5/25	4504	22.5	18.9	9.7	8.7	0.03	0	a	0.16	0.15	0
5/26-5/27	Lowered bottom pressure to atmospheric. Let sample equilibrate overnight.										
5/27-5/28	1527	22.5	19.0	10.0	0	0.01	0.97	a	NR	0.01	1.48
5/28-6/1	5804	22.4	16.9	10.2	0	0.01	0.29	a	NR	0.11	1.66
6/1-6/3	No data. Flow continued.										
6/3-6/5	2515	22.3	19.2	10.4	0	0.01	0.13	a	0	0.02	0.34
6/6-6/11	7039	21.2	18.9	10.4	0	0.01	0.11		0	0.09	0.77
6/11-6/13	3063	22.2	17.4	10.4	0	0.01	0.11		0	0.02	0.33
6/13-6/14	1240	22.2	15.8	10.4	0	0.01	0.05		0	0.01	0.06
6/14-6/15	1452	23.1	19.6	10.4	0	0.01	0.11		0.26	0.01	0.16
6/15-6/16	1618	23.1	19.6	10.3	0	0.00	0.09		0.30	0.01	0.14
6/16-6/17	1439	23.1	19.6	10.4	0	0.01	0.09		0.20	0.01	0.13
6/17-6/18	1258	23.1	19.6	10.3	0	0.01	0.02		0.15	0.01	0.03
6/18-6/19	1404	23.1	19.6	10.4	0	0.01	0.03		0.09	0.01	0.04
6/19-6/21	3196	23.1	19.5	10.3	0	0.00	0.08		0	0.01	0.26
6/21-6/22	1469	23.1	19.3	10.3	0	0.01	0.05		0	0.01	0.07
6/22-6/23	1285	23.1	19.6	10.4	0	0.02	0.04		0	0.02	0.05
6/23-6/24	1599	23.1	19.4	10.4	0	0.00	0.08		0.44	0.00	0.12
6/24-6/25	1279	23.1	19.4	10.3	0	0.01	0.02		NR	0.01	0.03
6/25-6/30	7148	23.1	19.2	10.3	0	0.01	0.05		1.09	0.10	0.34
6/30-7/1	1456	23.0	19.5	10.3	0	0.00	0.02		0.28	0.00	0.03
7/1-7/3	2601	23.1	19.5	10.3	0	0.00	0.03		0.36	0.01	0.07
7/3-7/5	2737	23.0	19.5	10.3	0	0.00	0.04		0.39	0.01	0.10
Weighted Averages:		22.7	19.1	10.3	0	0.01	0.07	b			
Totals:									4.41	0.77	6.21

Table A.4 Test Results for Sample SGE-2-2--Continued

Date	Elapsed Time (min)	Axial Stress (MPa)	Confining Stress (MPa)	Top Pressure (MPa)	Bottom Pressure (MPa)	Flow Rate In ($\times 10^{-3}$ cc/min)	Flow Rate Out ($\times 10^{-3}$ cc/min)	Notes	V _A (cc)	V _I (cc)	V _O (gm)
Cement System 1 Plug Poured 4:45 pm, July 7, 1982											
7/19-7/20	1385	23.2	19.6	9.9	0	0.58	0.32		0.26	0.81	0.45
7/20-7/21	1487	23.2	19.7	9.9	0	0.57	0.68		0.22	0.85	1.01
7/21-7/22	1468	23.2	19.7	9.9	0	0.48	0.68		0.00	0.71	1.00
7/22-7/23	828	23.2	19.6	9.9	0	0.36	0.68		0.20	0.30	0.56
7/23-7/24	Gauge calibration. Flow stopped.										
7/24-7/26	3414	23.4	19.6	9.9	0	0.83	0.58		0.32	2.85	1.99
7/26-7/27	1088	23.4	19.7	9.9	0	0.89	0.41		0.00	0.97	0.45
7/27-7/28	1119	23.4	19.6	9.9	0	0.84	0.51		0.18	0.94	0.57
7/28-7/30	No data. Flow continued.										
7/30-7/31	865	23.4	19.8	10.0	0	1.47	0.53		0.54	1.27	0.46
7/31-8/3	4270	23.4	19.6	9.9	0	0.21	0.42		0.34	0.90	1.80
8/3-8/5	3072	23.4	19.8	10.0	0	0.06	0.33		0.35	0.19	1.02
8/5-8/7	2711	23.4	19.7	10.0	0	0.06	0.35		0.16	0.16	0.94
8/7-8/10	4585	23.4	19.5	10.1	0	0.04	0.36		0.43	0.20	1.65
8/10-8/13	4377	23.4	19.6	10.2	0	0.05	0.29		0.27	0.24	1.27
8/13-8/17	5505	23.4	19.5	10.5	0	0.04	0.26		0.69	0.24	1.43
8/17-8/22	7410	23.4	19.7	10.3	0	0.03	0.24		0.41	0.25	1.79
8/22-9/1	14,072	23.4	19.6	10.4	0	0.02	0.18		0.91	0.35	2.59
9/7-9/14	9,970	23.4	19.8	9.9	0	0.03	0.18		0.22	0.27	1.76
Weighted Averages:		23.4	19.6	10.1	0	0.15	0.29	b			
Last 10 readings:		23.4	19.6	10.2	0	0.05	0.24	Totals:	4.78	3.05	15.83
9/14-9/18	5840	14.5	13.7	10.1	0	0.03	0.17		0.17	0.17	0.99
9/18-9/23	7195	14.6	13.6	10.1	0	0.02	0.14		0.77	0.14	1.01
9/23-9/27	5830	14.6	14.1	10.1	0	0.02	0.20		0.00	0.14	1.19
9/27-9/28	1481	15.1	13.8	10.0	0	0.66	0.00	c	0.08	0.98	0.00
9/28-9/30	2497	15.1	13.8	9.9	0	0.18	0.26		0.19	0.44	0.65
9/30-10/4	6070	15.1	13.8	9.8	0	0.08	0.17		0.08	0.48	1.04

Table A.4 Test Results for Sample SGE-2-2--Continued

Date	Elapsed Time (min)	Axial Stress (MPa)	Confining Stress (MPa)	Top Pressure (MPa)	Bottom Pressure (MPa)	Flow Rate In ($\times 10^{-3}$ cc/min)	Flow Rate Out ($\times 10^{-3}$ cc/min)	Notes	V _A (cc)	V _I (cc)	V _O (gm)
10/4-10/6	2662	15.1	13.8	9.9	0	0.08	0.01		0.21	0.21	0.02
10/6-10/9	4337	15.1	13.9	9.9	0	0.04	0.24		0.00	0.19	1.02
10/9-10/14	7117	15.1	13.8	9.9	0	0.05	0.15		0.18	0.37	1.04
10/14-10/23	13380	15.1	13.7	9.9	0	0.02	0.15		0.42	0.22	1.99
10/23-10/25	2490	15.1	13.9	10.0	0	0.00	0.00		0.00	0.00	0.00
Weighted Averages:		14.9	13.8	9.9	0	0.06	0.15	b			
								Totals:	2.10	3.34	8.95
10/25-10/27	3106	8.0	7.0	7.0	0	0.05	0.18		0.08	0.15	0.56
10/27-10/28	1153	8.0	7.0	7.0	0	0.14	0.00		0.10	0.16	0.00
10/28-11/06	13107	7.4	6.9	6.9	0	0.02	0.12		0.23	0.20	1.60
Weighted Averages:		7.5	6.9	6.9	0	0.03	0.12	b			
								Totals:	0.41	0.51	2.16
11/7-11/10	Sample dried in lab										
11/10-12/21	Sample dried in oven @130°F										
12/21-12/27	Sample dried in lab										
12/27-1/12	Sample saturated in permeameter										
Cement System 1 Plug, After Drying											
1/12	108	8.7	7.2	1.6	0	917.04	925.19		0.00	99.04	99.92
1/12	137	8.7	7.1	1.6	0	760.44	772.34		0.00	104.18	105.81
1/13	83	8.8	7.3	1.9	0	736.27	744.10		0.00	61.11	61.76
1/13	119	8.8	7.3	2.0	0	766.47	769.24		0.00	91.21	91.54
1/15	179	8.8	7.2	2.1	0	532.91	531.90		0.00	95.39	95.21
1/15	142	8.8	7.3	1.9	0	484.23	484.23		0.00	68.76	68.76
1/16	134	8.8	7.2	2.0	0	375.75	376.12		0.00	50.35	50.40
1/17	305	8.9	7.6	2.1	0	258.13	262.16		0.00	78.73	79.96
1/18	284	8.9	7.6	2.0	0	239.47	242.25		0.00	68.01	68.80

Table A.4 Test Results for Sample SGE-2-2--Continued

Date	Elapsed Time (min)	Axial Stress (MPa)	Confining Stress (MPa)	Top Pressure (MPa)	Bottom Pressure (MPa)	Flow Rate In ($\times 10^{-3}$ cc/min)	Flow Rate Out ($\times 10^{-3}$ cc/min)	Notes	V _A (cc)	V _I (cc)	V _O (gm)
1/27	279	8.8	6.9	2.0	0	109.89	109.68		0.00	30.66	30.60
1/27-1/28	1027	8.8	6.8	2.0	0	96.19	96.17		0.15	98.79	98.77
1/28	400	8.8	6.9	2.1	0	102.63	101.73		0.00	41.05	40.69
1/28-1/29	957	8.8	6.9	2.0	0	85.84	85.63		0.16	82.15	81.95
1/29	714	8.8	6.9	2.0	0	85.24	85.39		0.00	60.86	60.97
1/29-1/30	815	8.8	6.9	2.0	0	75.60	75.80		0.24	61.61	61.78
1/30-1/31	1366	8.8	6.9	2.0	0	71.46	71.41		0.14	97.61	97.55
1/31	404	8.9	6.9	2.1	0	68.19	67.67		0.00	27.55	27.34
1/31-2/1	1423	8.9	6.9	2.0	0	55.74	55.61		0.00	79.32	79.14
2/1-2/2	1577	8.8	6.8	2.1	0	53.54	53.25		0.00	84.43	83.97
2/2-2/4	2461	8.8	6.7	1.9	0	34.91	32.02		0.75	85.92	78.79
2/4-2/5	1658	8.8	7.0	2.0	0	30.07	26.79		0.00	49.85	44.41
2/5-2/6	No data. Computer crashed. Flow continued.										
2/6-2/7	1131	8.8	6.9	1.9	0	22.76	20.13		0.00	25.74	22.77
2/7-2/9	2987	8.8	6.9	2.0	0	20.37	17.50		0.41	60.84	52.26
2/9-2/10	1500	8.8	7.0	1.4	0	NR	17.61		0.18	NR	26.41
2/10-2/11	1154	8.8	7.0	2.1	0	17.47	15.13		0.14	20.16	17.46
2/11-2/14	4461	8.9	7.1	2.1	0	17.05	13.82		0.00	76.07	61.65
2/14-2/16	2446	8.8	6.8	2.1	0	16.11	12.81		1.44	39.41	31.33
2/16-2/18	3379	8.9	7.5	2.1	0	14.91	14.86		0.00	50.39	50.21
2/18-2/21	3786	8.9	7.2	2.0	0	14.77	14.76		0.00	55.93	55.90
2/21-2/23	2762	8.8	6.9	2.1	0	15.29	15.22		1.26	42.23	42.03
2/23-2/24	1605	8.8	7.0	2.0	0	15.35	15.16		0.15	24.63	24.33
2/24-2/25	Computer crashed. No data. Flow continued.										
2/25-2/28	4225	8.8	7.0	2.0	0	15.23	15.16		0.41	64.33	64.03
2/28-3/2	2842	8.8	7.0	2.1	0	15.39	15.53		0.35	43.73	44.13
3/2-3/2	142	8.9	7.1	6.9	0	51.76	51.62		0.00	7.35	7.33
3/2-3/3	902	8.9	7.1	7.0	0	52.82	56.90		0.00	47.64	51.32
3/3-3/4	481	8.9	7.0	6.9	0	53.22	53.89		0.00	25.60	25.92
3/4-3/5	805	9.0	6.9	7.0	0	62.02	61.94		0.00	49.93	49.86
3/5-3/6	1825	9.0	6.9	7.0	0	54.03	55.16		0.40	98.60	100.67
3/6-3/7	1677	9.0	7.0	7.2	0	59.45	58.98		0.22	99.70	98.91

Table A.4 Test Results for Sample SGE-2-2--Continued

Date	Elapsed Time (min)	Axial Stress (MPa)	Confining Stress (MPa)	Top Pressure (MPa)	Bottom Pressure (MPa)	Flow Rate In ($\times 10^{-3}$ cc/min)	Flow Rate Out ($\times 10^{-3}$ cc/min)	Notes	V_A (cc)	V_I (cc)	V_O (gm)
3/7-3/8	1289	9.1	7.0	6.9	0	62.26	61.96		0.17	80.25	79.86
3/9-3/9	1112	14.7	13.0	9.9	0	82.58	84.20	a	2.41	91.83	93.63
3/9-3/10	365	14.5	11.0	9.8	0	92.27	93.15	a	0.00	33.68	34.00
3/10-3/11	1022	14.5	11.0	10.2	0	97.08	100.55		0.00	99.22	102.76
Weighted Averages:		14.5	11.0	10.1	0	94.87	96.34	b			
								Totals:	5.69	346.33	352.58
3/11-3/12	1026	23.0	19.1	9.9	0	86.36	85.91		0.82	88.61	88.14
3/12	307	23.4	19.8	10.0	0	85.90	87.04		0.00	26.37	26.72
3/15	490	23.4	19.8	9.9	0	78.94	79.04		0.00	38.68	39.73
3/15-3/16	936	23.2	19.7	10.1	0	79.72	78.62		0.37	74.62	73.59
3/16	440	23.0	19.8	10.0	0	79.36	79.09		0.00	34.92	34.80
Weighted Averages:		23.2	19.5	10.0	0	82.27	81.90				
								Totals:	1.19	263.20	261.98

NOTES:

- (a) Datum not included in average. Flow amounts included in totals (last three columns).
 (b) Averages weighted with respect to time. Totals for last three columns.
 (c) At beginning of this run the top seal was broken by raising the annulus pressure too high.

Axial stress readings taken prior to 9/14 may be about 3% too high.

V_A is volume of water added to annulus.

V_I is volume of water pumped into top hole.

V_O is volume of water flowing from bottom hole.

Table A.5 Test Results for Sample SGE-2-3

Date	Elapsed Time (min)	Axial Stress (MPa)	Confining Stress (MPa)	Top Pressure (MPa)	Bottom Pressure (MPa)	Flow Rate In ($\times 10^{-3}$ cc/min)	Flow Rate Out ($\times 10^{-3}$ cc/min)	Notes	V _A (cc)	V _I (cc)	V _O (gm)
6/13-6/14	1253	12.3	10.3	9.7	0	0.02	0.53	a	0	0.02	0.67
6/14-6/15	1498	12.3	10.2	9.7	0	0.01	0.156	a	0.08	0.02	0.22
6/15-6/16	1568	12.3	10.2	9.8	0	0.00	0.08		0	0.00	0.12
6/16-6/17	1470	12.3	10.1	9.7	0	0.01	0.03		0.14	0.02	0.04
6/17-6/18	1275	12.3	10.2	9.7	0	0.01	0.00		0	0.02	0.00
6/18-6/19	1351	12.3	10.2	9.7	0	0.00	0.00		0	0.00	0.00
6/19-6/21	3238	12.2	10.1	9.8	0	0.02	0.01		0.16	0.06	0.03
6/21-6/22	1396	12.3	10.2	9.8	0	0.01	0.00		0	0.01	0.00
6/22-6/23	1325	12.3	10.1	9.8	0	0.02	0.01		0	0.02	0.01
6/23-6/24	1600	12.3	10.2	9.8	0	0.02	0.02		0	0.03	0.03
Weighted Averages:		12.3	10.2	9.8	0	0.01	0.02	b			
								Totals:	0.38	0.20	1.12
6/24-6/25	1254	12.2	10.1	6.9	0	0.05	0.00		0.10	0.06	0.00
6/25-6/30	7220	12.2	9.9	7.0	0	0.00	0.00		0.60	0.00	0.00
6/30-7/1	1413	12.1	9.9	6.9	0	0.00	0.00		0	0.00	0.00
Weighted Averages:		12.2	9.9	7.0	0	0.01	0.00	b			
								Totals:	0.70	0.06	0.00
Cement System 1 poured at 4:45 pm, July 7, 1982											
7/19-7/20	1397	23.2	19.6	9.9	0	1.49	1.68		0.94	2.08	2.34
7/20-7/21	1461	23.3	19.6	9.8	0	1.24	1.83		0.49	1.81	2.68
7/21-7/22	1506	23.3	19.6	9.7	0	1.40	2.17		0.29	2.11	3.27
7/22-7/23	807	23.3	19.6	10.0	0	1.28	2.30		0.00	1.03	1.86
7/23-7/24	Top gauge disconnected for calibration.										
7/24-7/26	3402	23.2	19.6	9.8	0	1.10	2.01		0.24	3.73	6.85
7/26-7/27	1104	23.3	19.7	9.7	0	0.89	1.82		0.00	0.98	2.01

Table A.5 Test Results for Sample SGE-2-3--Continued

Date	Elapsed Time (min)	Axial Stress (MPa)	Confining Stress (MPa)	Top Pressure (MPa)	Bottom Pressure (MPa)	Flow Rate In ($\times 10^{-3}$ cc/min)	Flow Rate Out ($\times 10^{-3}$ cc/min)	Notes	V _A (cc)	V _I (cc)	V _O (gm)
7/27-7/28	1088	23.3	19.7	10.0	0	0.95	1.65		0.18	1.03	1.80
7/28-7/30	Computer down.		No data.	Flow continued.							
7/30-7/31	819	23.2	19.8	9.9	0	1.06	0.65		0.40	0.87	0.53
7/31-8/2	2885	23.2	19.7	8.9	0	0.50	0.85	a,d	0.27	1.45	2.46
8/2-8/5	4373	23.2	19.6	10.0	0	0.55	0.88		0.33	2.39	3.84
8/5-8/7	2752	23.2	19.7	9.8	0	0.52	0.91		0.15	1.43	2.51
8/7-8/10	4628	23.3	19.6	9.9	0	0.48	0.81		0.09	2.20	3.75
8/10-8/13	4377	23.3	19.6	10.4	0	0.46	0.61		0.47	2.00	2.67
8/13-8/17	5579	23.2	19.7	10.4	0	0.42	0.54		0.55	2.35	3.01
8/17-8/22	7361	23.2	19.7	9.8	0	0.34	0.48		0.23	2.52	3.55
8/22-9/1	14,050	23.2	19.5	9.8	0	0.32	0.36		0.98	4.46	5.10
9/1-9/3	2879	22.7	19.7	10.0	0	0.26	0.34		0.75	0.75	0.97
9/3-9/7	5984	22.6	19.3	10.1	0	0.02	0.37		1.80	0.10	2.24
9/7-9/9	3107	23.0	19.9	10.1	0	<0.22	0.09	a,e	0.00	<0.69	0.29
9/9-9/14	6798	23.2	19.7	10.0	0	0.33	0.31		0.32	2.27	2.14
9/14-9/18	5940	23.2	19.5	10.1	0	0.29	0.32		0.00	1.71	1.90
9/18-9/20	3075	23.2	19.4	10.0	0	0.28	0.34		0.00	0.87	1.04
9/20-9/21	1636	23.2	19.3	9.3	0	0.12	0.15	a,d	0.45	0.20	0.25
9/21-9/23	2312	23.2	19.6	10.0	0	0.32	0.22		0.21	0.74	0.51
9/23-9/27	5895	23.2	19.7	9.9	0	0.24	0.32		0.36	1.43	1.89
9/27-9/28	1445	23.2	19.7	9.8	0	0.22	0.16		0.00	0.32	0.23
Weighted Averages:		23.2	19.6	10.0	0	0.44	0.64	b			
								Totals:	9.50	41.52	59.69
Last 10 Readings:		23.1	19.6	9.9	0	0.27	0.35				
" " " :									5.10	16.06	20.11
9/28-9/30	2551	14.4	10.4	10.1	0	0.31	0.31		0.14	0.80	0.78
9/30-10/4	5982	14.5	10.4	10.1	0	0.30	0.29		0.00	1.77	1.73
Weighted Averages:		14.5	10.4	10.1	0	0.30	0.30	b			
								Totals:	0.14	2.57	2.51

Table A.5 Test Results for Sample SGE-2-3--Continued

Date	Elapsed Time (min)	Axial Stress (MPa)	Confining Stress (MPa)	Top Pressure (MPa)	Bottom Pressure (MPa)	Flow Rate In ($\times 10^{-3}$ cc/min)	Flow Rate Out ($\times 10^{-3}$ cc/min)	Notes	V _A (cc)	V _I (cc)	V _O (gm)
10/4-10/6	2612	7.8	6.7	6.7	0	0.03	0.12	a,f	NR	0.07	0.32
10/6-10/9	4384	9.7	5.2	3.5	0	0.08	0.13		0.0	0.35	0.59
10/9-10/14	7130	9.6	5.2	3.4	0	0.11	0.10		0.00	0.77	0.73
Weighted Averages:		9.6	5.2	3.4	0	0.10	0.11	b			
								Totals:	0.00	1.12	1.32

NOTES:

- (a) Datum not included in average. Flow amounts included in totals (last three columns).
- (b) Averages weighted with respect to time. Totals for last three columns.
- (c) Bottom valve closed for several days prior to test. Excess water out probably due to drainage when bottom valve opened and bottom pressure fell to zero.
- (d) Ran out of N₂ driving injection pump.
- (e) Changed N₂ tank before this test. Forgot to open top valve. Q_{IN} represents water injected when top valve opened.
- (f) Annulus in communication with top hole through top seal. Believe bottom seal holding.
- (NR) Not recorded.
- (*) See text for discussion.

Axial stress readings taken prior to 9/14 may be about 3% too high.

V_A is volume of water added to annulus.

V_I is volume of water pumped into top hole.

V_O is volume of water flowing from bottom hole.

Table A.6 Test Results for Sample NTS-TPTS-101

Date	Elapsed Time (min)	Axial Stress (MPa)	Confining Stress (MPa)	Top Pressure (MPa)	Bottom Pressure (MPa)	Flow Rate In ($\times 10^{-3}$ cc/min)	Flow Rate Out ($\times 10^{-3}$ cc/min)	Notes	V _A (cc)	V _I (cc)	V _O (gm)
Rock Bridge											
12/18	272	10.5	7.6	1.8	0	99.26	49.72	a,c	0.00	26.97	13.51
12/18	194	10.5	7.1	1.8	0	58.71	56.75	a,c	0.00	11.39	11.01
12/18-12/19	696	10.5	6.5	1.9	0	62.60	61.75	a,c	1.49	43.57	42.98
12/19-12/21	No testing. Flow stopped.										
12/21-12/22	934	8.5	7.0	1.8	0	52.59	51.35	a	1.79	49.13	47.97
12/22	511	8.5	6.9	1.7	0	37.92	43.40	a	1.21	19.38	22.18
12/22-12/23	1368	8.5	6.5	1.9	0	48.32	49.52		3.23	66.10	67.74
12/23-12/24	No data. Flow continued										
12/24-12/25	1393	8.5	6.5	1.8	0	38.87	41.34		3.34	54.15	57.59
12/25-12/27	2528	8.4	6.0	1.8	0	35.26	37.17	a	4.98	89.14	93.97
12/27-12/28	1494	8.5	6.6	1.8	0	34.20	36.17		3.29	51.10	54.04
12/28-12/29	1286	8.5	6.7	1.9	0	34.99	37.40		2.99	45.00	48.09
12/29-12/30	1458	8.5	6.6	1.8	0	29.79	33.25		3.30	43.44	48.48
Weighted Averages		8.5	6.6	1.8	0	37.12	39.43				
Totals:									24.13	417.44	440.06
1/11-1/12	1101	8.6	6.3	3.4	0	79.86	88.36	a	2.86	87.93	97.28
1/12-1/13	1391	8.6	6.7	3.5	0	75.70	79.25		2.92	105.30	110.24
1/13-1/14	1394	8.5	6.6	3.5	0	72.65	80.37		3.76	101.28	112.03
1/14-1/15	1084	8.6	6.9	3.5	0	69.08	67.88		2.26	74.88	73.58
Weighted Averages		8.6	6.7	3.5	0	72.75	76.47	b			
Totals:									11.80	369.39	393.13
1/15	422	8.9	7.5	6.0	0	151.68	152.82		0.37	64.01	64.49
1/16	280	8.9	7.6	6.0	0	152.29	159.46		0.00	42.64	44.65
1/16-1/17	301	9.0	7.4	6.1	0	151.33	NR	d	0.00	45.11	NR
1/18	338	8.8	6.3	6.1	0	190.89	147.69		1.80	64.52	49.92

Table A.6 Test Results for Sample NTS-TPTS-101--Continued

Date	Elapsed Time (min)	Axial Stress (MPa)	Confining Stress (MPa)	Top Pressure (MPa)	Bottom Pressure (MPa)	Flow Rate In ($\times 10^{-3}$ cc/min)	Flow Rate Out ($\times 10^{-3}$ cc/min)	Notes	V _A (cc)	V _I (cc)	V _O (gm)
1/18	247	8.7	6.4	6.2	0	180.16	150.40		1.55	44.50	37.15
1/18-1/19	665	8.4	5.2	6.0	0	168.41	168.00		5.80	111.99	111.72
Weighted Averages		8.7	6.5	6.1	0	165.65	157.75	b			
								Totals:	9.52	372.77	307.93
1/27	66	9.0	6.9	7.0	0	186.67	219.55		0.00	12.32	14.49
Weighted Averages		9.0	6.9	7.0	0	186.67	219.55				
								Totals:	0.00	12.32	14.49
1/29	405	8.8	6.9	6.0	0	137.56	127.90	a	0.00	55.71	51.80
1/29	267	8.8	7.1	5.9	0	126.59	128.76		0.45	33.80	34.38
1/29-1/30	804	8.9	7.0	6.0	0	129.03	129.95		0.92	103.74	104.48
1/30	347	8.9	7.1	6.0	0	121.79	116.43		0.00	42.26	40.40
Weighted Averages		8.9	7.0	6.0	0	126.80	126.42	b			
								Totals:	1.37	235.51	231.06
1/30-1/31	1282	15.3	8.9	3.4	0	52.09	52.69	a	0.00	66.78	67.55
1/31-2/1	1567	14.6	5.7	3.5	0	55.41	51.39	a	0.00	86.83	80.53
2/1-2/2	1565	14.3	4.2	3.5	0	57.52	53.29	a	0.00	90.02	83.40
2/2-2/3	908	14.1	3.7	3.5	0	55.97	49.56	a	NR	50.82	45.00
2/3-2/4	939	15.4	11.2	3.5	0	46.74	NR	a	NR	43.89	NR
2/4	237	15.5	13.1	3.5	0	46.33	56.24		3.37	10.98	13.33
2/4	231	15.5	13.6	3.5	0	42.47	41.21		2.68	9.81	9.52
2/4-2/5	733	15.4	12.2	3.5	0	43.70	48.88		6.68	32.03	35.83
2/5	462	15.6	14.0	3.5	0	41.82	50.61		4.13	19.32	23.38
2/5-2/6	No data. Computer crashed. Flow continued.										
2/6-2/7	1114	15.3	11.8	3.5	0	43.92	47.33		8.29	48.93	52.73
Weighted Averages:		15.5	13.0	3.5	0	43.38	49.34	b			
								Totals:	25.15	459.41	411.27

Table A.6 Test Results for Sample NTS-TPTS-101--Continued

Date	Elapsed Time (min)	Axial Stress (MPa)	Confining Stress (MPa)	Top Pressure (MPa)	Bottom Pressure (MPa)	Flow Rate In ($\times 10^{-3}$ cc/min)	Flow Rate Out ($\times 10^{-3}$ cc/min)	Notes	V _A (cc)	V _I (cc)	V _O (gm)
2/7	424	15.7	13.7	7.0	0	100.12	99.65		2.29	42.25	42.25
2/7-2/8	897	15.7	12.6	7.0	0	101.94	101.94		5.50	91.44	91.44
2/8-2/9	966	15.7	12.1	7.0	0	102.47	104.05		7.09	98.99	100.51
Weighted Averages:		15.7	12.6	7.0	0	101.83	102.41	b			
								Totals:	14.88	232.88	234.20
2/9	269	15.9	13.7	10.0	0	166.77	161.56		1.83	44.86	43.76
2/9	166	16.1	13.9	10.0	0	171.69	179.04		NR	28.50	29.72
2/10	323	15.8	13.4	10.0	0	173.99	244.80	a,e	3.76	56.20	79.07
2/10-2/11	919	15.3	12.8	3.5	0	46.61	53.88	a,e	4.43	42.83	49.52
2/11	305	15.8	14.0	10.0	0	167.31	164.33		1.38	51.03	50.12
2/11	326	15.8	13.9	10.0	0	165.00	165.37		1.70	53.79	53.91
Weighted Averages		15.9	13.9	10.0	0	167.15	166.24	b			
								Totals:	13.30	277.21	306.10
2/11-2/14	No testing										
2/14-2/15	844	23.3	17.7	3.5	0	34.82	53.40	a	6.78	29.39	45.07
2/15	274	23.4	19.6	3.5	0	30.07	48.91		3.04	8.24	13.40
2/15	191	23.3	19.2	3.5	0	33.98	48.90		2.30	6.49	9.34
2/15-2/16	1114	23.0	17.2	3.5	0	37.31	48.72	a	18.30	41.56	54.27
2/16	382	23.3	19.4	3.5	0	36.31	47.91		4.05	13.87	18.30
2/16-2/17	990	23.1	17.6	3.6	0	37.81	46.85	a	6.79	37.43	46.38
2/17	486	23.3	19.7	3.5	0	34.36	45.06		4.02	16.70	21.90
Weighted Averages:		23.3	19.5	3.5	0	33.98	47.22	b			
								Totals:	45.28	153.68	208.66
2/18	320	23.3	19.5	7.0	0	86.59	89.47		12.36	27.71	28.63
2/18-2/19	821	23.3	18.8	7.0	0	87.73	93.06	a	5.14	72.03	76.40
2/19	408	23.4	19.6	7.0	0	82.65	88.58		2.75	33.72	36.14
Weighted Averages:		23.4	19.6	7.0	0	84.38	88.97	b			
								Totals:	20.25	133.46	141.17

Table A.6 Test Results for Sample NTS-TPTS-101--Continued

Date	Elapsed Time (min)	Axial Stress (MPa)	Confining Stress (MPa)	Top Pressure (MPa)	Bottom Pressure (MPa)	Flow Rate In ($\times 10^{-3}$ cc/min)	Flow Rate Out ($\times 10^{-3}$ cc/min)	Notes	V _A (cc)	V _I (cc)	V _O (gm)
2/21	444	23.5	18.9	10.1	0	134.74	158.63	a	4.02	60.27	70.43
2/21-2/22	702	23.5	18.9	10.0	0	134.93	146.21	a	4.22	94.72	102.64
2/22	257	23.5	19.8	9.9	0	133.77	136.77		1.56	34.38	35.15
2/22	242	23.5	19.6	10.0	0	135.21	141.74		2.21	32.72	34.30
2/23	180	23.4	19.3	10.0	0	139.61	135.17		3.53	25.13	24.33
2/24	315	23.4	19.7	10.1	0	133.84	139.71		1.91	42.16	44.01
Weighted Averages:		23.5	19.6	10.0	0	135.20	138.62				
Totals:									17.45	289.38	310.86
3/8	10	18.9	7.0	7.0	0	6178.00	6218.00		0.90	61.78	62.18
3/8	13.72	18.9	7.0	7.0	0	5000.00	5084.55		1.00	68.60	69.76
3/8	42.13	19.0	7.0	7.0	0	2026.58	2073.82		1.14	85.38	87.37
3/8	37.19	19.1	7.6	7.0	0	1684.05	1898.09		NR	62.63	70.59
3/18	92.26	19.1	7.6	7.0	0	564.71	695.10		11.04	52.10	64.13
3/22	97.03	19.1	7.6	7.0	0	367.82	543.44		15.90	35.69	52.73
3/23	99.07	19.2	7.6	7.1	0	363.68	504.49		13.18	36.03	49.98
3/24	136	19.1	7.6	7.0	0	373.38	487.13		15.24	50.78	66.25
3/28	159	19.1	7.6	7.1	0	251.51	369.18		17.39	39.99	58.70
3/30	78	19.1	7.6	7.1	0	145.38	290.26		10.61	11.34	22.64
4/1	138	19.1	7.6	7.1	0	126.81	236.74		13.53	17.50	32.67
4/8	155	19.1	7.6	7.0	0	87.29	239.42		24.56	13.53	37.11
TOTALS:									124.49	535.35	674.11

NOTES:

- a) Not included in weighted average.
- b) Averages weighted with respect to time.
- c) Rock still saturating.
- d) Pump ran out of water; Flow Rate In from data logger.
- e) Poor mass balance.

NR) not recorded

Table A.7 Test Results for Sample CCR-P-100

Date	Elapsed Time (min)	Axial Stress (MPa)	Confining Stress (MPa)	Top Pressure (MPa)	Bottom Pressure (MPa)	Flow Rate In ($\times 10^{-3}$ cc/min)	Flow Rate Out ($\times 10^{-3}$ cc/min)	Notes	V _A (cc)	V _I (cc)	V _O (gm)
Cement 1 Plug, Before Drying											
8/3-8/3	423	7.9	2.0	2.0	0	10.35	9.60		0.00	4.38	4.06
8/3-8/4	1070	7.8	2.0	2.0	0	8.67	8.23		0.26	9.28	8.81
8/4-8/4	346	7.8	2.1	2.0	0	2.86	5.61		0.00	0.99	1.94
8/4-8/5	1076	7.8	2.1	2.1	0	9.40	7.27		0.00	10.11	7.82
8/5-8/5	265	7.8	2.1	1.9	0	8.34	8.38		0.00	2.21	2.22
8/5-8/6	1219	7.8	2.1	1.9	0	7.91	NR	a	0.00	9.64	NR
8/6-8/7	1313	7.7	2.0	2.1	0	8.40	7.82		0.00	11.03	10.27
8/7-8/9	2704	7.7	2.0	1.9	0	7.27	7.17		0.00	19.60	19.33
8/9-8/10	1466	7.7	2.0	2.2	0	NR	3.10	a	0.00	NR	11.88
8/10-8/11	1362	7.8	2.0	2.2	0	10.79	8.58		0.00	14.69	11.68
8/11-8/12	1476	7.7	2.0	2.1	0	10.36	8.45		0.11	15.29	12.47
Weighted Averages:		7.7	2.0	2.0	0	8.73	7.84	b			
								Totals:	0.37	97.22	90.48
Cement 1 Plug, After Drying											
9/10-9/11	1386	7.5	2.2	1.9	0	11.93	10.49		0.00	16.54	14.54
9/11-9/12	1157	7.5	2.2	1.8	0	10.82	11.31		0.00	12.52	13.08
9/12-9/13	1318	7.5	2.1	1.8	0	10.86	11.39		0.00	14.31	15.01
9/13	387	7.5	2.1	1.8	0	10.72	12.79		0.00	4.15	4.95
9/13-9/14	1087	7.5	2.1	1.7	0	10.71	10.95		0.00	11.64	11.90
9/14-9/15	1365	7.4	2.1	1.7	0	10.53	11.00		0.00	14.37	15.01
9/15-9/15	250	7.4	2.1	1.7	0	10.44	NR	a	0.00	2.61	NR
9/15-9/16	1082	7.4	2.1	2.1	0	NR	13.61	a	0.00	NR	14.73
9/16-9/16	476	7.4	2.1	2.1	0	NR	13.68	a	0.00	NR	6.51
9/16-9/17	1040	7.4	2.0	1.9	0	12.15	12.55		0.00	12.64	13.05
9/17-9/18	1572	7.4	2.0	2.0	0	14.04	14.08		0.38	22.07	22.14

Table A.7 Test Results for Sample CCR-P-100--Continued

Date	Elapsed Time (min)	Axial Stress (MPa)	Confining Stress (MPa)	Top Pressure (MPa)	Bottom Pressure (MPa)	Flow Rate In ($\times 10^{-3}$ cc/min)	Flow Rate Out ($\times 10^{-3}$ cc/min)	Notes	V _A (cc)	V _I (cc)	V _O (gm)
9/18-9/19	1320	7.4	2.1	2.1	0	14.02	NR	a	0.00	18.50	NR
9/18-9/20	2818	7.4	2.1	2.1	0	NR	14.30	a	0.00	NR	40.30
9/20-9/21	1401	<u>7.4</u>	<u>2.1</u>	<u>2.1</u>	<u>0</u>	<u>13.80</u>	<u>14.13</u>		<u>0.00</u>	<u>19.34</u>	<u>19.80</u>
Weighted Averages:		7.5	2.1	1.9	0	11.91	12.09	b			
Totals:									0.38	148.69	191.02
Begin Dye Injection											
9/22-9/23	1161	7.0	1.9	1.9	0	2.23	1.98		0.90	2.59	2.30
9/23-9/28	7343	7.0	1.9	1.8	0	0.79	0.78		0.55	5.78	5.76
9/28-9/29	1370	7.0	2.1	2.2	0	0.58	NR		0.00	0.79	NR
9/29-9/30	932	7.0	2.0	2.2	0	0.69	NR		0.00	0.64	NR
9/30-10/4	5832	7.0	1.9	2.1	0	0.65	0.63		0.38	3.79	3.70

NOTES:

- (a) Datum not included in average.
- (b) Averages weighted with respect to elapsed time.

NR = Not recorded

V_A is volume of water added to annulus.
V_I is volume of water pumped into top hole.
V_O is volume of water flowing from bottom hole.

Table A.8 Test Results for Sample CCR-D-100

Date	Elapsed Time (min)	Axial Stress (MPa)	Confining Stress (MPa)	Top Pressure (MPa)	Bottom Pressure (MPa)	Flow Rate In ($\times 10^{-3}$ cc/min)	Flow Rate Out ($\times 10^{-3}$ cc/min)	Notes	V _A (cc)	V _I (cc)	V _O (gm)
Rock Bridge											
10/10-10/11	1526	8.1	6.4	1.6	?	15.32	3.78	a,c	1.34	23.38	5.77
10/11-10/12	1348	8.2	6.9	1.7	?	4.07	2.85	a,c	0.00	5.48	3.84
10/12-10/13	1515	8.3	6.8	1.7	?	2.97	2.34	a,c	0.23	4.50	3.55
10/13-10/14	1326	8.4	6.9	1.7	0	2.59	2.41	a,c	0.00	3.44	3.19
10/14-10/15	1383	8.3	6.8	1.7	0	18.52	NR	a	0.00	25.62	NR
10/15-10/16	1446	8.2	6.8	1.9	0	18.35	15.69		0.00	26.54	22.69
10/16-10/18	2760	8.2	6.5	1.6	0	15.52	12.03		0.77	42.84	33.20
10/18-10/19	989	8.3	6.8	1.5	0	14.62	10.21		0.23	14.46	10.10
10/19-10/20	1452	8.3	6.8	1.5	0	14.82	10.59		0.37	21.52	15.37
10/20-10/21	Computer down.										
10/21-10/22	1415	8.3	6.8	1.6	0	16.13	12.05		0.41	22.83	17.05
10/22-10/23	1247	8.3	6.8	1.7	0	16.22	12.53		0.24	20.23	15.62
10/23-10/25	Pump ran out of water.										
10/25-10/26	1536	<u>8.3</u>	<u>6.9</u>	<u>1.7</u>	<u>0</u>	<u>15.27</u>	<u>15.47</u>		<u>0.00</u>	<u>23.43</u>	<u>23.76</u>
Weighted Averages:		8.3	6.7	1.6	0	15.85	12.71	b			
								Totals:	3.59	234.27	154.14
10/26-10/27	1418	8.4	7.0	3.6	0	36.81	37.80		0.00	52.20	53.60
10/27-10/28	261	8.5	7.0	3.5	0	36.34	38.08		0.00	45.82	48.02
10/28-10/29	1310	<u>8.5</u>	<u>6.9</u>	<u>3.6</u>	<u>0</u>	<u>36.54</u>	<u>37.47</u>		<u>0.00</u>	<u>47.87</u>	<u>49.08</u>
Weighted Averages:		8.5	7.0	3.6	0	36.57	37.78	b			
								Totals:	0.00	145.89	150.70
10/29-11/2	Testing set-up (valving) incorrect.										
11/2-11/3	1407	8.8	7.1	7.0	0	77.92	78.19		0.00	109.63	110.02
11/3-11/4	Pump ran out of water.										
11/4	Computer down.										
11/4-11/5	929	8.8	7.1	7.1	0	79.85	72.80		0.00	74.18	67.63
11/5-11/8	No testing.										
11/8	725	<u>8.5</u>	<u>7.2</u>	<u>7.1</u>	<u>0</u>	<u>79.48</u>	<u>73.23</u>		<u>0.00</u>	<u>57.62</u>	<u>53.09</u>
Weighted Averages:		8.7	7.1	7.1	0	78.88	75.38	b			
								Totals:	0.00	241.43	230.74

Table A.8 Test Results for Sample CCR-D-100---Continued

Date	Elapsed Time (min)	Axial Stress (MPa)	Confining Stress (MPa)	Top Pressure (MPa)	Bottom Pressure (MPa)	Flow Rate In ($\times 10^{-3}$ cc/min)	Flow Rate Out ($\times 10^{-3}$ cc/min)	Notes	V _A (cc)	V _I (cc)	V _O (gm)
11/8-11/10	2629	14.9	13.6	3.5	0	25.86	26.16		0.00	67.98	68.77
11/10-11/12	No reading. Top valve left closed after refilling pump.										
11/12-11/22	System down.										
11/22-11/23	707	15.2	13.9	3.5	0	23.73	23.30		0.00	16.78	16.47
11/23-11/24	1782	15.2	13.8	3.5	0	24.17	23.73		0.20	43.07	42.28
11/24-11/25	1195	15.1	13.8	3.4	0	23.89	22.93		0.00	28.55	27.40
11/25-11/26	1426	15.1	13.7	3.5	0	24.51	23.27		0.37	34.95	33.89
Weighted Averages:		15.1	13.7	3.5	0	24.72	24.40	b			
								Totals:	0.57	191.33	188.81
11/26-11/27	1431	15.3	14.0	6.8	0	50.13	49.15		0.00	71.73	70.34
11/27-11/28	1397	15.3	13.9	7.1	0	52.08	52.22		0.00	72.76	72.95
11/28-11/29	1773	15.3	13.9	7.0	0	50.83	51.08		0.00	90.13	90.51
Weighted Averages:		15.3	13.9	7.0	0	50.99	50.83	b			
								Totals:	0.00	234.62	233.86
11/29-11/30	1214	15.5	13.9	10.0	0	76.85	77.29		0.00	93.30	93.83
11/30-12/1	1426	15.5	13.8	9.9	0	76.51	76.68		0.00	109.10	109.34
Weighted Averages:		15.5	13.8	9.9	0	76.67	76.96	b			
								Totals:	0.00	202.40	203.17
12/1-12/3	2667	22.6	19.8	3.5	0	18.09	18.06		0.00	48.25	48.16
12/3-12/4	1578	23.8	19.8	3.6	0	17.17	17.80		0.00	27.09	28.09
12/4-12/6	2746	23.2	19.7	3.5	0	17.72	17.72		0.00	48.67	48.66
12/6-12/7	1516	23.0	19.6	3.5	0	17.77	17.61		0.00	26.94	26.70
Weighted Averages:		23.1	19.7	3.5	0	17.74	17.82	b			
								Totals:	0.00	150.95	151.61
12/7-12/8	1267	23.0	19.6	7.0	0	35.65	36.54		0.00	45.17	46.30
12/8-12/10	2807	22.9	19.7	7.0	0	36.57	36.58		0.00	102.65	102.68
Weighted Averages:		22.9	19.7	7.0	0	36.28	36.57	b			
								Totals:	0.00	147.82	148.92

Table A.8 Test Results for Sample CCR-D-100---Continued

Date	Elapsed Time (min)	Axial Stress (MPa)	Confining Stress (MPa)	Top Pressure (MPa)	Bottom Pressure (MPa)	Flow Rate In ($\times 10^{-3}$ cc/min)	Flow Rate Out ($\times 10^{-3}$ cc/min)	Notes	V _A (cc)	V _I (cc)	V _O (gm)
12/10-12/13	Computer down.		No data.								
12/13-12/14	1532	23.1	19.7	10.0	0	53.20	52.98		0.00	81.51	81.16
12/14-12/15	1314	23.1	19.7	9.9	0	52.75	52.28		0.00	69.32	68.69
12/15-12/16	1593	23.1	19.6	10.0	0	53.35	53.24		0.00	84.98	84.81
Weighted Averages:		23.1	19.7	10.0	0	53.12	52.87	b			
								Totals:	0.00	235.81	234.66
Cement System 1 Plug Poured at 10:45 a.m., January 18, 1983											
2/3-2/4	1269	23.4	19.8	3.5	0	14.85	13.88	a	0.00	18.85	17.61
2/4-2/5	1654	23.4	19.6	3.4	0	14.85	14.73	a	0.00	24.56	24.36
2/5-2/6	No data. Computer crashed. Flow continued.										
2/6-2/7	1188	23.2	19.6	3.5	0	15.25	14.05	a	0.23	18.12	16.69
2/7-2/8	1273	23.2	19.7	3.5	0	15.29	14.35	a	0.23	19.47	18.27
2/8-2/9	1647	23.2	19.6	3.5	0	15.16	14.09	a	0.26	24.97	23.20
2/9-2/10	Stopped test to fix pump.										
2/10-2/11	1249	23.1	19.6	3.6	0	13.75	13.91		0.21	17.17	17.37
2/11-2/14	4469	23.1	19.7	3.5	0	13.46	13.70		0.00	60.16	61.22
Weighted Averages:		23.1	19.7	3.5	0	13.52	13.75	b			
								Totals:	0.93	183.30	178.72
2/14-2/16	2454	23.2	19.5	7.0	0	26.94	27.08		0.96	66.12	66.46
2/16-2/18	3346	23.1	20.3	7.0	0	26.59	26.07		0.00	88.96	87.22
2/18-2/21	3871	23.1	19.7	7.0	0	25.32	25.37		1.07	98.02	98.20
Weighted Averages:		23.1	19.9	7.0	0	26.17	26.05	b			
								Totals:	2.03	253.10	251.88
2/21-2/23	2762	23.2	19.8	9.9	0	36.00	37.11	a	0.00	99.42	102.49
2/23-2/24	1605	23.2	19.8	10.0	0	36.77	36.86		0.00	59.01	59.16
2/24-2/25	No data. Computer crashed. Flow continued.										

Table A.8 Test Results for Sample CCR-D-100--Continued

Date	Elapsed Time (min)	Axial Stress (MPa)	Confining Stress (MPa)	Top Pressure (MPa)	Bottom Pressure (MPa)	Flow Rate In ($\times 10^{-3}$ cc/min)	Flow Rate Out ($\times 10^{-3}$ cc/min)	Notes	V _A (cc)	V _I (cc)	V _O (gm)
2/25-2/26	1819	23.2	19.7	10.0	0	36.70	36.68		0.00	66.75	66.72
2/26-2/27	1175	23.2	19.6	10.0	0	36.53	36.62		0.32	42.92	43.03
Weighted Averages:		23.2	19.7	10.0	0	36.68	36.73	b			
								Totals:	0.32	268.10	271.40
2/27-2/28	1195	15.6	13.9	3.5	0	14.08	13.75	a	0.00	16.83	16.43
2/28-3/2	2842	15.3	13.8	3.5	0	14.05	14.03		0.30	39.94	39.86
3/2-3/3	1579	15.4	13.8	3.5	0	13.95	14.00		0.17	22.02	22.11
Weighted Averages:		15.3	13.8	3.5	0	14.01	14.02	b	0.47	78.79	78.40
3/3-3/5	2431	15.3	13.8	7.0	0	30.08	30.05		0.00	73.13	73.06
3/5-3/6	1825	15.3	13.8	7.0	0	30.80	29.83		0.00	56.21	54.44
3/6-3/8	2896	15.3	13.8	7.0	0	29.80	29.54		0.18	86.31	85.55
Weighted Averages:		15.3	13.8	7.0	0	30.15	29.79	b			
								TOTALS:	0.18	215.65	123.05
3/8-3/9	1112	15.7	13.9	9.9	0	45.33	45.29		0.00	50.41	50.36
3/9-3/10	1708	15.3	13.9	10.0	0	46.00	45.63		0.00	78.57	77.93
3/10-3/11	1435	15.4	13.8	10.0	0	45.70	45.05		0.00	65.58	64.64
Weighted Averages		15.4	13.9	10.0	0	45.72	45.35	b			
								TOTALS:	0.00	194.56	192.93
3/11-3/12	180	8.6	7.1	7.0	0	483.67	508.44	a	0.00	87.06	91.52
3/12-3/12	307	8.9	7.1	7.0	0	213.52	213.19	a	0.00	65.55	65.45
3/15-3/15	371	8.6	7.1	7.0	0	235.71	237.22	a	0.00	87.45	88.01
3/16-3/16	440	9.0	7.2	7.0	0	184.39	185.34	a	0.00	81.13	81.55
3/18	450	8.6	7.2	7.0	0	163.20	163.53	a	0.00	73.44	73.59
3/19	312	8.7	7.2	7.0	0	129.10	128.69	a	0.00	40.28	40.15
3/21	279	9.1	7.3	7.0	0	119.53	119.53	a	0.00	33.35	33.35
3/22	314	9.2	7.3	7.0	0	116.50	116.31	a	0.00	36.58	36.52
3/23	209	9.1	7.3	7.0	0	114.64	113.64	a	0.00	23.96	23.75
3/24	418	9.1	7.3	6.9	0	121.58	120.96	a	0.00	50.82	50.56
3/25	172	8.6	7.2	7.0	0	125.47	125.47	a	0.00	21.58	21.58

Table A.8 Test Results for Sample CCR-D-100--Continued

Date	Elapsed Time (min)	Axial Stress (MPa)	Confining Stress (MPa)	Top Pressure (MPa)	Bottom Pressure (MPa)	Flow Rate In ($\times 10^{-3}$ cc/min)	Flow Rate Out ($\times 10^{-3}$ cc/min)	Notes	V _A (cc)	V _I (cc)	V _O (gm)
3/26	238	8.6	7.1	7.0	0	132.94	133.32	a	0.00	31.64	31.73
3/26	296	8.6	7.1	7.0	0	135.17	135.00	a	0.00	40.01	39.96
3/28	265	8.6	7.1	7.0	0	93.36	93.66	a	0.00	24.74	24.82
3/28-3/29	905	8.6	7.1	7.0	0	99.14	99.16		0.00	89.72	89.74
3/29	369	8.6	7.1	7.0	0	103.20	103.09		0.00	38.08	38.04
3/29-3/30	902	8.6	7.1	7.0	0	106.08	107.13		0.00	95.68	96.63
Weighted Averages:		8.6	7.1	7.0	0	102.71	103.13	b			
								TOTALS:	0.00	921.07	926.95
3/30-3/31	1208	8.6	7.1	3.5	0	35.14	32.60	a	0.16	42.45	39.38
3/31-4/1	1364	8.5	7.1	3.5	0	31.32	28.07		0.13	42.72	38.29
4/1-4/2	1371	8.6	6.7	3.5	0	31.60	28.88	a	1.46	43.33	39.59
4/2-4/3	1377	8.6	7.1	3.5	0	29.85	26.80		0.31	41.11	36.91
4/3-4/4	1381	8.6	7.1	3.5	0	29.17	25.43		0.23	40.29	35.12
Weighted Averages:		8.6	7.1	3.5	0	30.11	26.76	b			
								TOTALS:	2.29	209.90	189.29
4/4-4/5	1687	8.7	7.0	1.6	0	11.98	8.16		0.60	20.21	13.77
4/5-4/6	1023	8.7	7.1	1.6	0	11.26	8.36		NR	11.52	8.55
4/6-4/7	867	8.7	7.2	1.6	0	11.07	8.35		0.00	9.60	7.24
4/7-4/8	1426	8.7	7.1	1.6	0	10.67	7.73		0.18	15.21	11.03
Weighted Averages:		8.7	7.1	1.6	0	11.30	8.11	b			
								TOTALS:	0.78	56.54	40.59

NOTES:

- a) Not included in weighted average.
b) Averages weighted with respect to time.
c) Bottom valve closed.

NR) not recorded

Table A.9 Test Results for Sample CG-104

Date	Elapsed Time (min)	Axial Stress (MPa)	Confining Stress (MPa)	Top Pressure (MPa)	Bottom Pressure (MPa)	Flow Rate In ($\times 10^{-3}$ cc/min)	Flow Rate Out ($\times 10^{-3}$ cc/min)	Notes	V _A (cc)	V _I (cc)	V _O (gm)
6/17	378	8.6	6.9	3.3	0	15.63	2.03	a	0.00	5.91	0.77
6/17-6/18	1259	8.6	6.9	3.2	0	10.64	10.29		0.00	13.40	12.96
6/18-6/19	1241	8.6	6.9	3.5	0	11.91	12.04		0.00	14.78	14.94
6/19-6/20	1381	8.6	7.0	3.5	0	12.18	12.12+	a,c	0.00	16.82	16.74
6/20-6/21	1947	8.6	7.0	3.5	0	12.18	12.52		0.00	23.72	24.37
Weighted Averages:		8.6	6.9	3.4	0	11.67	11.75	b			
								Totals:	0	74.63	69.78
6/21-6/22	1486	8.6	7.0	1.7	0	3.62	3.91		0.16	5.38	5.81
6/22-6/23	1261	8.6	6.9	1.5	0	3.70	3.63		0.28	4.66	4.58
6/23-6/24	1575	8.6	6.9	1.6	0	4.65	4.64		NR	7.32	7.31
Weighted Averages:		8.6	6.9	1.6	0	4.02	4.09	b			
								Totals:	0.44	17.36	17.70
6/24-6/25	1320	15.4	13.4	3.3	0	4.48	5.10	a	0.85	5.92	6.73
6/25-6/29	5392	14.4	12.3	3.6	0	6.05	4.40	a	3.19	32.60	23.70
6/29-6/30	1669	16.7	13.1	3.2	0	4.12	4.60	a	NR	6.88	7.67
6/30-7/1	1534	15.2	13.2	3.5	0	4.84	5.08		1.64	7.43	7.79
7/1-7/3	2514	15.3	13.8	3.4	0	4.85	5.03		0.00	12.20	12.65
Weighted Averages:		15.3	13.6	3.4	0	4.85	5.05	b			
								Totals:	5.68	65.03	58.54
7/3-7/4	1153	15.4	13.8	7.0	0	10.89	11.69		0.00	12.56	13.48
7/4-7/5	1414	15.4	13.8	7.0	0	11.07	11.65		0.00	15.65	16.48
7/5-7/6	No data. Programming computer.										
7/6-7/7	1149	15.4	13.4	7.0	0	11.27	11.60		0.92	12.95	13.33
Weighted Averages:		15.4	13.7	7.0	0	11.08	11.65	b			
								Totals:	0.92	41.16	43.29

Table A.9 Test Results for Sample CG-104--Continued

Date	Elapsed Time (min)	Axial Stress (MPa)	Confining Stress (MPa)	Top Pressure (MPa)	Bottom Pressure (MPa)	Flow Rate In ($\times 10^{-3}$ cc/min)	Flow Rate Out ($\times 10^{-3}$ cc/min)	Notes	V _A (cc)	V _I (cc)	V _O (gm)
7/7-7/8	1280	15.5	13.8	9.9	0	18.43	18.98		0.00	23.59	24.29
7/8	425	15.6	13.7	10.0	0	18.87	28.19	a	0.30	8.02	11.98
7/8-7/9	1183	15.6	13.4	10.1	0	19.68	20.18		0.78	23.28	23.87
7/9-7/10	1105	15.6	13.8	10.2	0	19.89	20.39		0.00	21.99	22.54
7/10-7/11	1566	<u>15.6</u>	<u>14.1</u>	<u>10.1</u>	<u>0</u>	<u>19.46</u>	<u>19.86</u>		<u>0.00</u>	<u>30.48</u>	<u>31.10</u>
Weighted Averages:		15.6	13.8	10.1	0	19.35	19.83	b			
								Totals:	1.08	107.36	113.78
7/11-7/12	1100	22.6	19.1	7.2	0	8.76	10.34	a,d	1.20	9.63	11.37
7/12	268	23.2	19.6	10.0	0	8.90	8.47		0.19	2.38	2.27
7/12-7/13	1460	23.1	19.6	10.1	0	8.66	8.94		0.16	12.65	13.05
7/13-7/14	1295	23.0	19.6	10.1	0	7.75	8.02		0.14	10.03	10.39
7/14-7/15	1409	<u>23.0</u>	<u>19.6</u>	<u>10.0</u>	<u>0</u>	<u>8.76</u>	<u>8.96</u>		<u>0.07</u>	<u>12.35</u>	<u>12.62</u>
Weighted Averages:		23.0	19.6	10.1	0	8.44	8.65	b			
								Totals:	1.76	47.04	49.70
7/15-7/16	1028	22.9	19.6	7.1	0	5.72	5.68	a	0.08	5.88	5.84
7/16-7/19	Programming computer.			No data.							
7/19-7/20	1353	23.0	19.8	7.0	0	4.63	4.72		0.00	6.27	6.38
7/20-7/21	1535	23.0	19.5	7.0	0	4.66	4.78		0.46	7.16	7.34
7/21-7/22	1420	<u>23.0</u>	<u>19.8</u>	<u>7.0</u>	<u>0</u>	<u>4.69</u>	<u>4.73</u>		<u>0.12</u>	<u>6.66</u>	<u>6.72</u>
Weighted Averages:		23.0	19.7	7.0	0	4.66	4.74	b			
								Totals:	0.66	25.97	26.28
7/22-7/23	858	22.9	19.6	3.6	0	2.06	2.23		0.25	1.77	1.91
7/23-7/24	Testing interrupted for gauge calibration.										
7/24-7/26	3446	22.9	19.6	3.4	0	1.92	2.00		0.36	6.61	6.89
7/26-7/27	1070	22.9	19.7	3.4	0	1.86	2.06		0.00	1.99	2.20
7/27-7/28	1148	<u>22.9</u>	<u>19.6</u>	<u>3.4</u>	<u>0</u>	<u>1.92</u>	<u>1.93</u>		<u>0.22</u>	<u>2.20</u>	<u>2.22</u>
Weighted Averages:		22.9	19.6	3.4	0	1.93	2.03	b			
								Totals:	0.83	12.57	13.22

Table A.9 Test Results for Sample CG-104--Continued

Date	Elapsed Time (min)	Axial Stress (MPa)	Confining Stress (MPa)	Top Pres-sure (MPa)	Bottom Pres-sure (MPa)	Flow Rate In ($\times 10^{-3}$ cc/min)	Flow Rate Out ($\times 10^{-3}$ cc/min)	Notes	V_A (cc)	V_I (cc)	V_O (gm)
Total for rock bridge:									11.37	391.12	392.29
7/28-8/19	Perform pulse tests.										
8/20	Drill out rock bridge. Place bentonite tablets and cure.										
8/22	Put $P_T = 2$ MPa. Clay plug will not hold. Lower pressure to zero and let plug heal, swell more.										
8/23-9/1	$P_T = 0.1-0.3$ MPa on clay plug. No data due to equipment problems. Some piping of clay plug.										
9/1-9/2	1545	21.1	~18.4	~0.8	0	1.65	2.82	a	3.18	2.55	4.36
9/2-9/3	Ran out of N_2 driving pump.										
9/3-9/4	1746	21.0	18.1	~0.9	0	1.00	2.14		2.13	0.00	3.17
9/4-9/6	2929	20.9	17.1	~1.1	0	0.65	2.68		3.45	1.74	3.74
9/6-9/7	1223	23.0	18.6	1.0	0	0.31	2.19		4.90	1.89	7.85
9/7-9/8	1782	22.7	18.2	1.0	0	0.00	1.95		3.10	0.38	2.68
9/8-9/9	1420	22.7	18.4	0.9	0	0.03	1.70		4.09	0.00	3.48
9/9-9/11	2855	22.6	17.3	1.1	0	0.00	1.49		2.97	0.04	2.41
9/11-9/14	4372	22.1	15.4	2.1	0	0.03	1.66	a	6.18	0.00	4.26
Weighted Averages:		22.0	17.8	1.0	0	0.34	2.04	b	10.22	0.15	7.25
Totals:									40.22	6.75	39.20
9/14-9/15	Annulus leaking badly. Lower σ_c to 13.8 MPa and set $P_T = 3.5$ MPa.										
9/15	140	21.0	13.8	3.5	0	1.71	1.50		0.00	0.24	0.21
9/15-9/16	1289	21.0	13.1	3.5	0	NR	1.08	a,d	NR	NR	1.39
9/16-9/18	2644	20.9	12.3	3.8	0	0.07	1.26		3.12	0.19	3.33
Weighted Averages:		20.9	12.4	3.8	0	0.15	1.27	b			
Totals:									3.12	0.43	4.93
Totals for clay plug:									43.34	7.18	44.13

Table A.9 Test Results for Sample CG-104--Continued

Date	Elapsed Time (min)	Axial Stress (MPa)	Confining Stress (MPa)	Top Pres-sure (MPa)	Bottom Pres-sure (MPa)	Flow Rate In ($\times 10^{-3}$ cc/min)	Flow Rate Out ($\times 10^{-3}$ cc/min)	Notes	V _A (cc)	V _I (cc)	V _O (gm)
9/18	Leakage from annulus raised P _T . Plug failed at P _T ~4.2 MPa.										
9/20	Allowed plug to heal two days. Failure now occurred between 2.0 and 2.5 MPa.										
9/21-10/23	Sample removed from permeameter. Permeameter down for servicing. Replaced sample in permeameter on 10/12 and placed new bentonite plug. Let bentonite plug swell 11 days.										
10/23-10/25	2486	22.2	14.4	0.7	0	2.83	2.35	a	5.73	7.03	5.85
10/25-10/26	1609	22.2	19.3	1.2	0	2.25	2.01	a	1.05	3.62	3.24
10/26-10/27	1333	22.4	19.5	1.5	0	1.95	2.09		0.00	2.60	2.78
10/27-10/28	1354	22.4	19.2	1.4	0	1.72	1.91		NR	2.33	2.59
10/28-10/29	1407	22.4	18.9	1.4	0	1.33	1.65		NR	1.87	2.32
10/29-11/1	3895	22.3	18.2	1.5	0	1.54	1.62		0.00	6.01	6.32
11/1-11/2	1437	22.3	17.7	1.5	0	1.43	1.56		0.00	2.06	2.25
11/2-11/3	1412	22.2	17.4	1.5	0	1.42	1.57		0.00	2.00	2.21
11/3-11/5	2842	22.2	17.0	1.5	0	1.44	1.54		0.00	4.08	4.39
11/5-11/6	Computer down. No data. Flow continued.										
11/6-11/8	2582	22.9	19.5	1.5	0	1.10	1.37		1.06	2.84	2.53
11/8-11/10	3231	22.9	19.5	1.4	0	1.18	1.30		0.94	3.81	4.19
Weighted Averages:		22.5	18.5	1.5	0	1.42	1.57	b			
								Totals:	2.00	27.60	30.58
11/10-11/12	2710	23.0	19.8	2.0	0	2.09	1.90		0.28	5.66	5.15
11/12-11/13	1392	23.0	19.6	2.0	0	1.76	1.82		0.00	2.45	2.53
Weighted Averages:		23.0	19.7	2.0	0	1.98	1.87	b			
								Totals:	0.28	8.11	7.68
11/13-12/8	Bentonite plug failed. Sample removed from permeameter, cleaned, re-epoxied. New plug placed 12/5/83.										
12/8-12/10	2715	23.4	19.6	0.5	0	1.48	1.39	a	1.00	4.03	3.78
12/10-12/13	Computer down. No data. Flow continued.										
12/13-12/14	1521	21.2	17.4	1.2	0	1.23	3.96	a	0.00	1.87	6.02

Table A.9 Test Results for Sample CG-104--Continued

Date	Elapsed Time (min)	Axial Stress (MPa)	Confining Stress (MPa)	Top Pressure (MPa)	Bottom Pressure (MPa)	Flow Rate In ($\times 10^{-3}$ cc/min)	Flow Rate Out ($\times 10^{-3}$ cc/min)	Notes	V_A (cc)	V_I (cc)	V_O (gm)
12/14-12/15	1321	21.1	14.7	1.1	0	1.51	1.59		0.00	1.99	2.10
12/15-12/16	1601	21.0	14.4	1.2	0	1.44	1.57		0.00	2.30	2.52
12/16-12/20	5770	21.0	13.9	1.2	0	1.37	1.48		1.13	7.93	8.55
12/20-12/22	2839	<u>21.0</u>	<u>14.2</u>	<u>1.2</u>	<u>0</u>	<u>1.39</u>	<u>1.48</u>		<u>0.61</u>	<u>3.96</u>	<u>4.19</u>
Weighted Averages:		21.0	14.1	1.2	0	1.40	1.51	b			
								Totals:	1.74	16.18	17.36
12/22-12/23	1326	21.0	14.4	1.9	0	2.62	2.59		0.23	3.47	3.44
12/23-12/24	Computer down.		No data.	Flow continued.							
12/24-12/27	4084	21.0	14.1	1.9	0	2.14	2.16		0.76	8.75	8.83
12/27-12/30	4239	21.0	14.3	2.0	0	2.12	2.09		0.52	8.99	8.87
12/30-1/4	7422	21.0	14.0	2.0	0	1.59	0.91	a,e	1.00	11.81	6.78
1/4-i/8	5333	<u>21.0</u>	<u>14.2</u>	<u>2.1</u>	<u>0</u>	<u>0.03</u>	<u>0.11</u>	<u>a,e</u>	<u>0.65</u>	<u>0.15</u>	<u>0.61</u>
Weighted Averages:		21.0	14.2	1.9	0	2.20	2.19	b			
								Totals:	3.16	33.17	28.53
1/8-1/10	Plug failed by piping.										
1/10-1/18	Let plug heal while $P_c = 0$										
1/18-1/19	1125	20.8	12.6	0.4	0	0.55	0.17	a	0.00	0.62	0.21
1/19-1/25	8745	<u>20.8</u>	<u>12.3</u>	<u>0.5</u>	<u>0</u>	<u>0.51</u>	<u>0.55</u>		<u>0.85</u>	<u>4.50</u>	<u>4.77</u>
Weighted Averages:		20.8	12.3	0.5	0	0.51	0.55	b			
								Totals:	0.85	5.12	4.98
1/27-1/29	2836	20.8	12.3	1.0	0	0.87	0.91		0.00	2.46	2.57
1/29-1/30	1573	<u>20.8</u>	<u>12.0</u>	<u>1.0</u>	<u>0</u>	<u>0.90</u>	<u>0.97</u>		<u>0.50</u>	<u>1.42</u>	<u>1.52</u>
Weighted Averages:		20.8	12.2	1.0	0	0.88	0.93	b			
								Totals:	0.50	3.88	4.09

Table A.9 Test Results for Sample CG-104--Continued

Date	Elapsed Time (min)	Axial Stress (MPa)	Confining Stress (MPa)	Top Pressure (MPa)	Bottom Pressure (MPa)	Flow Rate In ($\times 10^{-3}$ cc/min)	Flow Rate Out ($\times 10^{-3}$ cc/min)	Notes	V_A (cc)	V_I (cc)	V_O (gm)
1/30-2/2	4788	12.2	6.1	1.0	0	2.52	2.33	f	0.00	12.06	11.16
2/2-2/3	872	12.3	5.7	1.0	0	2.73	2.81	f	0.00	2.38	2.45
2/3-2/4	1535	12.2	5.7	1.0	0	3.02	3.04	f	0.00	4.64	4.66
Weighted Averages:		12.2	6.0	1.0	0	2.65	2.54	b			
								Totals:	0.00	19.08	18.27
2/4-2/7	Let plug heal while $P_t = 0$.										
2/7-2/9	3018	12.2	5.6	1.0	0	0.55	0.02	a	0.00	1.66	0.07
2/9-2/10	1588	12.2	5.4	1.0	0	0.08	-	a	NR	0.13	-0.10
2/10-2/11	1044	12.2	5.1	1.0	0	0.86	0.73		0.00	0.90	0.76
2/11-2/14	4433	12.4	6.1	1.4	0	0.09	0.15		0.17	0.41	0.66
Weighted Averages:		12.4	5.9	1.3	0	0.24	0.26	b			
								Totals:	0.17	3.10	1.39

NOTES:

- (a) Datum not included in average
- (b) Averages weighted with respect to elapsed time.
- (c) Bottom flask overflowed.
- (d) Pump ran out of water.
- (e) Some piping. Poor mass balance.
- (f) Much piping.

NR = Not recorded

 V_A is volume of water added to annulus. V_I is volume of water pumped into top hole. V_O is volume of water flowing from bottom hole.

REFERENCES

- American Petroleum Institute, 1977, "Specification 10B, Testing Oil-Well Cements and Cement Additives": American Petroleum Institute, Dallas, Texas.
- Anderson, F. M., 1955, "A Study of Surface Casing and Open-Hole Plug-Back Cementing Practices in the Mid-Continent District": Drilling and Production Practice, American Petroleum Institute, pp. 312-325.
- Anderson, W. J., Clayton, L. G., Cottam, A. E., Jacobs, G. K., Scheely, W. W., and Watrous, W. A., 1982, "Nuclear Waste Repository in Basalt Seal Development Studies": DOE/NWTS-30, Proc. of the 1982 National Waste Terminal Storage Information Meeting, U.S. Department of Energy, p. 58.
- Arnold, D. M. and Paap, H. J., 1979, "Quantitative Monitoring of Water Flow Behind and in Wellbore Casing": Transactions of the Society of Petroleum Engineers, v. 267, pp. 121-130.
- Barbreau, A., Heremans, R., and Skytte Jensen, B., 1980, "Radionuclide Migration in Geological Formations": in Radioactive Waste Management and Disposal, R. Simon and S. Orlowski, editors, Proc. of the First European Community Conference, Luxembourg, pp. 515-530.
- Bartlett, John W., and Koplik, Charles M., 1979, "Information Base for Waste Repository Design, Volume 7 - Executive Summary": Report No. NUREG/CR-0495, TR-1210-1, Prepared by The Analytical Sciences Corporation for the Division of Waste Management, Office of Nuclear Material Safety and Safeguards, U.S. Nuclear Regulatory Commission.
- Bates, Robert L., 1969, Geology of the Industrial Rocks and Minerals: Dover Publications, New York, 459 pp.
- Baumeister, Theodore, and Marks, Lionel S. (Eds.), 1967, Standard Handbook for Mechanical Engineers, Seventh Edition: McGraw-Hill Book Company, San Francisco.
- Bernaix, J., 1969, "New Laboratory Methods of Studying the Mechanical Properties of Rocks": Int. J. Rock Mech. Min. Sci., Vol 6, pp. 43-90.

- Bowen, Robert, 1975, Grouting in Engineering Practice: Applied Sciences Publishers, Ltd., London.
- Brace, W. F., 1980, "Permeability of Crystalline and Argillaceous Rocks": Int. J. Rock Mech. Min. Sci. & Geomech. Abstr., Vol 17, No. 5, pp 241-251.
- Brace, W. F., Walsh, J. B., and Frangos, W. T., 1968, "Permeability of Granite Under High Pressure": Journal of Geophysical Research, Vol 73, No. 6, pp. 2225-2236.
- Brunauer, S. and Kantro, D. L., 1964, The Chemistry of Cement: H. F. W. Taylor, editor, Academic Press, London, p. 305.
- Buck, A. D., Burkes, J. Pl, and Rhoderick, J. E., 1981, "Examination of ERDA-10 Grout Specimens at Different Ages": Report No. ONWI-341, Office of Nuclear Waste Isolation, Battelle Memorial Institute, Columbus, Ohio.
- Buck, A. D. and Mather, K., 1982, "Grout Formulations for Nuclear Waste Isolation": Report No. ONWI-413, Office of Nuclear Waste Isolation, Battelle Memorial Institute, Columbus, Ohio.
- Chatterji, S. and Jeffery, J. W., 1971, "The Nature of the Bond Between Different Types of Aggregates and Portland Cement": Indian Concrete Journal, August, 1971, p. 346.
- Christensen, Charles L. and Peterson, Edward W., 1981, "The Bell Canyon Test Summary Report": SAND80-1375, Sandia National Laboratories, Albuquerque, New Mexico.
- Christensen, Charles L., 1980, "Sandia Borehole Plugging Program for the Waste Isolation Pilot Plant: Sandia National Laboratories, Paper presented at the Workshop on Borehole and Shaft Plugging, Columbus, Ohio, May 7-9, 1980, 12 pp. Report No. SAND80-0390C.
- Cobb, Steven Lloyd, 1981, "A Laboratory Facility for Testing the Performance of Borehole Plugs in Rock Subjected to Polyaxial Loading": M.S. Thesis, University of Arizona, Tucson.
- Daemen, Jaak J. K., South, David L., Jeffrey, Robert G., and Klejbuck, Lucien W., 1979, "Rock Mass Sealing, Annual Report, October 1, 1978 - September 30, 1979": Dept. of Mining and Geological Engineering, University of Arizona, Tucson.
- D'Appolonia, 1981, "Draft Report - Geotechnical Services for Repository Sealing, FY Summary Report": Prepared for Battelle

- Memorial Institute, Project Management Division, Office of Nuclear Waste Isolation, Columbus, Ohio.
- D'Appolonia Consulting Engineers, 1980a, "Repository Sealing Design Approach - 1979": Report No. ONWI-55, Office of Nuclear Waste Isolation, Battelle Memorial Institute, Columbus, Ohio.
- D'Appolonia, 1980b, "Repository Sealing: Evaluation of Materials Research Objectives & Requirements - 1980": Battelle Memorial Institute, Office of Nuclear Waste Isolation, Columbus, Ohio. Preprint copy of Report No. ONWI-108.
- D'Appolonia, 1979, "The Status of Borehole Plugging & Shaft Sealing for Geologic Isolation of Radioactive Waste": Report No. ONWI-15, Office of Nuclear Waste Isolation, Battelle Memorial Institute, Columbus, Ohio.
- De Wiest, R. J., 1965, Geohydrology: John Wiley & Sons, New York.
- Eilers L. H., 1974, "Sealing AEC #1 Well, Lyons, Kansas - Final Report: Report No. ORNL/Sub/33542-74/1, Office of Waste Isolation, Oak Ridge National Laboratories, Oak Ridge, Tennessee.
- Eilers, L. H., 1973, "Borehole Sealing Final Report": Report No. ORNL/Sub/15966-73/1, Office of Waste Isolation, Oak Ridge National Laboratories, Oak Ridge, Tennessee.
- EPA, 1980, "Research Summary: Controlling Hazardous Wastes": Report No. EPA-600/8-80-017, U.S. Environmental Protection Agency.
- EPA, 1978, "State of Geological Knowledge Regarding Potential Repositories": Office of Radiation Programs, Environmental Protection Agency, Washington, D. C. Available from National Technical Information Service, Report No. PB-289947.
- Fernandez, R., McGowen, C., Nolan, E., Moray, R., and Palty, A., 1976, "Borehole Plugging by Compaction Process": Charles Stark Draper Laboratory, Inc., Cambridge, Mass.
- Goodwin, Laurel B., 1983, personal communication.
- Greer, William B., 1983, M.S. Thesis, in progress, University of Arizona, Tucson.
- Hunt, Terence, 1983, "Reagan Signs Nuclear Waste Bill": Associated Press, in Arizona Daily Star, January 8, 1983.

- IAEA, 1981, "A Guide to Site Investigations of Repositories for Solid Low- and Intermediate-Level Radioactive Wastes in Rock Cavities": Working Draft for the IAEA Advisory Group Meeting to be Held in Otanleai, Finland, 22-26 June, 1981. International Atomic Energy Agency.
- IAEA, 1980, "Waste Management and Disposal": Report of INFCE Working Group 7, International Nuclear Fuel Cycle Evaluation, Published by the International Atomic Energy Agency, Vienna.
- International Society for Rock Mechanics, 1978, "Suggested Methods for Determining the Uniaxial Compressive Strength and Deformability of Rock Materials": International Journal of Rock Mechanics and Mining Sciences & Geomechanics Abstracts, Vol. 16, pp. 135-140.
- Ishii, Shiro, Hitotsuya, Izume, Yoshito, and Soeda, Koichi, 1982, "Development and Application of Non-explosive Demolition Agent Used Limestone as Main Material": Preprint No. 82-330, First International SME-AME Fall Meeting, Honolulu, Hawaii, September 4-9, 1982.
- Jaeger, J. C., and Cook, N. G. W., 1976, Fundamentals of Rock Mechanics: Halsted Press, John Wiley & Sons, Inc., New York.
- Jeffrey, Robert Graham, 1981, "Shaft or Borehole Plug-Rock Mechanical Interaction": M.S. Thesis, University of Arizona.
- Kelsall, P. C., Case, J. B., Meyer, D., and Coons, W. E., 1982, "Schematic Designs for Repository Seals for a Reference Repository in Bedded Salt": Report No. ONWI-405, Office of Nuclear Waste Isolation, Battelle Memorial Institute, Columbus, Ohio.
- Klinkenberg, L. J., 1941, "The Permeability of Porous Media to Liquids and Gases": Drilling and Production Practice, Presented at 11th Mid-year Meeting, Tulsa.
- Koplik, Charles M., Pentz, David L., and Talbot, Richard, 1979, "Information Base for Waste Repository Design, Volume I - Borehole and Shaft Sealing": Report No. NUREG/CR-0495, TR-1210-1, Division of Waste Management, Office of Nuclear Material Safety and Safeguards, U.S. Nuclear Regulatory Commission, Washington, D.C.
- Lambe, William T., and Whitman, Robert B., 1969, Soil Mechanics: John Wiley & Sons, New York, 553 pp.

- Levine, D. C., Thomas, E. W., and Tolle, G. C., 1980, "How to Prevent Annular Gas Flow Following Cementing Operations": World Oil, p. 85-94.
- Lingle, R., Stanford, K. L., Peterson, P. E., and Woodhead, S. F., 1982, "Wellbore Damage Zone Experimental Determination": Report No. ONWI-349, Office of Nuclear Waste Isolation, Battelle Memorial Institute, Columbus, Ohio.
- Lipman, Peter W., and McKay, Edward J., 1965, "Geologic Map of the Topapah Spring SW Quadrangle, Nye County, Nevada": GQ-439, U.S. Geological Survey.
- Martin, R. Torrence, 1975, "Feasibility of Sealing Boreholes with Compacted Natural Earthen Material: Report No. ORNL/Sub-3960/2, Oak Ridge National Laboratories, Oak Ridge, Tennessee.
- Mather, K., 1964, "Cement-Aggregate Reaction: What is the Problem?": Geol. Soc. Amer., Engineering Geology Case Histories, No. 2.
- Mathis, Stephen Philip, 1982, "Drilling Induced Damage to Borehole Wallrock: A Theoretical, Laboratory, and Field Comparison of the Effects of Diamond and Percussion Drilling": M.S. Thesis, University of Arizona, Tucson.
- McDaniel, Earl W., 1980, "Cement Technology for Borehole Plugging: An Interim Report on Permeability of Cementitious Solids": Report No. ORNL/TM-7092, Oak Ridge National Laboratories, Oak Ridge, Tennessee.
- Moore, J. G., Morgan, M. T., McDaniel, E. W., Greene, H. B., and West, G. A., 1979, "Cement Technology for Plugging Boreholes in Radioactive Waste Repository Sites: Progress Report for the Period October 1, 1977, to September 30, 1978": ORNL-5524, Oak Ridge National Laboratory, Oak Ridge, Tennessee.
- Neville, A. M., 1973, Properties of Concrete: John Wiley & Sons, New York.
- Neuman, Shlomo P., 1976, "User's Guide for FRESURF I": Department of Hydrology and Water Resources, University of Arizona, Tucson.
- Neuman, Shlomo P. and Witherspoon, P. A., 1970, "Finite Element Method of Analyzing Steady Seepage with a Free Surface": Water Resources Research, Vol. 6, No. 3, pp. 889-897.
- Nuclear Regulatory Commission, 1981, "Disposal of High-Level Radioactive Wastes in Geologic Repositories, Proposed Rule":

- 10CFR60, Federal Register, Vol. 48, No. 130, Wednesday, July 8, 1981, p. 35294.
- ONWI-39, 1979, "An Assessment of LWR Spent Fuel Disposal Options, Volume 3, Study Bases and System Design Considerations (Appendices)": Office of Nuclear Waste Isolation, Battelle National Laboratories.
- ONWI-78, 1981, "Tabulation of Waste Isolation Computer Models": Office of Nuclear Waste Isolation, Battelle Project Management Division, Columbus, Ohio.
- Paterson, Mervyn S., 1978, Experimental Rock Deformation - The Brittle Field: Springer-Verlag, New York, p. 80.
- Piper, Arthur M., 1969, "Disposal of Liquid Wastes by Injection Underground - Neither Myth nor Millenium": U.S. Geological Survey Circular 631, 15 pp.
- Powers, T. C., 1958, "Structure and Physical Properties of Hardened Portland Cement Paste": Journal of the American Ceramic Society, Vol. 41, No. 1, January, 1958, pp. 38-48.
- Pugh, T. D., 1967, "What to Consider When Cementing Deep Wells": World Oil, September, 1967, p. 52.
- Rennick, G. E., Pasini, J., III, Armstrong, F. E., and Abrams, J. R., 1972, "Demonstration of Safety Plugging of Oil Wells Penetrating Appalachian Coal Mines": U.S. Bureau of Mines Technical Progress Report, July, 1972.
- Rhoderick, J. E., and Buck, A. D., 1981, "Petrographic Examination of Several Four-Year-Old Laboratory Developed Grout Mixtures": Report No. ONWI-342, Office of Nuclear Waste Isolation, Battelle Memorial Institute, Columbus, Ohio.
- Roark, Raymond J., and Young, Warren C., 1975, Formulas for Stress and Strain, Fifth Edition: McGraw-Hill Book Company, San Francisco.
- Rockwell International, 1979, "Geologic Studies of the Columbia Plateau, A Status Report": Basalt Waste Isolation Project, Geosciences Group, Rockwell Hanford Operations, Energy Systems Group, Richland, WA, Report No. RHO-BWI-ST-4.
- Roy, D. M., and Langton, C. A., 1982, "Longevity of Borehole and Shaft Sealing Materials: Characterization of Cement-Based Ancient Building Materials": Report No. ONWI-202, prepared by The Pennsylvania State University for Office of Nuclear Waste Isolation, Battelle Memorial Institute, Columbus, Ohio.

- Roy, D. M. and Grutzeck, M. W., 1980, "PSU/WES Interlaboratory Comparative Methodology Study of an Experimental Cementitious Repository Seal Material": Report No. ONWI-198, Office of Nuclear Waste Isolation, Battelle Memorial Institute, Columbus, Ohio.
- Roy, D. M., Brindley, G. W., Biggers, J. V., McCarthy, G. J., McKinstry, H. A., Voight, B., White, W. B., Scheetz, B. E., Komarneni, S., and Perison, J., 1977, "Borehole Cement and Rock Properties Studies": Report No. Y/OWI/Sub-4091/6, Office of Waste Isolation, Oak Ridge National Laboratory, Oak Ridge, Tennessee. Prepared by Materials Research Laboratory, The Pennsylvania State University, University Park, PA 16802.
- Schneider, K. J., and Platt, A. M., 1974, "Advanced Waste Management Studies, High-Level Radioactive Waste Disposal Alternatives": BNWL-1900, Battelle Pacific Northwest Laboratory, Richland, Washington.
- Scully, L. W. and Rothman, A. J., 1982, "Repository and Engineering Barriers Design": DOE/NWTS-30, Proc. of the 1982 National Waste Terminal Storage Information Meeting, U.S. Department of Energy, p. 15.
- Smith, Dwight K., 1976, Cementing: Society of Petroleum Engineers of AIME, 184 pp.
- South, David L., Greer, William B., Colburn, Nora I., Kousari, Behrooz, Jeffrey, Robert G., Wakely, Carolyn A., and Daemen, Jaak J. K., 1982, "Nuclear Waste Management Research, Annual Report, Rock Mass Sealing June 1, 1981 - May 31, 1982": Prepared for U.S. Nuclear Regulatory Commission, SAFER Division, by Department of Mining and Geological Engineering, University of Arizona.
- South, David L., 1980, "Borehole Sealing with Clay/Considerations in Clay Mineral Stability": Topical Report prepared for U. S. Nuclear Regulatory Commission by Department of Mining and Geological Engineering, University of Arizona, Tucson.
- South, David L., 1979, "Well Cementing": Topical Report prepared for SAFER Division, U. S. Nuclear Regulatory Commission by Department of Mining and Geological Engineering, University of Arizona, Tucson.
- Sowers, George B. and Sowers, George F., 1970, Introductory Soil Mechanics and Foundations: MacMillan Publishing Co., Inc., New York.

- Spengler, Rick, 1982, personal communication.
- Spotts, M. F., 1971, Design of Machine Elements: Prentice-Hall, Englewood Cliffs, New Jersey.
- Stormont, John C., 1983, "Mechanical Strength of Borehole Plugs": M.S. Thesis, University of Arizona.
- Sultan, Hassan A., 1979, "Chemical Grouting for Rock Mass Sealing": Topical Report prepared for SAFER Division, U.S. Nuclear Regulatory Commission, by the Department of Mining and Geological Engineering, University of Arizona, Tucson.
- Taylor, C. L., O'Rourke, J. E., Alliot, D., and O'Connor, K., 1980, "Preconceptual Systems and Equipment for Plugging of Man-Made Accesses to a Repository in Basalt": RHO-BWI-C-67, Rockwell International, Rockwell Hanford Operations, Energy Systems Group, Richland, WA 99352.
- Taylor, C. L., Anttonen, G. J., O'Rourke, J. E., and Niccum, M. R., 1979, "Borehole Plugging of Man-Made Accesses to a Basalt Repository: A Preliminary Study": RHO-BWI-C-49, Rockwell Hanford Operations, Richland, Washington.
- Timoshenko, S., 1976, Strength of Materials, Part II: Advanced Theory and Problems: Robert E. Krieger Publishing Company, Huntington, New York, 572 pp.
- Wakeley, L. D., Roy, D. M., and Grutzeck, M. W., 1981, "Experimental Studies of Seal Materials for Potential Use in a Los Medanos-Type Bedded Salt Repository": Report No. ONWI-325, Office of Nuclear Waste Isolation, Battelle Memorial Institute, Columbus, Ohio.